

# [MS-WMF]: Windows Metafile Format

---

## Intellectual Property Rights Notice for Open Specifications Documentation

- **Technical Documentation.** Microsoft publishes Open Specifications documentation for protocols, file formats, languages, standards as well as overviews of the interaction among each of these technologies.
- **Copyrights.** This documentation is covered by Microsoft copyrights. Regardless of any other terms that are contained in the terms of use for the Microsoft website that hosts this documentation, you may make copies of it in order to develop implementations of the technologies described in the Open Specifications and may distribute portions of it in your implementations using these technologies or your documentation as necessary to properly document the implementation. You may also distribute in your implementation, with or without modification, any schema, IDL's, or code samples that are included in the documentation. This permission also applies to any documents that are referenced in the Open Specifications.
- **No Trade Secrets.** Microsoft does not claim any trade secret rights in this documentation.
- **Patents.** Microsoft has patents that may cover your implementations of the technologies described in the Open Specifications. Neither this notice nor Microsoft's delivery of the documentation grants any licenses under those or any other Microsoft patents. However, a given Open Specification may be covered by Microsoft [Open Specification Promise](#) or the [Community Promise](#). If you would prefer a written license, or if the technologies described in the Open Specifications are not covered by the Open Specifications Promise or Community Promise, as applicable, patent licenses are available by contacting [iplg@microsoft.com](mailto:iplg@microsoft.com).
- **Trademarks.** The names of companies and products contained in this documentation may be covered by trademarks or similar intellectual property rights. This notice does not grant any licenses under those rights.
- **Fictitious Names.** The example companies, organizations, products, domain names, e-mail addresses, logos, people, places, and events depicted in this documentation are fictitious. No association with any real company, organization, product, domain name, email address, logo, person, place, or event is intended or should be inferred.

**Reservation of Rights.** All other rights are reserved, and this notice does not grant any rights other than specifically described above, whether by implication, estoppel, or otherwise.

**Tools.** The Open Specifications do not require the use of Microsoft programming tools or programming environments in order for you to develop an implementation. If you have access to Microsoft programming tools and environments you are free to take advantage of them. Certain Open Specifications are intended for use in conjunction with publicly available standard specifications and network programming art, and assumes that the reader either is familiar with the aforementioned material or has immediate access to it.

## Revision Summary

| Date       | Revision History | Revision Class | Comments   |
|------------|------------------|----------------|--|
| 02/22/2007 | 0.01             |                | MCPD Milestone 3 Initial Availability                            |
| 06/01/2007 | 1.0              | Major          | Updated and revised the technical content.                       |
| 07/03/2007 | 1.1              | Minor          | Restructured for better usability, technical corrections.        |
| 07/20/2007 | 1.2              | Minor          | Updated the technical content.                                   |
| 08/10/2007 | 1.3              | Minor          | Updated the technical content.                                   |
| 09/28/2007 | 1.3.1            | Editorial      | Revised and edited the technical content.                        |
| 10/23/2007 | 1.4              | Minor          | Updated artwork.   |
| 11/30/2007 | 1.5              | Minor          | Standardized artwork.  |
| 01/25/2008 | 1.5.1            | Editorial      | Revised and edited the technical content.                        |
| 03/14/2008 | 2.0              | Major          | Abstract data model and Windows version-specific behavior added. |
| 05/16/2008 | 2.0.1            | Editorial      | Revised and edited the technical content.                        |
| 06/20/2008 | 3.0              | Major          | Updated and revised the technical content.                       |
| 07/25/2008 | 3.0.1            | Editorial      | Revised and edited the technical content.                        |
| 08/29/2008 | 3.0.2            | Editorial      | Revised and edited the technical content.                        |
| 10/24/2008 | 4.0              | Major          | Glossary updated; PitchAndFamily object added.                   |
| 12/05/2008 | 4.1              | Minor          | Updated the technical content.                                   |
| 01/16/2009 | 5.0              | Major          | Updated and revised the technical content.                       |
| 02/27/2009 | 5.1              | Minor          | Updated the technical content.                                   |
| 04/10/2009 | 6.0              | Major          | Updated and revised the technical content.                       |
| 05/22/2009 | 7.0              | Major          | Updated and revised the technical content.                       |
| 07/02/2009 | 7.0.1            | Editorial      | Revised and edited the technical content.                        |
| 08/14/2009 | 7.0.2            | Editorial      | Revised and edited the technical content.                        |
| 09/25/2009 | 7.1              | Minor          | Updated the technical content.                                   |
| 11/06/2009 | 8.0              | Major          | Updated and revised the technical content.                       |
| 12/18/2009 | 8.1              | Minor          | Updated the technical content.                                   |
| 01/29/2010 | 8.1.1            | Editorial      | Revised and edited the technical content.                        |

| Date       | Revision History | Revision Class | Comments   |
|------------|------------------|----------------|--|
| 03/12/2010 | 8.2              | Minor          | Updated the technical content.   |
| 04/23/2010 | 8.2.1            | Editorial      | Revised and edited the technical content.                                    |
| 06/04/2010 | 8.3              | Minor          | Updated the technical content.   |
| 07/16/2010 | 8.4              | Minor          | Clarified the meaning of the technical content.                              |
| 08/27/2010 | 8.5              | Minor          | Clarified the meaning of the technical content.                              |
| 10/08/2010 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 11/19/2010 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 01/07/2011 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 02/11/2011 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 03/25/2011 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 05/06/2011 | 8.5              | No change      | No changes to the meaning, language, or formatting of the technical content. |
| 06/17/2011 | 9.0              | Major          | Significantly changed the technical content.                                 |

# Contents

|          |  |           |
|----------|--|-----------|
| <b>1</b> | <b>Introduction .....</b>                            | <b>9</b>  |
| 1.1      | Glossary .....                                       | 9         |
| 1.2      | References.....                                      | 15        |
| 1.2.1    | Normative References.....                            | 15        |
| 1.2.2    | Informative References .....                         | 15        |
| 1.3      | Overview .....                                       | 16        |
| 1.3.1    | Metafile Structure.....                              | 16        |
| 1.3.2    | Graphics Objects .....                               | 17        |
| 1.3.3    | Byte Ordering .....                                  | 17        |
| 1.4      | Relationship to Protocols and Other Structures ..... | 18        |
| 1.5      | Applicability Statement.....                         | 18        |
| 1.6      | Versioning and Localization .....                    | 18        |
| 1.7      | Vendor-Extensible Fields.....                        | 18        |
| <b>2</b> | <b>Structures .....</b>                              | <b>19</b> |
| 2.1      | WMF Constants .....                                  | 19        |
| 2.1.1    | WMF Enumerations.....                                | 19        |
| 2.1.1.1  | RecordType Enumeration .....                         | 19        |
| 2.1.1.2  | BinaryRasterOperation Enumeration.....               | 24        |
| 2.1.1.3  | BitCount Enumeration .....                           | 28        |
| 2.1.1.4  | BrushStyle Enumeration .....                         | 29        |
| 2.1.1.5  | CharacterSet Enumeration .....                       | 30        |
| 2.1.1.6  | ColorUsage Enumeration .....                         | 31        |
| 2.1.1.7  | Compression Enumeration .....                        | 32        |
| 2.1.1.8  | FamilyFont Enumeration .....                         | 33        |
| 2.1.1.9  | FloodFill Enumeration.....                           | 33        |
| 2.1.1.10 | FontQuality Enumeration .....                        | 34        |
| 2.1.1.11 | GamutMappingIntent Enumeration.....                  | 34        |
| 2.1.1.12 | HatchStyle Enumeration .....                         | 35        |
| 2.1.1.13 | Layout Enumeration .....                             | 36        |
| 2.1.1.14 | LogicalColorSpace Enumeration .....                  | 36        |
| 2.1.1.15 | LogicalColorSpaceV5 Enumeration .....                | 36        |
| 2.1.1.16 | MapMode Enumeration .....                            | 37        |
| 2.1.1.17 | MetafileEscapes Enumeration .....                    | 38        |
| 2.1.1.18 | MetafileType Enumeration.....                        | 41        |
| 2.1.1.19 | MetafileVersion Enumeration .....                    | 42        |
| 2.1.1.20 | MixMode Enumeration .....                            | 42        |
| 2.1.1.21 | OutPrecision Enumeration .....                       | 42        |
| 2.1.1.22 | PaletteEntryFlag Enumeration.....                    | 43        |
| 2.1.1.23 | PenStyle Enumeration .....                           | 44        |
| 2.1.1.24 | PitchFont Enumeration.....                           | 45        |
| 2.1.1.25 | PolyFillMode Enumeration .....                       | 45        |
| 2.1.1.26 | PostScriptCap Enumeration .....                      | 46        |
| 2.1.1.27 | PostScriptClipping Enumeration .....                 | 46        |
| 2.1.1.28 | PostScriptFeatureSetting Enumeration.....            | 46        |
| 2.1.1.29 | PostScriptJoin Enumeration .....                     | 47        |
| 2.1.1.30 | StretchMode Enumeration .....                        | 48        |
| 2.1.1.31 | TernaryRasterOperation Enumeration .....             | 48        |
| 2.1.2    | WMF Flags.....                                       | 80        |
| 2.1.2.1  | ClipPrecision Flags .....                            | 80        |

|           |                                       |     |
|-----------|---------------------------------------|-----|
| 2.1.2.2   | ExtTextOutOptions Flags .....         | 80  |
| 2.1.2.3   | TextAlignmentMode Flags .....         | 81  |
| 2.1.2.4   | VerticalTextAlignmentMode Flags ..... | 82  |
| 2.2       | WMF Objects .....                     | 82  |
| 2.2.1     | Graphics Objects .....                | 83  |
| 2.2.1.1   | Brush Object .....                    | 83  |
| 2.2.1.2   | Font Object .....                     | 84  |
| 2.2.1.3   | Palette Object .....                  | 86  |
| 2.2.1.4   | Pen Object .....                      | 87  |
| 2.2.1.5   | Region Object .....                   | 87  |
| 2.2.2     | Structure Objects .....               | 88  |
| 2.2.2.1   | Bitmap16 Object .....                 | 88  |
| 2.2.2.2   | BitmapCoreHeader Object .....         | 89  |
| 2.2.2.3   | BitmapInfoHeader Object .....         | 90  |
| 2.2.2.4   | BitmapV4Header Object .....           | 91  |
| 2.2.2.5   | BitmapV5Header Object .....           | 94  |
| 2.2.2.6   | CIEXYZ Object .....                   | 95  |
| 2.2.2.7   | CIEXYZTriple Object .....             | 95  |
| 2.2.2.8   | ColorRef Object .....                 | 96  |
| 2.2.2.9   | DeviceIndependentBitmap Object .....  | 96  |
| 2.2.2.10  | LogBrush Object .....                 | 97  |
| 2.2.2.11  | LogColorSpace Object .....            | 98  |
| 2.2.2.12  | LogColorSpaceW Object .....           | 100 |
| 2.2.2.13  | PaletteEntry Object .....             | 102 |
| 2.2.2.14  | PitchAndFamily Object .....           | 102 |
| 2.2.2.15  | PointL Object .....                   | 103 |
| 2.2.2.16  | PointS Object .....                   | 103 |
| 2.2.2.17  | PolyPolygon Object .....              | 103 |
| 2.2.2.18  | Rect Object .....                     | 104 |
| 2.2.2.19  | RectL Object .....                    | 104 |
| 2.2.2.20  | RGBQuad Object .....                  | 105 |
| 2.2.2.21  | Scan Object .....                     | 105 |
| 2.2.2.22  | SizeL Object .....                    | 106 |
| 2.3       | WMF Records .....                     | 106 |
| 2.3.1     | Bitmap Record Types .....             | 107 |
| 2.3.1.1   | META_BITBLT Record .....              | 108 |
| 2.3.1.1.1 | With Bitmap .....                     | 109 |
| 2.3.1.1.2 | Without Bitmap .....                  | 109 |
| 2.3.1.2   | META_DIBBITBLT Record .....           | 110 |
| 2.3.1.2.1 | With Bitmap .....                     | 111 |
| 2.3.1.2.2 | Without Bitmap .....                  | 112 |
| 2.3.1.3   | META_DIBSTRETCHBLT Record .....       | 112 |
| 2.3.1.3.1 | With Bitmap .....                     | 113 |
| 2.3.1.3.2 | Without Bitmap .....                  | 114 |
| 2.3.1.4   | META_SETDIBTODEV Record .....         | 115 |
| 2.3.1.5   | META_STRETCHBLT Record .....          | 116 |
| 2.3.1.5.1 | With Bitmap .....                     | 117 |
| 2.3.1.5.2 | Without Bitmap .....                  | 118 |
| 2.3.1.6   | META_STRETCHDIB Record .....          | 119 |
| 2.3.2     | Control Record Types .....            | 121 |
| 2.3.2.1   | META_EOF Record .....                 | 121 |
| 2.3.2.2   | META_HEADER Record .....              | 121 |
| 2.3.2.3   | META_PLACEABLE Record .....           | 122 |

|          |   |     |
|----------|---|-----|
| 2.3.3    | Drawing Record Types .....              | 123 |
| 2.3.3.1  | META_ARC Record .....                   | 124 |
| 2.3.3.2  | META_CHORD Record.....                  | 125 |
| 2.3.3.3  | META_ELLIPSE Record.....                | 126 |
| 2.3.3.4  | META_EXTFLOODFILL Record .....          | 127 |
| 2.3.3.5  | META_EXTTEXTOUT Record .....            | 127 |
| 2.3.3.6  | META_FILLREGION Record.....             | 128 |
| 2.3.3.7  | META_FLOODFILL Record .....             | 129 |
| 2.3.3.8  | META_FRAMEREGION Record .....           | 130 |
| 2.3.3.9  | META_INVERTREGION Record .....          | 130 |
| 2.3.3.10 | META_LINETO Record.....                 | 131 |
| 2.3.3.11 | META_PAINTREGION Record .....           | 132 |
| 2.3.3.12 | META_PATBLT Record.....                 | 132 |
| 2.3.3.13 | META_PIE Record .....                   | 133 |
| 2.3.3.14 | META_POLYLINE Record .....              | 134 |
| 2.3.3.15 | META_POLYGON Record.....                | 134 |
| 2.3.3.16 | META_POLYPOLYGON Record .....           | 135 |
| 2.3.3.17 | META_RECTANGLE Record .....             | 136 |
| 2.3.3.18 | META_ROUNDRECT Record .....             | 136 |
| 2.3.3.19 | META_SETPIXEL Record.....               | 137 |
| 2.3.3.20 | META_TEXTOUT Record .....               | 138 |
| 2.3.4    | Object Record Types.....                | 138 |
| 2.3.4.1  | META_CREATEBRUSHINDIRECT Record .....   | 139 |
| 2.3.4.2  | META_CREATEFONTINDIRECT Record .....    | 140 |
| 2.3.4.3  | META_CREATEPALETTE Record.....          | 141 |
| 2.3.4.4  | META_CREATEPATTERNBRUSH Record .....    | 141 |
| 2.3.4.5  | META_CREATEPENINDIRECT Record .....     | 143 |
| 2.3.4.6  | META_CREATEREGION Record.....           | 143 |
| 2.3.4.7  | META_DELETEOBJECT Record .....          | 144 |
| 2.3.4.8  | META_DIBCREATEPATTERNBRUSH Record ..... | 144 |
| 2.3.4.9  | META_SELECTCLIPREGION Record.....       | 145 |
| 2.3.4.10 | META_SELECTOBJECT Record.....           | 146 |
| 2.3.4.11 | META_SELECTPALETTE Record .....         | 146 |
| 2.3.5    | State Record Types .....                | 147 |
| 2.3.5.1  | META_ANIMATEPALETTE Record .....        | 149 |
| 2.3.5.2  | META_EXCLUDECLIPRECT Record .....       | 149 |
| 2.3.5.3  | META_INTERSECTCLIPRECT Record .....     | 150 |
| 2.3.5.4  | META_MOVETO Record.....                 | 151 |
| 2.3.5.5  | META_OFFSETCLIPRGN Record.....          | 151 |
| 2.3.5.6  | META_OFFSETVIEWPORTORG Record.....      | 152 |
| 2.3.5.7  | META_OFFSETWINDOWORG Record.....        | 152 |
| 2.3.5.8  | META_REALIZEPALETTE Record .....        | 153 |
| 2.3.5.9  | META_RESIZEPALETTE Record .....         | 153 |
| 2.3.5.10 | META_RESTOREDC Record .....             | 153 |
| 2.3.5.11 | META_SAVEDC Record.....                 | 154 |
| 2.3.5.12 | META_SCALEVIEWPORTEXT Record.....       | 154 |
| 2.3.5.13 | META_SCALEWINDOWEXT Record.....         | 155 |
| 2.3.5.14 | META_SETBKCOLOR Record .....            | 156 |
| 2.3.5.15 | META_SETBKMODE Record .....             | 156 |
| 2.3.5.16 | META_SETLAYOUT Record.....              | 157 |
| 2.3.5.17 | META_SETMAPMODE Record .....            | 157 |
| 2.3.5.18 | META_SETMAPPERFLAGS Record .....        | 158 |
| 2.3.5.19 | META_SETPALENTRIES Record .....         | 158 |

|          |  |     |
|----------|--|-----|
| 2.3.5.20 | META_SETPOLYFILLMODE Record .....          | 159 |
| 2.3.5.21 | META_SETRELABS Record .....                | 160 |
| 2.3.5.22 | META_SETROP2 Record .....                  | 160 |
| 2.3.5.23 | META_SETSTRETCHBLTMODE Record .....        | 161 |
| 2.3.5.24 | META_SETTEXTALIGN Record .....             | 161 |
| 2.3.5.25 | META_SETTEXTCHAREXTRA Record .....         | 162 |
| 2.3.5.26 | META_SETTEXTCOLOR Record .....             | 162 |
| 2.3.5.27 | META_SETTEXTJUSTIFICATION Record .....     | 163 |
| 2.3.5.28 | META_SETVIEWPORTEXT Record .....           | 163 |
| 2.3.5.29 | META_SETVIEWPORTORG Record .....           | 164 |
| 2.3.5.30 | META_SETWINDOWEXT Record .....             | 164 |
| 2.3.5.31 | META_SETWINDOWORG Record .....             | 165 |
| 2.3.6    | Escape Record Types .....                  | 165 |
| 2.3.6.1  | META_ESCAPE Record .....                   | 168 |
| 2.3.6.2  | ABORTDOC Record .....                      | 168 |
| 2.3.6.3  | BEGIN_PATH Record .....                    | 169 |
| 2.3.6.4  | CHECK_JPEGFORMAT Record .....              | 169 |
| 2.3.6.5  | CHECK_PNGFORMAT Record .....               | 170 |
| 2.3.6.6  | CLIP_TO_PATH Record .....                  | 171 |
| 2.3.6.7  | CLOSE_CHANNEL Record .....                 | 171 |
| 2.3.6.8  | DOWNLOAD_FACE Record .....                 | 172 |
| 2.3.6.9  | DOWNLOAD_HEADER Record .....               | 173 |
| 2.3.6.10 | DRAW_PATTERNRECT Record .....              | 173 |
| 2.3.6.11 | ENCAPSULATED_POSTSCRIPT Record .....       | 174 |
| 2.3.6.12 | END_PATH Record .....                      | 175 |
| 2.3.6.13 | ENDDOC Record .....                        | 176 |
| 2.3.6.14 | EPS_PRINTING Record .....                  | 176 |
| 2.3.6.15 | EXTTEXTOUT Record .....                    | 177 |
| 2.3.6.16 | GET_COLORTABLE Record .....                | 177 |
| 2.3.6.17 | GET_DEVICEUNITS Record .....               | 179 |
| 2.3.6.18 | GET_EXTENDED_TEXTMETRICS Record .....      | 179 |
| 2.3.6.19 | GET_FACENAME Record .....                  | 180 |
| 2.3.6.20 | GET_PAIRKERNTABLE Record .....             | 180 |
| 2.3.6.21 | GET_PHYSPAGESIZE Record .....              | 181 |
| 2.3.6.22 | GET_PRINTINGOFFSET Record .....            | 181 |
| 2.3.6.23 | GET_PS_FEATURESETTING Record .....         | 182 |
| 2.3.6.24 | GET_SCALINGFACTOR Record .....             | 182 |
| 2.3.6.25 | META_ESCAPE_ENHANCED_METAFILE Record ..... | 183 |
| 2.3.6.26 | METAFILE_DRIVER Record .....               | 185 |
| 2.3.6.27 | NEWFRAME Record .....                      | 185 |
| 2.3.6.28 | NEXTBAND Record .....                      | 186 |
| 2.3.6.29 | PASSTHROUGH Record .....                   | 186 |
| 2.3.6.30 | POSTSCRIPT_DATA Record .....               | 187 |
| 2.3.6.31 | POSTSCRIPT_IDENTIFY Record .....           | 187 |
| 2.3.6.32 | POSTSCRIPT_IGNORE Record .....             | 188 |
| 2.3.6.33 | POSTSCRIPT_INJECTION Record .....          | 189 |
| 2.3.6.34 | POSTSCRIPT_PASSTHROUGH Record .....        | 189 |
| 2.3.6.35 | OPEN_CHANNEL Record .....                  | 190 |
| 2.3.6.36 | QUERY_DIBSUPPORT Record .....              | 190 |
| 2.3.6.37 | QUERY_ESCSUPPORT Record .....              | 191 |
| 2.3.6.38 | SET_COLORTABLE Record .....                | 192 |
| 2.3.6.39 | SET_COPYCOUNT Record .....                 | 192 |
| 2.3.6.40 | SET_LINECAP Record .....                   | 193 |

|          |   |            |
|----------|---|------------|
| 2.3.6.41 | SET_LINEJOIN Record .....                   | 194        |
| 2.3.6.42 | SET_MITERLIMIT Record .....                 | 194        |
| 2.3.6.43 | SPCLPASSTHROUGH2 Record .....               | 195        |
| 2.3.6.44 | STARTDOC Record .....                       | 196        |
| <b>3</b> | <b>Structure Examples .....</b>             | <b>197</b> |
| 3.1      | Metafile Design .....                       | 197        |
| 3.1.1    | Device Independence .....                   | 197        |
| 3.1.2    | Byte Ordering Example .....                 | 197        |
| 3.1.3    | Mapping Modes .....                         | 198        |
| 3.1.4    | Managing Objects .....                      | 199        |
| 3.1.4.1  | WMF Object Table .....                      | 199        |
| 3.1.4.2  | Object Scaling .....                        | 199        |
| 3.1.5    | Playback Device Context .....               | 200        |
| 3.1.6    | Run-Length Encoding (RLE) Compression ..... | 203        |
| 3.1.6.1  | Bitmaps with 4 Bits per Pixel .....         | 203        |
| 3.1.6.2  | Bitmaps with 8 Bits per Pixel .....         | 204        |
| 3.2      | WMF Metafile Example .....                  | 206        |
| 3.2.1    | META_HEADER Example .....                   | 206        |
| 3.2.2    | META_CREATEPENINDIRECT Example .....        | 207        |
| 3.2.3    | META_SELECTOBJECT Example .....             | 208        |
| 3.2.4    | META_CREATEBRUSHINDIRECT Example .....      | 209        |
| 3.2.5    | META_SELECTOBJECT Example .....             | 210        |
| 3.2.6    | META_RECTANGLE Example .....                | 210        |
| 3.2.7    | META_TEXTOUT Example .....                  | 211        |
| 3.2.8    | META_EOF Example .....                      | 212        |
| <b>4</b> | <b>Security Considerations .....</b>        | <b>213</b> |
| <b>5</b> | <b>Appendix A: Product Behavior .....</b>   | <b>214</b> |
| <b>6</b> | <b>Change Tracking .....</b>                | <b>220</b> |
| <b>7</b> | <b>Index .....</b>                          | <b>222</b> |



# 1 Introduction

This is a specification of the **Windows metafile format (WMF)** structure. The WMF structure specifies a **metafile** format that can store a picture in portable form. The stored picture can be rendered by parsing and processing the metafile.

A WMF metafile is a series of variable-length records, called WMF records, that contain graphics drawing commands, object definitions and properties. The metafile begins with a header record, which includes the metafile version, its size, and the number of objects it defines. A WMF metafile is "played back" when its records are converted to a format understood by a specific graphics device.

## 1.1 Glossary

The following terms are defined in [\[MS-GLOS\]](#):

**American National Standards Institute (ANSI) character set**

**ASCII**

**big-endian**

**color profile**

**enhanced metafile format (EMF)**

**Graphics Device Interface (GDI)**

**Image Color Management (ICM)**

**little-endian**

**original equipment manufacturer (OEM) character set**

**PostScript**

**print job**

**Printer Control Language (PCL)**

**printer driver**

**Unicode**

**UTF16-LE (Unicode Transformation Format, 16-bits, little-endian)**

**Windows metafile format (WMF)**

**XML**

The following terms are specific to this document:

**additive color model:** A **color model** that involves light emitted directly from a source or illuminant of some sort. The additive reproduction process usually uses red, green, and blue light to produce the other colors.

**anisotropic:** Refers to the properties of an image, such as the scaling of logical units to device units, which are not the same regardless of the direction (x-axis versus y-axis) that is measured. Contrast with **isotropic**.

**anti-aliasing:** The smoothing of the jagged appearance of font characters and lines, which is an artifact of the limited resolution on an output device. The pixels that surround the edges of the character glyph or line are changed to varying shades of color in order to blend the sharp edge into the background.

**banding:** A printing technique in which an application prints an image by dividing it into a number of bands and sending each band to the printer separately.

**baseline:** The imaginary line to which the bottom of the lowercase "x" character in a font **typeface** is aligned.

**bitmap:** A collection of structures that contain a representation of a graphical image, a **logical palette**, dimensions and other information.

**bottom-up bitmap:** A **bitmap** with an origin at the bottom-left corner.

**chromaticity:** The quality of a color as determined by the magnitudes and relative intensities of its **red green blue (RGB)** components in the **color space**.

**CIEXYZ:** A widely used device-independent color standard developed by the **Commission Internationale de l'Éclairage (CIE)**. The CIEXYZ standard is based on color-matching experiments on human observers. No actual device is expected to produce colors in this **color space**. It is used as a means of converting colors from one **color space** to another. The primary colors in this **color space** are the abstract colors X, Y, and Z.

**ClearType:** A font technology developed by Microsoft that can display fractions of pixels of character glyphs and which improves the readability of text on liquid crystal displays (LCDs) and flat-panel monitors.

**CMYK:** A **color space** used for commercial printing and most color computer printers. In theory, cyan, magenta, and yellow (CMY) can print all colors, but inks are not pure and black comes out muddy. The black (K) ink is required for quality black-and-white printing.

**color correction:** A process used in graphics image rendering and other disciplines to alter the overall quality of the light measured on a scale known as color temperature, a characteristic of visible light is determined by comparing its chromaticity with a theoretical, heated black-body radiator. Color temperatures are expressed in degrees Kelvin, as the temperature at which a heated black-body radiator matches the color of a given light source.

**color matching:** The conversion of a color, sent from its original **color space**, to its visually closest color in the destination **Image Color Management (ICM)**.

**color model:** See **color Space**.

**color space:** A system for describing color numerically, also known as a **color model**. Mathematically, a color space is a mapping of color components to a multidimensional coordinate system. The number of dimensions is generally one, three, or four. For example, if colors are expressed as a combination of the three components red, green, and blue, a three-dimensional space is sufficient to describe all possible colors. **Grayscale**s, however, can be mapped to a one-dimensional color space. If transparency is considered one of the components of a **RGB** color, four dimensions are appropriate.

**color table:** An array of data that maps pixel values into a **color space**.

**Commission Internationale de l'Eclairage (CIE):** An international Commission on Illumination in Vienna, Austria ([www.cie.co.at](http://www.cie.co.at)) that sets standards for all aspects of lighting and illumination, including colorimetry, photometry, and the measurement of visible and invisible radiation.

**device context:** An abstract data structure that defines a set of graphics objects and their associated attributes, and the graphics parameters that affect output. Graphics objects include a pen for line drawing, a brush for painting and filling, a font for text output, a **palette** for defining the set of available colors, and a **region** for clipping and other operations. All these device context properties and objects together define an environment for graphics output.

**device-independent bitmap (DIB):** A container for bitmapped graphics, which specifies characteristics of the **bitmap** such that it can be created using one application and loaded and displayed in another application, while retaining an identical appearance.

**dithering:** A form of digital **halftoning**.

**Encapsulated PostScript (EPS):** A file of PostScript-language raw data that describes the appearance of a single page. EPS data can describe text, graphics, and images; but the primary purpose of an EPS file is to be encapsulated within another PostScript-language page definition.

**font association:** The automatic pairing of a font that contains ideographs with a font that does not contain ideographs. Font association is used to maintain font attributes across changes in locale. For example, it allows the user to enter ideographic characters regardless of which font is selected.

**font embedding:** The process of attaching a font to a document so that the font may be used wherever the document is used, regardless of whether the font is installed on the system.

**font mapper:** An operating system component that maps specified font attributes to available, installed fonts on the system.

**gamma:** A value that describes the way brightness is distributed across the intensity spectrum by a graphics device. Depending on the device, the gamma may have a significant effect on the way colors are perceived. Technically, gamma is an expression of the relationship between input voltage and resulting output intensity. A perfect linear device would have a gamma of 1.0; a monitor or printer typically has a gamma in the range of 1.8 to 2.6, which affects midrange tones. Gamma values are used to implement **gamma correction**. Typically, separate gamma values are used for each component of a **color space**.

**gamma correction:** An adjustment to the light intensity (brightness) of a graphics device, in order to match the output more closely to the original image.

**grayscale:** A continuum of shades of gray used to represent an image. Continuous-tone images, such as black-and-white photographs, use an almost unlimited number of shades of gray. Conventional computer hardware and software, however, can only represent a limited gray, typically 16 or 256. Grayscale is the process of converting a continuous-tone image to an image that a computer can manipulate.

Note that grayscale is different from **dithering**: **Dithering** simulates shades of gray by altering the density and pattern of black and white dots. In grayscale, each individual dot can have a different shade of gray.

**halftoning:** The process of converting **grayscale** or continuous-tone graphics to a representation with a discrete number of gray or tone levels.

**ICC Color Profile:** An **International Color Consortium (ICC)**-approved color management standard for specifying the attributes of imaging devices such as scanners, digital cameras, monitors, and printers so that the color of an image remains true from source to destination. A **color profile** can be embedded within the image itself. See [\[ICC\]](#) for further details on the **International Color Consortium (ICC)**.

**International Color Consortium (ICC):** A group established in 1993 by eight industry vendors for the purpose of creating, promoting, and encouraging the standardization and evolution of an open, vendor-neutral, cross-platform color management system architecture and components. The outcome of this cooperation was the development of the ICC profile specification. Version 4 of the specification is now widely used and has recently been approved as International Standard ISO 15076.

**isotropic:** Refers to the properties of an image, such as the scaling of logical units to device units, which are the same regardless of the direction (x-axis versus y-axis) that is measured. Contrast with **anisotropic**.

**Joint Photographic Experts Group (JPEG):** A standard still-image format that is very popular due to its excellent compression capabilities. JPEG files are widely used for photographic images, but are not as well suited for compressing charts and diagrams, because text can become fuzzy. JPEG files use the JPEG File Interchange Format, as specified in [\[JFIF\]](#), and file extensions are .JPG or .JFF.

**logical object:** A graphics object that is defined with device-independent parameters, without assuming device specifics, such as color format or resolution.

**logical palette:** A **palette** that defines colors as device-independent values. Unlike the **system palette**, which has predefined, device-specific color definitions, a logical palette contains color values that can be defined entirely by an application. A logical palette entry must be mapped to the **system palette** entry in order for the custom colors to appear when the application is run.

**mapping mode:** The way in which **page space** coordinates are mapped to the coordinate system of an output device, which may be the client area of an application window, the entire desktop, a complete window, or a page of printer or plotter paper.

**metafile:** A sequence of record structures that store an image in an application-independent format. Metafile records contain drawing commands, object definitions, and configuration settings. When a metafile is processed, the stored image can be rendered on a display, output to a printer or plotter, stored in memory, or saved to a file or stream.

**METAFILEPICT:** A structure that defines the **metafile** picture format. METAFILEPICT is used for exchanging **metafile** data through the clipboard. See [\[MSDN-CLIPFORM\]](#) for further information

**n-up printing:** Arranging multiple logical pages on a physical sheet of paper.

**OpenType:** A **Unicode**-based font technology developed by Microsoft and Adobe. It is an extension to **TrueType** and **type 1 font** technologies; OpenType allows **PostScript** glyph definitions in addition to **TrueType** glyph definitions both to reside in a common container format.

**outline font:** A font that is defined with mathematical equations, which makes it possible for a printer or other output device to generate the characters at any size. Besides being arbitrarily scalable, the appearance of an outline font improves in proportion to the resolution of an output device. **TrueType** and **PostScript** are examples of outline font technology.

**packed bitmap:** A **device-independent bitmap (DIB)** in which the bit array immediately follows a [BitmapInfoHeader object \(section 2.2.2.3\)](#).

**page space:** A logical coordinate system used for graphics operations. It is determined by the **mapping mode**. Page space is defined with device-independent units, such as pixels.

**palette:** An array of values, each element of which contains the definition of a color. The color elements in a palette are often indexed so that clients can refer to the colors, each of which can occupy 24 bits or more, by a number that requires less storage space.

**path:** A graphics object that is a container for a series of line and curve segments, and **regions** in an image.

**pitch:** A property of a font that describes the horizontal density of characters in a font; that is, the number of characters that can fit in a given unit of space. When all the characters in a font have the same width, the font is called "fixed-pitch"; if characters can have various widths, the font is "variable-pitch".

"Times New Roman" is a variable-pitch font; it is easy to see that the characters in the font may have different widths. For example, the width of a lowercase "i" is visibly less than the width of an uppercase "W".

**playback device context:** The **device\_context** that defines the current graphics state during playback of the **metafile**. Playback is always associated with an output device with specific properties, such as resolution, color support, etc.

**Portable Network Graphics (PNG):** A bitmapped graphics file format that provides advanced graphics features such as 48-bit color, alpha channels, built-in **gamma correction** and **color correction**, tight compression, and the ability to display at one resolution and print at another.

**raster operation:** The process of combining the bits in a source **bitmap** with the bits in a destination **bitmap**.

**rasterization:** The process of converting geometric shapes into a matrix of discrete pixel settings.

**rasterized font:** A font produced with **rasterization**. Such fonts are not scalable, but must define glyph **bitmaps** at specific sizes. Because of this, the appearance of rasterized fonts does not improve in proportion to the resolution of an output device and, when magnified, appear significantly worse than **vector fonts**.

**raw mode:** Refers to a spool file format that requires no further processing; it is ready to be received by the printer for which the data was formatted.

**red green blue (RGB):** An **additive color model** in which red, green, and blue are combined in various ways to reproduce other colors.

**region:** A graphics object that is an area of an image, non-rectilinear in shape, that is defined by an array of **scanlines**.

**reverse Polish notation:** A mathematical notation wherein every operator follows all of its operands. Also known as "postfix" notation.

**run-length encoding (RLE) compression:** A form of data compression in which repeated values are represented by a count and a single instance of the value. Applied to a **bitmap**, RLE compression can significantly reduce disk and memory space requirements.

See section [3.1.6](#) for more information.

**scanline:** A row of pixels in a **rasterized** image or **bitmap**. Multiple scanlines can be used to define the boundaries and to fill any polygon or shape.

**sRGB:** A standard, predefined **color space** that is portable across all devices and allows accurate **color matching** with little overhead. sRGB was developed by Hewlett-Packard and Microsoft and is specified in [\[IEC-RGB\]](#). It is available to users of Windows.[<1>](#)

**stock object:** A predefined graphics object. Stock objects are used as default brush, font, **palette**, and pen objects in the **playback device context**.

**system palette:** The **palette** that is actually in use to reproduce colors on a device such as a computer screen. A system palette has predefined, device-specific colors that are used by default, so that every application does not have to set them up.

**top-down bitmap:** A **bitmap** with an origin at the upper-left corner.

**tri-stimulus:** The generation of color using three color components.

**TrueType:** A scalable font technology that renders fonts for both the printer and the screen. Originally developed by Apple, it was enhanced jointly by Apple and Microsoft. Each TrueType font contains its own algorithms for converting printer outlines into screen **bitmaps**, which means both the outline and **bitmap** information is **rasterized** from the same font data. The lower-level language embedded within the TrueType font allows great flexibility in their design. Both TrueType and **Type 1 font** technologies are part of the **OpenType** format.

**Type 1 font:** A public, standard, type format originally developed by Adobe for use with **PostScript** printers. Type 1 fonts contain two components—**outline fonts**, used for printing; and a **bitmap** font set, used for screen display.

**typeface:** A term that is used interchangeably with "font"; however, more accurately, a typeface is the primary design of a set of printed characters, such as Courier, Helvetica, and Times Roman, while a font is the particular implementation and variation of the typeface, such as normal, bold, or italic. The distinguishing characteristic of a typeface is often the presence or absence of serifs.

**TWIP:** A unit of measurement used in printing, equal to 1/20 point, or 1/1440 of an inch.

**vector font:** A font that is defined with geometrical primitives such as points, lines, curves and polygons, which are all based on mathematical equations instead of collections of discrete pixel settings. Vector fonts can be rendered in high quality at arbitrary sizes. **Outline fonts** are vector fonts. Contrast with **rasterized fonts**.

**white point:** A set of **tri-stimulus** values that define the color "white" in graphics image rendering. Depending on the application, different definitions of white may be needed to produce acceptable results. For example, photographs taken indoors may be lit by incandescent lights, which are relatively orange compared to daylight. Defining "white" as daylight will give unacceptable results when attempting to **color-correct** a photograph taken with incandescent lighting.

**Windows Color System (WCS):** Color management technology that ensures a color image, graphic, or text object is rendered as closely as possible to its original intent on any device, despite differences in imaging technologies and color capabilities between devices. WCS is a superset of **ICM** APIs and functionality and includes a variety of new functions that provide significant improvements in flexibility, transparency, predictability, and extensibility for vendors. <2>

**XML Paper Specification (XPS):** A Windows technology that uses **XML** to describe a container for application data. It enables end users to create, annotate, and view fixed-layout paginated documents, and to digitally sign and apply rights management to those documents. For more information, see [\[MSDN-XMLP\]](#).

**MAY, SHOULD, MUST, SHOULD NOT, MUST NOT:** These terms (in all caps) are used as specified in [\[RFC2119\]](#). All statements of optional behavior use either MAY, SHOULD, or SHOULD NOT.

## 1.2 References

References to Microsoft Open Specification documents do not include a publishing year because links are to the latest version of the documents, which are updated frequently. References to other documents include a publishing year when one is available.

### 1.2.1 Normative References

We conduct frequent surveys of the normative references to assure their continued availability. If you have any issue with finding a normative reference, please contact [dochelp@microsoft.com](mailto:dochelp@microsoft.com). We will assist you in finding the relevant information. Please check the archive site, <http://msdn2.microsoft.com/en-us/library/E4BD6494-06AD-4aed-9823-445E921C9624>, as an additional source.

[ICC] International Color Consortium, "Image Technology Colour Management - Architecture, Profile Format, and Data Structure", Specification ICC.1:2004-10, May 2006, [http://www.color.org/icc\\_specs2.xalter](http://www.color.org/icc_specs2.xalter)

[IEC-RGB] International Electrotechnical Commission, "Colour Measurement and Management in Multimedia Systems and Equipment - Part 2-1: Default RGB Colour Space - sRGB", May 1998, <http://www.colour.org/tc8-05/Docs/colospace/61966-2-1.pdf>

[ISO/IEC-8859-1] International Organization for Standardization, "Information Technology -- 8-Bit Single-Byte Coded Graphic Character Sets -- Part 1: Latin Alphabet No. 1", ISO/IEC 8859-1, 1998, <http://www.iso.org/iso/en/CatalogueDetailPage.CatalogueDetail?CSNUMBER=28245&ICS1=35&ICS2=40&ICS3=>

**Note** There is a charge to download the specification.

[JFIF] Hamilton, E., "JPEG File Interchange Format, Version 1.02", September 1992, <http://www.w3.org/Graphics/JPEG/jfif.txt>

[MS-DTYP] Microsoft Corporation, "[Windows Data Types](#)".

[RFC2083] Boutell, T., "PNG (Portable Network Graphics) Specification Version 1.0", RFC 2083, March 1997, <http://www.ietf.org/rfc/rfc2083.txt>

[W3C-PNG] World Wide Web Consortium, "Portable Network Graphics (PNG) Specification, Second Edition", November 2003, <http://www.w3.org/TR/PNG>

[RFC2119] Bradner, S., "Key words for use in RFCs to Indicate Requirement Levels", BCP 14, RFC 2119, March 1997, <http://www.rfc-editor.org/rfc/rfc2119.txt>

### 1.2.2 Informative References

[MS-EMF] Microsoft Corporation, "[Enhanced Metafile Format](#)".

[MS-GLOS] Microsoft Corporation, "[Windows Protocols Master Glossary](#)".

[MSDN-CLIPFORM] Microsoft Corporation, "Clipboard Formats", <http://msdn.microsoft.com/en-us/library/ms649013.aspx>

[MSDN-XMLP] Microsoft Corporation, "A First Look at APIs For Creating XML Paper Specification Documents", <http://msdn.microsoft.com//msdnmag/issues/06/01/xmlpaperspecification/default.aspx>




## 1.3 Overview

### 1.3.1 Metafile Structure

The WMF specifies structures for defining a graphical image. A WMF metafile contains drawing commands, property definitions, and graphics objects in a series of WMF records. In effect, a WMF metafile is a digital recording of an image, and the recording can be played back to reproduce that image. Because WMF metafiles are application-independent, they can be shared among applications and used for image storage.

Original WMF metafiles were device-specific; that is, the graphical images they contained would only be rendered correctly if played back on the output device for which they were recorded. To overcome this limitation, "placeable" WMF metafiles were developed, which contain an extension to the standard header with information about the placement and scaling of the image.

The following figure illustrates the high-level structures of the original and placeable forms of WMF metafile.



**Figure 1: Structures of original and placeable Windows metafiles**

The [META\\_HEADER record \(section 2.3.2.2\)](#) contains information that defines the characteristics of the metafile, including:

- The type of the metafile
- The version of the metafile
- The size of the metafile
- The number of objects defined in the metafile



- The size of the largest single record in the metafile

The [META\\_PLACEABLE record \(section 2.3.2.3\)](#) contains extended information concerning the image, including:

- A bounding rectangle
- Logical unit size, for scaling
- A checksum, for validation

WMF records have a generic format, which is specified in section [2.3](#). Every WMF record contains the following information:

- The record size
- The record function
- Parameters, if any, for the record function

All WMF metafiles are terminated by a [WMF end-of-file](#) record.

### 1.3.2 Graphics Objects

Graphics objects include the brushes, fonts, palettes, pens, and regions, which are used in the drawing and painting operations specified in the records of a WMF metafile. They can be defined in metafile records prior to the records that specify their use; that is, they are designed to have a lifetime outside the processing of a particular record and to be reusable during the course of playing back the metafile. The structure of WMF graphics objects is specified in section [2.2.1](#).

Throughout this specification, it is assumed that these reusable graphics objects are available when needed for the processing of particular metafile records. This implies that they are stored or managed in some fashion; the store of available objects is referred to in the text as the **WMF Object Table**, which is described in section [3.1.4.1](#). The exact characteristics of the object store are determined by the particular implementations that parse and write the metafiles.

Records that specify drawing and painting operations can occur in a WMF metafile prior to the definition of any graphics objects. Thus, it is assumed that an initial state exists that specifies default graphics properties of the **playback device context**, including default graphics objects. Information concerning the playback device context is provided in section [3.1.5](#).

### 1.3.3 Byte Ordering

Data in the WMF metafile records is stored in **little-endian** format.

Some computer architectures number bytes in a binary word from left to right, which is referred to as **big-endian**. The byte numbering used for bitfields in this specification is big-endian. Other architectures number the bytes in a binary word from right to left, which is referred to as little-endian. The byte numbering used for enumerations, objects, and records in this specification is little-endian.

Using big-endian and little-endian methods, the number 0x12345678 would be stored as shown in the following.

| Byte order    | Byte 0 | Byte 1 | Byte 2 | Byte 3 |
|---------------|--------|--------|--------|--------|
| Big-endian    | 0x12   | 0x34   | 0x56   | 0x78   |
| Little-endian | 0x78   | 0x56   | 0x34   | 0x12   |

## 1.4 Relationship to Protocols and Other Structures

The WMF is not dependent on any protocols or other structures. The WMF defines a design and layout based on 16-bit operating systems. [<3>](#)

On 32-bit systems and for print spooling, it has been replaced by the **EMF**, defined in [\[MS-EMF\]](#).

## 1.5 Applicability Statement

Structures that are compliant with the WMF are portable, application-independent containers for images. The graphics supported in WMF metafiles are applicable to document content representation, including printing and plotting.

## 1.6 Versioning and Localization

This specification covers versioning issues in the following areas:

**Structure Versions:** There is only one version of the WMF structure.

**Localization:** This structure defines no locale-specific processes or data.

## 1.7 Vendor-Extensible Fields

The WMF defines a mechanism for the encapsulation of arbitrary, vendor-defined data. See section [2.3.6.1](#) for details.

## 2 Structures

This section specifies the structures used to define the WMF, including:

- Enumerations of WMF graphics properties, styles and flags.
- Definitions of WMF graphics and structure objects.
- Specifications of WMF metafile records, by type.

This protocol references commonly used data types as defined in [\[MS-DTYP\]](#).

### 2.1 WMF Constants

#### 2.1.1 WMF Enumerations

This section contains enumerations of constant values that are referenced in this specification.

##### 2.1.1.1 RecordType Enumeration

The **RecordType Enumeration** defines the types of records that can be used in WMF metafiles.

```
typedef enum
{
    META_EOF = 0x0000,
    META_REALIZEPALETTE = 0x0035,
    META_SETPALENTRIES = 0x0037,
    META_SETBKMODE = 0x0102,
    META_SETMAPMODE = 0x0103,
    META_SETROP2 = 0x0104,
    META_SETRELABS = 0x0105,
    META_SETPOLYFILLMODE = 0x0106,
    META_SETSTRETCHBLTMODE = 0x0107,
    META_SETTEXTCHAREXTRA = 0x0108,
    META_RESTOREDC = 0x0127,
    META_RESIZEPALETTE = 0x0139,
    META_DIBCREATEPATTERNBRUSH = 0x0142,
    META_SETLAYOUT = 0x0149,
    META_SETBKCOLOR = 0x0201,
    META_SETTEXTCOLOR = 0x0209,
    META_OFFSETVIEWPORTORG = 0x0211,
    META_LINETO = 0x0213,
    META_MOVETO = 0x0214,
    META_OFFSETCLIPRGN = 0x0220,
    META_FILLREGION = 0x0228,
    META_SETMAPPERFLAGS = 0x0231,
    META_SELECTPALETTE = 0x0234,
    META_POLYGON = 0x0324,
    META_POLYLINE = 0x0325,
    META_SETTEXTJUSTIFICATION = 0x020A,
    META_SETWINDOWORG = 0x020B,
    META_SETWINDOWEXT = 0x020C,
    META_SETVIEWPORTORG = 0x020D,
    META_SETVIEWPORTEXT = 0x020E,
    META_OFFSETWINDOWORG = 0x020F,
    META_SCALEWINDOWEXT = 0x0410,
    META_SCALEVIEWPORTEXT = 0x0412,
```

```

META_EXCLUDECLIPRECT = 0x0415,
META_INTERSECTCLIPRECT = 0x0416,
META_ELLIPSE = 0x0418,
META_FLOODFILL = 0x0419,
META_FRAMEREGION = 0x0429,
META_ANIMATEPALETTE = 0x0436,
META_TEXTOUT = 0x0521,
META_POLYPOLYGON = 0x0538,
META_EXTFLOODFILL = 0x0548,
META_RECTANGLE = 0x041B,
META_SETPIXEL = 0x041F,
META_ROUNDRECT = 0x061C,
META_PATBLT = 0x061D,
META_SAVEDC = 0x001E,
META_PIE = 0x081A,
META_STRETCHBLT = 0x0B23,
META_ESCAPE = 0x0626,
META_INVERTREGION = 0x012A,
META_PAINTREGION = 0x012B,
META_SELECTCLIPREGION = 0x012C,
META_SELECTOBJECT = 0x012D,
META_SETTEXTALIGN = 0x012E,
META_ARC = 0x0817,
META_CHORD = 0x0830,
META_BITBLT = 0x0922,
META_EXTTEXTOUT = 0x0a32,
META_SETDIBTODEV = 0x0d33,
META_DIBBITBLT = 0x0940,
META_DIBSTRETCHBLT = 0x0b41,
META_STRETCHDIB = 0x0f43,
META_DELETEOBJECT = 0x01f0,
META_CREATEPALETTE = 0x00f7,
META_CREATEPATTERNBRUSH = 0x01f9,
META_CREATEPENINDIRECT = 0x02fa,
META_CREATEFONTINDIRECT = 0x02fb,
META_CREATEBRUSHINDIRECT = 0x02fc,
META_CREATEREGION = 0x06ff
} RecordType;

```

**META\_EOF:** This record specifies the end of the file, the last record in the metafile.

**META\_REALIZEPALETTE:** This record maps entries from the **logical palette** that is defined in the **playback device context** to the **system palette**.

**META\_SETPALENTRIES:** This record defines **red green blue (RGB)** color values in a range of entries in the logical palette that is defined in the playback device context.

**META\_SETBKMODE:** This record defines the background **raster operation** mix mode in the playback device context. The background mix mode is the mode for combining pens, text, hatched brushes, and interiors of filled objects with background colors on the output surface.

**META\_SETMAPMODE:** This record defines the **mapping mode** in the playback device context. The mapping mode defines the unit of measure used to transform **page-space** coordinates into coordinates of the output device, and also defines the orientation of the device's x and y axes.

**META\_SETROP2:** This record defines the foreground raster operation mix mode in the playback device context. The foreground mix mode is the mode for combining pens and interiors of filled objects with foreground colors on the output surface.

**META\_SETRELABS:** This record is undefined and MUST be ignored.

**META\_SETPOLYFILLMODE:** This record defines polygon fill mode in the playback device context for graphics operations that fill polygons.

**META\_SETSTRETCHBLTMODE:** This record defines the **bitmap** stretching mode in the playback device context.

**META\_SETTEXTCHAREXTRA:** This record defines inter-character spacing for text justification in the playback device context. Spacing is added to the white space between each character, including break characters, when a line of justified text is output.

**META\_RESTOREDC:** This record restores the playback device context from a previously saved **device context**.

**META\_RESIZEPALETTE:** This record redefines the size of the logical palette that is defined in the playback device context.

**META\_DIBCREATEPATTERNBRUSH:** This record defines a brush with a pattern specified by a **device-independent bitmap (DIB)**.

**META\_SETLAYOUT:** This record defines the layout orientation in the playback device context.  
[<4>](#)

**META\_SETBKCOLOR:** This record sets the background color in the playback device context to a specified color, or to the nearest physical color if the device cannot represent the specified color.

**META\_SETTEXTCOLOR:** This record defines the text color in the playback device context.

**META\_OFFSETVIEWPORTORG:** This record moves the viewport origin in the playback device context by using specified horizontal and vertical offsets.

**META\_LINETO:** This record draws a line from the output position that is defined in the playback device context up to, but not including, a specified point.

**META\_MOVETO:** This record sets the output position in the playback device context to a specified point.

**META\_OFFSETCLIPRGN:** This record moves the clipping **region** that is defined in the playback device context by specified offsets.

**META\_FILLREGION:** This record fills a region by using a specified brush.

**META\_SETMAPPERFLAGS:** This record defines the algorithm that the **font mapper** uses when it maps logical fonts to physical fonts.

**META\_SELECTPALETTE:** This record specifies the logical palette in the playback device context.

**META\_POLYGON:** This record paints a polygon consisting of two or more vertices connected by straight lines. The polygon is outlined by using the pen and filled by using the brush and polygon fill mode; these are defined in the playback device context.

**META\_POLYLINE:** This record draws a series of line segments by connecting the points in a specified array.

**META\_SETTEXTJUSTIFICATION:** This record defines the amount of space to add to break characters in a string of justified text.

**META\_SETWINDOWORG:** This record defines the output window origin in the playback device context.

**META\_SETWINDOWEXT:** This record defines the horizontal and vertical extents of the output window in the playback device context.

**META\_SETVIEWPORTORG:** This record defines the viewport origin in the playback device context.

**META\_SETVIEWPORTEXT:** This record defines the horizontal and vertical extents of the viewport in the playback device context.

**META\_OFFSETWINDOWORG:** This record moves the output window origin in the playback device context by using specified horizontal and vertical offsets.

**META\_SCALEWINDOWEXT:** This record scales the horizontal and vertical extents of the output window that is defined in the playback device context by using the ratios formed by specified multiplicands and divisors.

**META\_SCALEVIEWPORTEXT:** This record scales the horizontal and vertical extents of the viewport that is defined in the playback device context by using the ratios formed by specified multiplicands and divisors.

**META\_EXCLUDECLIPRECT:** This record sets the clipping region that is defined in the playback device context to the existing clipping region minus a specified rectangle.

**META\_INTERSECTCLIPRECT:** This record sets the clipping region that is defined in the playback device context to the intersection of the existing clipping region and a specified rectangle.

**META\_ELLIPSE:** This record defines an ellipse. The center of the ellipse is the center of a specified bounding rectangle. The ellipse is outlined by using the pen and is filled by using the brush; these are defined in the playback device context.

**META\_FLOODFILL:** This record fills an area of the display surface with the brush that is defined in the playback device context.

**META\_FRAMEREGION:** This record defines a border around a specified region by using a specified brush.

**META\_ANIMATEPALETTE:** This record redefines entries in the logical palette that is defined in the playback device context.

**META\_TEXTOUT:** This record outputs a character string at a specified location using the font, background color, and text color; these are defined in the playback device context.

**META\_POLYPOLYGON:** This record paints a series of closed polygons. Each polygon is outlined by using the pen and filled by using the brush and polygon fill mode; these are defined in the playback device context. The polygons drawn in this operation can overlap.

**META\_EXTFLOODFILL:** This record fills an area with the brush that is defined in the playback device context.

**META\_RECTANGLE:** This record paints a rectangle. The rectangle is outlined by using the pen and filled by using the brush; these are defined in the playback device context.

**META\_SETPIXEL:** This record sets the pixel at specified coordinates to a specified color.

**META\_ROUNDRECT:** This record draws a rectangle with rounded corners. The rectangle is outlined by using the current pen and filled by using the current brush.

**META\_PATBLT:** This record paints the specified rectangle by using the brush that is currently selected into the playback device context. The brush color and the surface color or colors are combined using the specified raster operation.

**META\_SAVEDC:** This record saves the playback device context for later retrieval.

**META\_PIE:** This record draws a pie-shaped wedge bounded by the intersection of an ellipse and two radials. The pie is outlined by using the pen and filled by using the brush; these are defined in the playback device context.

**META\_STRETCHBLT:** This record specifies the transfer of a block of pixels according to a raster operation, with possible expansion or contraction.

**META\_ESCAPE:** This record makes it possible to access capabilities of a particular printing device that are not directly available through other WMF records.

**META\_INVERTREGION:** This record inverts the colors in a specified region.

**META\_PAINTREGION:** This record paints a specified region by using the brush that is defined in the playback device context.

**META\_SELECTCLIPREGION:** This record specifies the clipping region in the playback device context.

**META\_SELECTOBJECT:** This record specifies a graphics object in the playback device context. The new object replaces the previous object of the same type, if one is defined.

**META\_SETTEXTALIGN:** This record defines the text-alignment values in the playback device context.

**META\_ARC:** This record draws an elliptical arc.

**META\_CHORD:** This record draws a chord, which is a region bounded by the intersection of an ellipse and a line segment. The chord is outlined by using the pen and filled by using the brush; these are defined in the playback device context.

**META\_BITBLT:** This record specifies the transfer of a block of pixels according to a raster operation.

**META\_EXTTEXTOUT:** This record outputs a character string by using the font, background color, and text color; these are defined in the playback device context. Optionally, dimensions can be provided for clipping, opaquing, or both.

**META\_SETDIBTODEV:** This record sets a block of pixels using device-independent color data.

**META\_DIBBITBLT:** This record specifies the transfer of a block of pixels in device-independent format according to a raster operation.

**META\_DIBSTRETCHBLT:** This record specifies the transfer of a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction.

**META\_STRETCHDIB:** This record specifies the transfer of color data from a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction.

**META\_DELETEOBJECT:** This record deletes a graphics object, which can be a pen, brush, font, region, or **palette**.

**META\_CREATEPALETTE:** This record defines a logical palette.

**META\_CREATEPATTERNBRUSH:** This record defines a brush with a pattern specified by a DIB.

**META\_CREATEPENINDIRECT:** This record defines a pen with specified style, width, and color.

**META\_CREATEFONTINDIRECT:** This record defines a font with specified characteristics.

**META\_CREATEBRUSHINDIRECT:** This record defines a brush with specified style, color, and pattern.

**META\_CREATEREGION:** This record defines a region.

The high-order byte of the WMF record type values MAY [≤5>](#) be ignored for all record types except the following.

- **META\_BITBLT**
- **META\_DIBBITBLT**
- **META\_DIBSTRETCHBLT**
- **META\_POLYGON**
- **META\_POLYLINE**
- **META\_SETPALENTRIES**
- **META\_STRETCHBLT**

The meanings of the high-order bytes of these record type fields are specified in the respective sections that define them.

A record type is not defined for the WMF **Header** record, because only one can be present as the first record in the metafile.

#### 2.1.1.2 BinaryRasterOperation Enumeration

The **BinaryRasterOperation Enumeration** section lists the binary raster-operation codes. Raster-operation codes define how metafile processing combines the bits from the selected pen with the bits in the destination bitmap.

Each raster-operation code represents a Boolean operation in which the values of the pixels in the selected pen and the destination bitmap are combined. Following are the two operands used in these operations.

| Operand | Meaning            |
|---------|--------------------|
| P       | Selected pen       |
| D       | Destination bitmap |



Following are the Boolean operators used in these operations.

| Operator | Meaning                    |
|----------|----------------------------|
| a        | Bitwise AND                |
| n        | Bitwise NOT (inverse)      |
| o        | Bitwise OR                 |
| x        | Bitwise exclusive OR (XOR) |

All Boolean operations are presented in **reverse Polish notation**. For example, the following operation replaces the values of the pixels in the destination bitmap with a combination of the pixel values of the pen and the selected brush: DPo.

Each raster-operation code is a 32-bit integer whose high-order word is a Boolean operation index and whose low-order word is the operation code. The 16-bit operation index is a zero-extended, 8-bit value that represents all possible outcomes resulting from the Boolean operation on two parameters (in this case, the pen and destination values). For example, the operation indexes for the DPo and DPan operations are shown in the following list.

| P | D | DPo | DPan |
|---|---|-----|------|
| 0 | 0 | 0   | 1    |
| 0 | 1 | 1   | 1    |
| 1 | 0 | 1   | 1    |
| 1 | 1 | 1   | 0    |

The following enumeration lists the drawing modes and the Boolean operations that they represent.

```
typedef enum
{
    R2_BLACK = 0x0001,
    R2_NOTMERGEPEN = 0x0002,
    R2_MASKNOTPEN = 0x0003,
    R2_NOTCOPYPEN = 0x0004,
    R2_MASKPENNOT = 0x0005,
    R2_NOT = 0x0006,
    R2_XORPEN = 0x0007,
    R2_NOTMASKPEN = 0x0008,
    R2_MASKPEN = 0x0009,
    R2_NOTXORPEN = 0x000A,
    R2_NOP = 0x000B,
    R2_MERGENOTPEN = 0x000C,
    R2_COPYPEN = 0x000D,
    R2_MERGEPENNOT = 0x000E,
    R2_MERGEPEN = 0x000F,
    R2_WHITE = 0x0010
} BinaryRasterOperation;
```

**R2\_BLACK:** 0, Pixel is always 0.

**R2\_NOTMERGEPEN:** DPon, Pixel is the inverse of the **R2\_MERGEPEN** color.

**R2\_MASKNOTPEN:** DPna, Pixel is a combination of the screen color and the inverse of the pen color.

**R2\_NOTCOPYPEN:** Pn, Pixel is the inverse of the pen color.

**R2\_MASKPENNOT:** PDna, Pixel is a combination of the colors common to both the pen and the inverse of the screen.

**R2\_NOT:** Dn, Pixel is the inverse of the screen color.

**R2\_XORPEN:** DPx, Pixel is a combination of the colors in the pen or in the screen, but not in both.

**R2\_NOTMASKPEN:** DPan, Pixel is the inverse of the **R2\_MASKPEN** color.

**R2\_MASKPEN:** DPa, Pixel is a combination of the colors common to both the pen and the screen.

**R2\_NOTXORPEN:** DPxn, Pixel is the inverse of the **R2\_XORPEN** color.

**R2\_NOP:** D, Pixel remains unchanged.

**R2\_MERGENOTPEN:** DPno, Pixel is a combination of the colors common to both the screen and the inverse of the pen.

**R2\_COPYPEN:** P, Pixel is the pen color.

**R2\_MERGEPENNOT:** PDno, Pixel is a combination of the pen color and the inverse of the screen color.

**R2\_MERGEPEN:** DPo, Pixel is a combination of the pen color and the screen color.

**R2\_WHITE:** 1, Pixel is always 1

For a monochrome device, WMF format maps the value 0 to black and the value 1 to white. If an application attempts to draw with a black pen on a white destination by using the available binary raster operations, the following results occur.

| Raster operation      | Result             |
|-----------------------|--------------------|
| <b>R2_BLACK</b>       | Visible black line |
| <b>R2_COPYPEN</b>     | Visible black line |
| <b>R2_MASKNOTPEN</b>  | No visible line    |
| <b>R2_MASKPEN</b>     | Visible black line |
| <b>R2_MASKPENNOT</b>  | Visible black line |
| <b>R2_MERGENOTPEN</b> | No visible line    |
| <b>R2_MERGEPEN</b>    | Visible black line |
| <b>R2_MERGEPENNOT</b> | Visible black line |
| <b>R2_NOP</b>         | No visible line    |

| Raster operation      | Result             |
|-----------------------|--------------------|
| <b>R2_NOT</b>         | Visible black line |
| <b>R2_NOTCOPYPEN</b>  | No visible line    |
| <b>R2_NOTMASKPEN</b>  | No visible line    |
| <b>R2_NOTMERGEPEN</b> | Visible black line |
| <b>R2_NOTXORPEN</b>   | Visible black line |
| <b>R2_WHITE</b>       | No visible line    |
| <b>R2_XORPEN</b>      | No visible line    |

For a color device, WMF format uses RGB values to represent the colors of the pen and the destination. An RGB color value is a long integer that contains a red, a green, and a blue color field, each specifying the intensity of the given color. Intensities range from 0 through 255. The values are packed in the three low-order bytes of the long integer. The color of a pen is always a solid color, but the color of the destination may be a mixture of any two or three colors. If an application attempts to draw with a white pen on a blue destination by using the available binary raster operations, the following results occur.

| Raster operation      | Result                 |
|-----------------------|------------------------|
| <b>R2_BLACK</b>       | Visible black line     |
| <b>R2_COPYPEN</b>     | Visible white line     |
| <b>R2_MASKNOTPEN</b>  | Visible black line     |
| <b>R2_MASKPEN</b>     | Invisible blue line    |
| <b>R2_MASKPENNOT</b>  | Visible red/green line |
| <b>R2_MERGENOTPEN</b> | Invisible blue line    |
| <b>R2_MERGEPEN</b>    | Visible white line     |
| <b>R2_MERGENOT</b>    | Visible white line     |
| <b>R2_NOP</b>         | Invisible blue line    |
| <b>R2_NOT</b>         | Visible red/green line |
| <b>R2_NOTCOPYPEN</b>  | Visible black line     |
| <b>R2_NOTMASKPEN</b>  | Visible red/green line |
| <b>R2_NOTMERGEPEN</b> | Visible black line     |
| <b>R2_NOTXORPEN</b>   | Invisible blue line    |
| <b>R2_WHITE</b>       | Visible white line     |
| <b>R2_XORPEN</b>      | Visible red/green line |

### 2.1.1.3 BitCount Enumeration

The **BitCount Enumeration** specifies the number of bits that define each pixel and the maximum number of colors in a device-independent bitmap (DIB).

```
typedef enum
{
    BI_BITCOUNT_0 = 0x0000,
    BI_BITCOUNT_1 = 0x0001,
    BI_BITCOUNT_2 = 0x0004,
    BI_BITCOUNT_3 = 0x0008,
    BI_BITCOUNT_4 = 0x0010,
    BI_BITCOUNT_5 = 0x0018,
    BI_BITCOUNT_6 = 0x0020
} BitCount;
```

**BI\_BITCOUNT\_0:** The number of bits per pixel is undefined.

The image SHOULD be in either **JPEG** or **PNG** format. [<6>](#) Neither of these formats includes a **color table**, so this value specifies that no color table is present. See [\[JFIF\]](#) and [\[RFC2083\]](#) for more information concerning JPEG and PNG compression formats.

**BI\_BITCOUNT\_1:** The image is specified with two colors.

Each pixel in the bitmap is represented by a single bit. If the bit is clear, the pixel is displayed with the color of the first entry in the color table; if the bit is set, the pixel has the color of the second entry in the table.

**BI\_BITCOUNT\_2:** The image is specified with a maximum of 16 colors.

Each pixel in the bitmap is represented by a 4-bit index into the color table, and each byte contains 2 pixels.

**BI\_BITCOUNT\_3:** The image is specified with a maximum of 256 colors.

Each pixel in the bitmap is represented by an 8-bit index into the color table, and each byte contains 1 pixel.

**BI\_BITCOUNT\_4:** The image is specified with a maximum of  $2^{16}$  colors.

Each pixel in the bitmap is represented by a 16-bit value.

If the **Compression** field of the [BitmapInfoHeader Object](#) is BI\_RGB, the **Colors** field of DIB is NULL. Each **WORD** in the bitmap array represents a single pixel. The relative intensities of red, green, and blue are represented with 5 bits for each color component. The value for blue is in the least significant 5 bits, followed by 5 bits each for green and red. The most significant bit is not used. The color table is used for optimizing colors on palette-based devices, and contains the number of entries specified by the **ColorUsed** field of the BitmapInfoHeader Object.

If the **Compression** field of the BitmapInfoHeader Object is BI\_BITFIELDS, the **Colors** field contains three **DWORD** color masks that specify the red, green, and blue components, respectively, of each pixel. Each **WORD** in the bitmap array represents a single pixel.

When the **Compression** field is set to BI\_BITFIELDS, bits set in each **DWORD** mask MUST be contiguous and SHOULD NOT overlap the bits of another mask.

BI\_RGB and BI\_BITFIELDS are defined in [Compression Enumeration](#), section [2.1.1.7](#).

**BI\_BITCOUNT\_5:** The bitmap has a maximum of  $2^{24}$  colors, and the **Colors** field of DIB is NULL. Each 3-byte triplet in the bitmap array represents the relative intensities of blue, green, and red, respectively, for a pixel. The **Colors** color table is used for optimizing colors used on palette-based devices, and MUST contain the number of entries specified by the **ColorUsed** field of the BitmapInfoHeader Object.

**BI\_BITCOUNT\_6:** The bitmap has a maximum of  $2^{24}$  colors.

If the **Compression** field of the BitmapInfoHeader Object is set to BI\_RGB, the **Colors** field of DIB is set to NULL. Each **DWORD** in the bitmap array represents the relative intensities of blue, green, and red, respectively, for a pixel. The high byte in each **DWORD** is not used. The **Colors** color table is used for optimizing colors used on palette-based devices, and MUST contain the number of entries specified by the **ColorUsed** field of the BitmapInfoHeader Object.

If the **Compression** field of the BitmapInfoHeader Object is set to BI\_BITFIELDS, the **Colors** field contains three **DWORD** color masks that specify the red, green, and blue components, respectively, of each pixel. Each **DWORD** in the bitmap array represents a single pixel.

When the **Compression** field is set to BI\_BITFIELDS, bits set in each **DWORD** mask must be contiguous and should not overlap the bits of another mask. All the bits in the pixel do not need to be used.

BI\_RGB and BI\_BITFIELDS are specified in **Compression Enumeration**, section [2.1.1.7](#).

A DIB is specified by a [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#), and its header is a BitmapInfoHeader Object (section 2.2.2.3).

#### 2.1.1.4 BrushStyle Enumeration

The **BrushStyle Enumeration** specifies the different possible brush types that can be used in graphics operations. For more information, see the specification of the [Brush Object \(section 2.2.1.1\)](#).

```
typedef enum
{
    BS_SOLID = 0x0000,
    BS_NULL = 0x0001,
    BS_HATCHED = 0x0002,
    BS_PATTERN = 0x0003,
    BS_INDEXED = 0x0004,
    BS_DIBPATTERN = 0x0005,
    BS_DIBPATTERNPT = 0x0006,
    BS_PATTERN8X8 = 0x0007,
    BS_DIBPATTERN8X8 = 0x0008,
    BS_MONOPATTERN = 0x0009
} BrushStyle;
```

**BS\_SOLID:** A brush that paints a single, constant color, either solid or dithered.

**BS\_NULL:** A brush that does nothing. Using a BS\_NULL brush in a graphics operation MUST have the same effect as using no brush at all. [<7>](#)

**BS\_HATCHED:** A brush that paints a predefined simple pattern, or "hatch", onto a solid background.

**BS\_PATTERN:** A brush that paints a pattern defined by a bitmap, which MAY be a [Bitmap16 Object](#) or a [DeviceIndependentBitmap \(DIB\) Object](#).

**BS\_INDEXED:** Not supported.

**BS\_DIBPATTERN:** A pattern brush specified by a DIB.

**BS\_DIBPATTERNPT:** A pattern brush specified by a DIB.

**BS\_PATTERN8X8:** Not supported.

**BS\_DIBPATTERN8X8:** Not supported.

**BS\_MONOPATTERN:** Not supported.

### 2.1.1.5 CharacterSet Enumeration

The **CharacterSet Enumeration** defines the possible sets of character glyphs that are defined in fonts for graphics output.

```
typedef enum
{
    ANSI_CHARSET = 0x00000000,
    DEFAULT_CHARSET = 0x00000001,
    SYMBOL_CHARSET = 0x00000002,
    MAC_CHARSET = 0x0000004D,
    SHIFTJIS_CHARSET = 0x00000080,
    HANGUL_CHARSET = 0x00000081,
    JOHAB_CHARSET = 0x00000082,
    GB2312_CHARSET = 0x00000086,
    CHINESEBIG5_CHARSET = 0x00000088,
    GREEK_CHARSET = 0x000000A1,
    TURKISH_CHARSET = 0x000000A2,
    VIETNAMESE_CHARSET = 0x000000A3,
    HEBREW_CHARSET = 0x000000B1,
    ARABIC_CHARSET = 0x000000B2,
    BALTIC_CHARSET = 0x000000BA,
    RUSSIAN_CHARSET = 0x000000CC,
    THAI_CHARSET = 0x000000DE,
    EASTEUROPE_CHARSET = 0x000000EE,
    OEM_CHARSET = 0x000000FF
} CharacterSet;
```

**ANSI\_CHARSET:** Specifies the English character set.

**DEFAULT\_CHARSET:** Specifies a character set based on the current system locale; for example, when the system locale is United States English, the default character set is ANSI\_CHARSET.

**SYMBOL\_CHARSET:** Specifies a character set of symbols.

**MAC\_CHARSET:** Specifies the Apple Macintosh character set. [<8>](#)

**SHIFTJIS\_CHARSET:** Specifies the Japanese character set.

**HANGUL\_CHARSET:** Also spelled "Hangeul". Specifies the Hangul Korean character set.

**JOHAB\_CHARSET:** Also spelled "Johap". Specifies the Johab Korean character set.

**GB2312\_CHARSET:** Specifies the "simplified" Chinese character set for People's Republic of China.

**CHINESEBIG5\_CHARSET:** Specifies the "traditional" Chinese character set, used mostly in Taiwan and in the Hong Kong and Macao Special Administrative Regions.

**GREEK\_CHARSET:** Specifies the Greek character set.

**TURKISH\_CHARSET:** Specifies the Turkish character set.

**VIETNAMESE\_CHARSET:** Specifies the Vietnamese character set.

**HEBREW\_CHARSET:** Specifies the Hebrew character set

**ARABIC\_CHARSET:** Specifies the Arabic character set

**BALTIC\_CHARSET:** Specifies the Baltic (Northeastern European) character set

**RUSSIAN\_CHARSET:** Specifies the Russian Cyrillic character set.

**THAI\_CHARSET:** Specifies the Thai character set.

**EASTEUROPE\_CHARSET:** Specifies a Eastern European character set.

**OEM\_CHARSET:** Specifies a mapping to one of the OEM code pages, according to the current system locale setting.

### 2.1.1.6 ColorUsage Enumeration

The **ColorUsage Enumeration** specifies whether a color table exists in a device-independent bitmap (DIB) and how to interpret its values.

```
typedef enum
{
    DIB_RGB_COLORS = 0x0000,
    DIB_PAL_COLORS = 0x0001,
    DIB_PAL_INDICES = 0x0002
} ColorUsage;
```

**DIB\_RGB\_COLORS:** The color table contains RGB values specified by [RGBQuad Objects \(section 2.2.2.20\)](#).

**DIB\_PAL\_COLORS:** The color table contains 16-bit indices into the current logical palette in the playback device context.

**DIB\_PAL\_INDICES:** No color table exists. The pixels in the DIB are indices into the current logical palette in the playback device context.

A DIB is specified by a [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#).

### 2.1.1.7 Compression Enumeration

The **Compression Enumeration** specifies the type of compression for a bitmap image.

```
typedef enum
{
    BI_RGB = 0x0000,
    BI_RLE8 = 0x0001,
    BI_RLE4 = 0x0002,
    BI_BITFIELDS = 0x0003,
    BI_JPEG = 0x0004,
    BI_PNG = 0x0005,
    BI_CMYK = 0x000B,
    BI_CMYKRLE8 = 0x000C,
    BI_CMYKRLE4 = 0x000D
} Compression;
```

**BI\_RGB:** The bitmap is in uncompressed red green blue (RGB) format that is not compressed and does not use color masks.

**BI\_RLE8:** An RGB format that uses **run-length encoding (RLE) compression** for bitmaps with 8 bits per pixel. The compression uses a 2-byte format consisting of a count byte followed by a byte containing a color index.

**BI\_RLE4:** An RGB format that uses RLE compression for bitmaps with 4 bits per pixel. The compression uses a 2-byte format consisting of a count byte followed by two word-length color indexes.

**BI\_BITFIELDS:** The bitmap is not compressed and the color table consists of three **DWORD** color masks that specify the red, green, and blue components, respectively, of each pixel. This is valid when used with 16 and 32-bits per pixel bitmaps.

**BI\_JPEG:** The image is a JPEG image, as specified in [\[JFIF\]](#). This value SHOULD only be used in certain bitmap operations, such as JPEG pass-through. The application MUST query for the pass-through support, since not all devices support JPEG pass-through. Using non-RGB bitmaps MAY limit the portability of the metafile to other devices. For instance, display device contexts generally do not support this pass-through.

**BI\_PNG:** The image is a PNG image, as specified in [\[RFC2083\]](#). This value SHOULD only be used certain bitmap operations, such as JPEG/PNG pass-through. The application MUST query for the pass-through support, because not all devices support JPEG/PNG pass-through. Using non-RGB bitmaps MAY limit the portability of the metafile to other devices. For instance, display device contexts generally do not support this pass-through.

**BI\_CMYK:** The image is an uncompressed **CMYK** format.

**BI\_CMYKRLE8:** A CMYK format that uses RLE compression for bitmaps with 8 bits per pixel. The compression uses a 2-byte format consisting of a count byte followed by a byte containing a color index.

**BI\_CMYKRLE4:** A CMYK format that uses RLE compression for bitmaps with 4 bits per pixel. The compression uses a 2-byte format consisting of a count byte followed by two word-length color indexes.

**Note** A **bottom-up bitmap** can be compressed, but a **top-down bitmap** cannot.



See section [3.1.6](#) for more information on RLE compression.

### 2.1.1.8 FamilyFont Enumeration

The **FamilyFont enumeration** specifies the font family. Font families describe the look of a font in a general way. They are intended for specifying fonts when the exact **typeface** desired is not available.

```
typedef enum
{
    FF_DONTCARE = 0x00,
    FF_ROMAN = 0x01,
    FF_SWISS = 0x02,
    FF_MODERN = 0x03,
    FF_SCRIPT = 0x04,
    FF_DECORATIVE = 0x05
} FamilyFont;
```

**FF\_DONTCARE:** The default font is specified, which is implementation-dependent.

**FF\_ROMAN:** Fonts with variable stroke widths, which are proportional to the actual widths of the glyphs, and which have serifs. "MS Serif" is an example.

**FF\_SWISS:** Fonts with variable stroke widths, which are proportional to the actual widths of the glyphs, and which do not have serifs. "MS Sans Serif" is an example.

**FF\_MODERN:** Fonts with constant stroke width, with or without serifs. Fixed-width fonts are usually modern. "Pica", "Elite", and "Courier New" are examples.

**FF\_SCRIPT:** Fonts designed to look like handwriting. "Script" and "Cursive" are examples.

**FF\_DECORATIVE:** Novelty fonts. "Old English" is an example.

In a [Font object \(section 2.2.1.2\)](#), when a **FamilyFont enumeration** value is packed into a byte with a [PitchFont enumeration \(section 2.1.1.24\)](#) value, the result is a [PitchAndFamily object \(section 2.2.2.14\)](#).

### 2.1.1.9 FloodFill Enumeration

The **FloodFill Enumeration** specifies the type of fill operation to be performed.

```
typedef enum
{
    FLOODFILLBORDER = 0x0000,
    FLOODFILLSURFACE = 0x0001
} FloodFill;
```

**FLOODFILLBORDER:** The fill area is bounded by the color specified by the **Color** member. This style is identical to the filling performed by the [META\\_FLOODFILL](#) record.

**FLOODFILLSURFACE:** The fill area is bounded by the color that is specified by the **Color** member. Filling continues outward in all directions as long as the color is encountered. This style is useful for filling areas with multicolored boundaries.

### 2.1.1.10 FontQuality Enumeration

The **FontQuality Enumeration** specifies how closely the attributes of the logical font should match those of the physical font when rendering text.

```
typedef enum
{
    DEFAULT_QUALITY = 0x00,
    DRAFT_QUALITY = 0x01,
    PROOF_QUALITY = 0x02,
    NONANTIALIASED_QUALITY = 0x03,
    ANTIALIASED_QUALITY = 0x04,
    CLEARTYPE_QUALITY = 0x05
} FontQuality;
```

**DEFAULT\_QUALITY:** Specifies that the character quality of the font does not matter, so **DRAFT\_QUALITY** can be used.

**DRAFT\_QUALITY:** Specifies that the character quality of the font is less important than the matching of logical attributes. For **rasterized fonts**, scaling SHOULD be enabled, which means that more font sizes are available.

**PROOF\_QUALITY:** Specifies that the character quality of the font is more important than the matching of logical attributes. For rasterized fonts, scaling SHOULD be disabled, and the font closest in size SHOULD be chosen.

**NONANTIALIASED\_QUALITY:** Specifies that **anti-aliasing** SHOULD NOT be used when rendering text. [<9>](#<9>)

**ANTIALIASED\_QUALITY:** Specifies that anti-aliasing SHOULD be used when rendering text, if the font supports it. [<10>](#<10>)

**CLEARTYPE\_QUALITY:** Specifies that **ClearType** anti-aliasing SHOULD be used when rendering text, if the font supports it. [<11>](#<11>)

Fonts that do not support ClearType anti-aliasing include **type 1 fonts**, **PostScript** fonts, **OpenType** fonts without **TrueType** outlines, rasterized fonts, **vector fonts**, and device fonts.

### 2.1.1.11 GamutMappingIntent Enumeration

The **GamutMappingIntent Enumeration** specifies the relationship between logical and physical colors. [<12>](#<12>)

```
typedef enum
{
    LCS_GM_ABS_COLORIMETRIC = 0x00000008,
    LCS_GM_BUSINESS = 0x00000001,
    LCS_GM_GRAPHICS = 0x00000002,
    LCS_GM_IMAGES = 0x00000004
} GamutMappingIntent;
```

**LCS\_GM\_ABS\_COLORIMETRIC:** Specifies that the **white point** SHOULD be maintained. Typically used when logical colors MUST be matched to their nearest physical color in the destination **color gamut**.

Intent: Match

**ICC** name: Absolute Colorimetric

**LCS\_GM\_BUSINESS:** Specifies that saturation SHOULD be maintained. Typically used for business charts and other situations in which **dithering** is not required.

Intent: Graphic

ICC name: Saturation

**LCS\_GM\_GRAPHICS:** Specifies that a colorimetric match SHOULD be maintained. Typically used for graphic designs and named colors.

Intent: Proof

ICC name: Relative Colorimetric

**LCS\_GM\_IMAGES:** Specifies that contrast SHOULD be maintained. Typically used for photographs and natural images.

Intent: Picture

ICC name: Perceptual

#### 2.1.1.12 HatchStyle Enumeration

The **HatchStyle Enumeration** specifies the hatch pattern.

```
typedef enum
{
    HS_HORIZONTAL = 0x0000,
    HS_VERTICAL = 0x0001,
    HS_FDIAGONAL = 0x0002,
    HS_BDIAGONAL = 0x0003,
    HS_CROSS = 0x0004,
    HS_DIAGCROSS = 0x0005
} HatchStyle;
```

**HS\_HORIZONTAL:** A horizontal hatch.

**HS\_VERTICAL:** A vertical hatch.

**HS\_FDIAGONAL:** A 45-degree downward, left-to-right hatch.

**HS\_BDIAGONAL:** A 45-degree upward, left-to-right hatch.

**HS\_CROSS:** A horizontal and vertical cross-hatch.

**HS\_DIAGCROSS:** A 45-degree crosshatch.

### 2.1.1.13 Layout Enumeration

The **Layout Enumeration** defines options for controlling the direction in which text and graphics are drawn. [<13>](#<13>)

```
typedef enum
{
    LAYOUT_LTR = 0x0000,
    LAYOUT_RTL = 0x0001,
    LAYOUT_BITMAPORIENTATIONPRESERVED = 0x0008
} Layout;
```

**LAYOUT\_LTR:** Sets the default horizontal layout to be left-to-right.

**LAYOUT\_RTL:** Sets the default horizontal layout to be right-to-left. Switching to this layout SHOULD cause the mapping mode in the playback device context to become **MM\_ISOTROPIC** (section [2.1.1.16](#2.1.1.16)).

**LAYOUT\_BITMAPORIENTATIONPRESERVED:** Disables mirroring of bitmaps that are drawn by [META\\_BITBLT](#META_BITBLT) and [META\\_STRETCHBLT](#META_STRETCHBLT) operations, when the layout is right-to-left.

### 2.1.1.14 LogicalColorSpace Enumeration

The **LogicalColorSpace Enumeration** specifies the type of **color space**. [<14>](#<14>)

```
typedef enum
{
    LCS_CALIBRATED_RGB = 0x00000000,
    LCS_sRGB = 0x73524742,
    LCS_WINDOWS_COLOR_SPACE = 0x57696E20
} LogicalColorSpace;
```

**LCS\_CALIBRATED\_RGB:** Color values are calibrated red green blue (RGB) values.

**LCS\_sRGB:** The value is an encoding of the **ASCII** characters "**sRGB**", and it indicates that the color values are sRGB values.

**LCS\_WINDOWS\_COLOR\_SPACE:** The value is an encoding of the ASCII characters "Win ", including the trailing space, and it indicates that the color values are Windows default color space values.

### 2.1.1.15 LogicalColorSpaceV5 Enumeration

The **LogicalColorSpaceV5 Enumeration** is used to specify where to find **color profile** information for a [DeviceIndependentBitmap \(DIB\) Object \(section 2.2.2.9\)](#DeviceIndependentBitmap (DIB) Object (section 2.2.2.9)) that has a header of type [BitmapV5Header Object \(section 2.2.2.5\)](#BitmapV5Header Object (section 2.2.2.5)). [<15>](#<15>)

```
typedef enum
{
    LCS_PROFILE_LINKED = 0x4C494E4B,
    LCS_PROFILE_EMBEDDED = 0x4D424544
} LogicalColorSpaceV5;
```

**LCS\_PROFILE\_LINKED:** The value consists of the string "LINK" from the Windows character set (code page 1252). It indicates that the color profile **MUST** be linked with the DIB Object.

**LCS\_PROFILE\_EMBEDDED:** The value consists of the string "MBED" from the Windows character set (code page 1252). It indicates that the color profile **MUST** be embedded in the DIB Object.

### 2.1.1.16 MapMode Enumeration

The **MapMode Enumeration** defines how logical units are mapped to physical units; that is, assuming that the origins in both the logical and physical coordinate systems are at the same point on the drawing surface, what is the physical coordinate (x',y') that corresponds to logical coordinate (x,y).

For example, suppose the mapping mode is **MM\_TEXT**. Given the following definition of that mapping mode, and an origin (0,0) at the top left corner of the drawing surface, logical coordinate (4,5) would map to physical coordinate (4,5) in pixels.

Now suppose the mapping mode is **MM\_LOENGLISH**, with the same origin as the previous example. Given the following definition of that mapping mode, logical coordinate (4,-5) would map to physical coordinate (0.04,0.05) in inches.

```
typedef enum
{
    MM_TEXT = 0x0001,
    MM_LOMETRIC = 0x0002,
    MM_HIMETRIC = 0x0003,
    MM_LOENGLISH = 0x0004,
    MM_HIENGLISH = 0x0005,
    MM_TWIPS = 0x0006,
    MM_ISOTROPIC = 0x0007,
    MM_ANISOTROPIC = 0x0008
} MapMode;
```

**MM\_TEXT:** Each logical unit is mapped to one device pixel. Positive x is to the right; positive y is down.

**MM\_LOMETRIC:** Each logical unit is mapped to 0.1 millimeter. Positive x is to the right; positive y is up.

**MM\_HIMETRIC:** Each logical unit is mapped to 0.01 millimeter. Positive x is to the right; positive y is up.

**MM\_LOENGLISH:** Each logical unit is mapped to 0.01 inch. Positive x is to the right; positive y is up.

**MM\_HIENGLISH:** Each logical unit is mapped to 0.001 inch. Positive x is to the right; positive y is up.

**MM\_TWIPS:** Each logical unit is mapped to one twentieth (1/20) of a point. In printing, a point is 1/72 of an inch; therefore, 1/20 of a point is 1/1440 of an inch. This unit is also known as a **"twip"**.

Positive x is to the right; positive y is up.

**MM\_ISOTROPIC:** Logical units are mapped to arbitrary device units with equally scaled axes; that is, one unit along the x-axis is equal to one unit along the y-axis. The [META\\_SETWINDOWTEXT](#) and [META\\_SETVIEWPORTEXT](#) records specify the units and the orientation of the axes.

The processing application SHOULD make adjustments as necessary to ensure the x and y units remain the same size. For example, when the window extent is set, the viewport SHOULD be adjusted to keep the units **isotropic**.

**MM\_ANISOTROPIC:** Logical units are mapped to arbitrary units with arbitrarily scaled axes.

### 2.1.1.17 MetafileEscapes Enumeration

The **MetafileEscapes Enumeration** specifies **printer driver** functionality that might not be directly accessible through WMF records defined in the [RecordType Enumeration \(section 2.1.1.1\)](#).

These values are used by [Escape Record Types \(section 2.3.6\)](#).

```
typedef enum
{
    NEWFRAME = 0x0001,
    ABORTDOC = 0x0002,
    NEXTBAND = 0x0003,
    SETCOLORTABLE = 0x0004,
    GETCOLORTABLE = 0x0005,
    FLUSHOUT = 0x0006,
    DRAFTMODE = 0x0007,
    QUERYESCSUPPORT = 0x0008,
    SETABORTPROC = 0x0009,
    STARTDOC = 0x000A,
    ENDDOC = 0x000B,
    GETPHYSPPAGESIZE = 0x000C,
    GETPRINTINGOFFSET = 0x000D,
    GETSCALINGFACTOR = 0x000E,
    META_ESCAPE_ENHANCED_METAFILE = 0x000F,
    SETPENWIDTH = 0x0010,
    SETCOPYCOUNT = 0x0011,
    SETPAPERSOURCE = 0x0012,
    PASSTHROUGH = 0x0013,
    GETTECHNOLOGY = 0x0014,
    SETLINECAP = 0x0015,
    SETLINEJOIN = 0x0016,
    SETMITERLIMIT = 0x0017,
    BANDINFO = 0x0018,
    DRAWPATTERNRECT = 0x0019,
    GETVECTORPENSIZE = 0x001A,
    GETVECTORBRUSHSIZE = 0x001B,
    ENABLEDUPLEX = 0x001C,
    GETSETPAPERBINS = 0x001D,
    GETSETPRINTORIENT = 0x001E,
    ENUMPAPERBINS = 0x001F,
    SETDIBSCALING = 0x0020,
    EPSPRINTING = 0x0021,
    ENUMPAPERMETRICS = 0x0022,
    GETSETPAPERMETRICS = 0x0023,
```

```

POSTSCRIPT_DATA = 0x0025,
POSTSCRIPT_IGNORE = 0x0026,
GETDEVICEUNITS = 0x002A,
GETEXTENDEDTEXTMETRICS = 0x0100,
GETPAIRKERNTABLE = 0x0102,
EXTTEXTOUT = 0x0200,
GETFACENAME = 0x0201,
DOWNLOADFACE = 0x0202,
METAFILE_DRIVER = 0x0801,
QUERYDIBSUPPORT = 0x0C01,
BEGIN_PATH = 0x1000,
CLIP_TO_PATH = 0x1001,
END_PATH = 0x1002,
OPEN_CHANNEL = 0x100E,
DOWNLOADHEADER = 0x100F,
CLOSE_CHANNEL = 0x1010,
POSTSCRIPT_PASSTHROUGH = 0x1013,
ENCAPSULATED_POSTSCRIPT = 0x1014,
POSTSCRIPT_IDENTIFY = 0x1015,
POSTSCRIPT_INJECTION = 0x1016,
CHECKJPEGFORMAT = 0x1017,
CHECKPNGFORMAT = 0x1018,
GET_PS_FEATURESETTING = 0x1019,
MXDC_ESCAPE = 0x101A,
SPCLPASSTHROUGH2 = 0x11D8
} MetafileEscapes;

```

**NEWFRAME:** Notifies the printer driver that the application has finished writing to a page.

**ABORTDOC:** Stops processing the current document.

**NEXTBAND:** Notifies the printer driver that the application has finished writing to a band.

**SETCOLORTABLE:** Sets color table values.

**GETCOLORTABLE:** Gets color table values.

**FLUSHOUT:** Causes all pending output to be flushed to the output device.

**DRAFTMODE:** Indicates that the printer driver SHOULD print text only, and no graphics.

**QUERYESCSUPPORT:** Queries a printer driver to determine whether a specific escape function is supported on the output device it drives.

**SETABORTPROC:** Sets the application-defined function that allows a **print job** to be canceled during printing.

**STARTDOC:** Notifies the printer driver that a new print job is starting.

**ENDDOC:** Notifies the printer driver that the current print job is ending.

**GETPHYSPAGE SIZE:** Retrieves the physical page size currently selected on an output device.

**GETPRINTINGOFFSET:** Retrieves the offset from the upper-left corner of the physical page where the actual printing or drawing begins.

**GETSCALINGFACTOR:** Retrieves the scaling factors for the x-axis and the y-axis of a printer.

**META\_ESCAPE\_ENHANCED\_METAFILE:** Used to embed an enhanced metafile format (EMF) metafile within a WMF metafile.

**SETPENWIDTH:** Sets the width of a pen in pixels.

**SETCOPYCOUNT:** Sets the number of copies.

**SETPAPERSOURCE:** Sets the source, such as a particular paper tray or bin on a printer, for output forms.

**PASSTHROUGH:** This record passes through arbitrary data.

**GETTECHNOLOGY:** Gets information concerning graphics technology that is supported on a device.

**SETLINECAP:** Specifies the line-drawing mode to use in output to a device.

**SETLINEJOIN:** Specifies the line-joining mode to use in output to a device.

**SETMITERLIMIT:** Sets the limit for the length of miter joins to use in output to a device.

**BANDINFO:** Retrieves or specifies settings concerning **banding** on a device, such as the number of bands.

**DRAWPATTERNRECT:** Draws a rectangle with a defined pattern.

**GETVECTORPENSIZE:** Retrieves the physical pen size currently defined on a device.

**GETVECTORBRUSHSIZE:** Retrieves the physical brush size currently defined on a device.

**ENABLEDUPLEX:** Enables or disables double-sided (duplex) printing on a device.

**GETSETPAPERBINS:** Retrieves or specifies the source of output forms on a device.

**GETSETPRINTORIENT:** Retrieves or specifies the paper orientation on a device.

**ENUMPAPERBINS:** Retrieves information concerning the sources of different forms on an output device.

**SETDIBSCALING:** Specifies the scaling of device-independent bitmaps (DIBs).

**EPSPRINTING:** Indicates the start and end of an **encapsulated PostScript (EPS)** section.

**ENUMPAPERMETRICS:** Queries a printer driver for paper dimensions and other forms data.

**GETSETPAPERMETRICS:** Retrieves or specifies paper dimensions and other forms data on an output device.

**POSTSCRIPT\_DATA:** Sends arbitrary PostScript data to an output device.

**POSTSCRIPT\_IGNORE:** Notifies an output device to ignore PostScript data.

**GETDEVICEUNITS:** Gets the device units currently configured on an output device.

**GETEXTENDEDTEXTMETRICS:** Gets extended text metrics currently configured on an output device.

**GETPAIRKERNTABLE:** Gets the font kern table currently defined on an output device.



**EXTTEXTOUT:** Draws text using the currently selected font, background color, and text color.

**GETFACENAME:** Gets the font face name currently configured on a device.

**DOWNLOADFACE:** Sets the font face name on a device.

**METAFILE\_DRIVER:** Queries a printer driver about the support for metafiles on an output device.

**QUERYDIBSUPPORT:** Queries the printer driver about its support for DIBs on an output device.

**BEGIN\_PATH:** Opens a **path**.

**CLIP\_TO\_PATH:** Defines a clip region that is bounded by a path. The input **MUST** be a 16-bit quantity that defines the action to take.

**END\_PATH:** Ends a path.

**OPEN\_CHANNEL:** The same as **STARTDOC** specified with a NULL document and output filename, data in **raw mode**, and a type of zero.

**DOWNLOADHEADER:** Instructs the printer driver to download sets of PostScript procedures.

**CLOSE\_CHANNEL:** The same as **ENDDOC**. See **OPEN\_CHANNEL**.

**POSTSCRIPT\_PASSTHROUGH:** Sends arbitrary data directly to a printer driver, which is expected to process this data only when in PostScript mode. See **POSTSCRIPT\_IDENTIFY**. [<16>](#)

**ENCAPSULATED\_POSTSCRIPT:** Sends arbitrary data directly to the printer driver.

**POSTSCRIPT\_IDENTIFY:** Sets the printer driver to either PostScript or **GDI** mode. [<17>](#)

**POSTSCRIPT\_INJECTION:** Inserts a block of raw data into a PostScript stream. The input **MUST** be a 32-bit quantity specifying the number of bytes to inject, a 16-bit quantity specifying the injection point, and a 16-bit quantity specifying the page number, followed by the bytes to inject. [<18>](#)

**CHECKJPEGFORMAT:** Checks whether the printer supports a JPEG image. [<19>](#)

**CHECKPNGFORMAT:** Checks whether the printer supports a PNG image. [<20>](#)

**GET\_PS\_FEATURESETTING:** Gets information on a specified feature setting for a PostScript printer driver. [<21>](#)

**MXDC\_ESCAPE:** Enables applications to write documents to a file or to a printer in **XML Paper Specification (XPS)** format. [<22>](#)

**SPCLPASSTHROUGH2:** Enables applications to include private procedures and other arbitrary data in documents. [<23>](#)

### 2.1.1.18 MetafileType Enumeration

The **MetafileType Enumeration** specifies where the metafile is stored.

```
typedef enum
{
    MEMORYMETAFILE = 0x0001,
```

```

    DISKMETAFILE = 0x0002
} MetafileType;

```

**MEMORYMETAFILE:** Metafile is stored in memory.

**DISKMETAFILE:** Metafile is stored on disk.

#### 2.1.1.19 MetafileVersion Enumeration

The **MetafileVersion Enumeration** defines values that specify support for device-independent bitmaps (DIBs) in metafiles.

```

typedef enum
{
    METAVERSION100 = 0x0100,
    METAVERSION300 = 0x0300
} MetafileVersion;

```

**METAVERSION100:** DIBs are not supported.

**METAVERSION300:** DIBs are supported.

#### 2.1.1.20 MixMode Enumeration

The **MixMode Enumeration** specifies the background mix mode for text, hatched brushes, and other nonsolid pen styles.

```

typedef enum
{
    TRANSPARENT = 0x0001,
    OPAQUE = 0x0002
} MixMode;

```

**TRANSPARENT:** The background remains untouched.

**OPAQUE:** The background is filled with the background color that is currently defined in the playback device context before the text, hatched brush, or pen is drawn.

#### 2.1.1.21 OutPrecision Enumeration

The **OutPrecision enumeration** defines values for output precision, which is the requirement for the font mapper to match specific font parameters, including height, width, character orientation, escapement, **pitch**, and font type.

```

typedef enum
{
    OUT_DEFAULT_PRECIS = 0x00000000,
    OUT_STRING_PRECIS = 0x00000001,
    OUT_STROKE_PRECIS = 0x00000003,
    OUT_TT_PRECIS = 0x00000004,

```

```

OUT_DEVICE_PRECIS = 0x00000005,
OUT_RASTER_PRECIS = 0x00000006,
OUT_TT_ONLY_PRECIS = 0x00000007,
OUT_OUTLINE_PRECIS = 0x00000008,
OUT_SCREEN_OUTLINE_PRECIS = 0x00000009,
OUT_PS_ONLY_PRECIS = 0x0000000A
} OutPrecision;

```

**OUT\_DEFAULT\_PRECIS:** A value that specifies default behavior.

**OUT\_STRING\_PRECIS:** A value that is returned when rasterized fonts are enumerated.

**OUT\_STROKE\_PRECIS:** A value that is returned when TrueType and other **outline fonts**, and vector fonts are enumerated.

**OUT\_TT\_PRECIS:** A value that specifies the choice of a TrueType font when the system contains multiple fonts with the same name.

**OUT\_DEVICE\_PRECIS:** A value that specifies the choice of a device font when the system contains multiple fonts with the same name.

**OUT\_RASTER\_PRECIS:** A value that specifies the choice of a rasterized font when the system contains multiple fonts with the same name.

**OUT\_TT\_ONLY\_PRECIS:** A value that specifies the requirement for only TrueType fonts. If there are no TrueType fonts installed in the system, default behavior is specified.

**OUT\_OUTLINE\_PRECIS:** A value that specifies the requirement for TrueType and other outline fonts.

**OUT\_SCREEN\_OUTLINE\_PRECIS:** A value that specifies a preference for TrueType and other outline fonts.

**OUT\_PS\_ONLY\_PRECIS:** A value that specifies a requirement for only PostScript fonts. If there are no PostScript fonts installed in the system, default behavior is specified.

### 2.1.1.22 PaletteEntryFlag Enumeration

The **PaletteEntryFlag Enumeration** specifies how the palette entry should be used.

```

typedef enum
{
    PC_RESERVED = 0x01,
    PC_EXPLICIT = 0x02,
    PC_NOCOLLAPSE = 0x04
} PaletteEntryFlag;

```

**PC\_RESERVED:** Specifies that the logical palette entry be used for palette animation. This value prevents other windows from matching colors to the palette entry because the color frequently changes. If an unused system-palette entry is available, the color is placed in that entry. Otherwise, the color is not available for animation.

**PC\_EXPLICIT:** Specifies that the low-order word of the logical palette entry designates a hardware palette index. This value allows the application to show the contents of the display device palette.

**PC\_NOCOLLAPSE:** Specifies that the color be placed in an unused entry in the system palette instead of being matched to an existing color in the system palette. If there are no unused entries in the system palette, the color is matched normally. Once this color is in the system palette, colors in other logical palettes can be matched to this color.

### 2.1.1.23 PenStyle Enumeration

The 16-bit **PenStyle Enumeration** is used to specify different types of pens that can be used in graphics operations.

Various styles can be combined by using a logical OR statement, one from each subsection of Style, EndCap, Join, and Type (Cosmetic).

```
typedef enum
{
    PS_COSMETIC = 0x0000,
    PS_ENDCAP_ROUND = 0x0000,
    PS_JOIN_ROUND = 0x0000,
    PS_SOLID = 0x0000,
    PS_DASH = 0x0001,
    PS_DOT = 0x0002,
    PS_DASHDOT = 0x0003,
    PS_DASHDOTDOT = 0x0004,
    PS_NULL = 0x0005,
    PS_INSIDEFRAME = 0x0006,
    PS_USERSTYLE = 0x0007,
    PS_ALTERNATE = 0x0008,
    PS_ENDCAP_SQUARE = 0x0100,
    PS_ENDCAP_FLAT = 0x0200,
    PS_JOIN_BEVEL = 0x1000,
    PS_JOIN_MITER = 0x2000
} PenStyle;
```

**PS\_COSMETIC:** The pen is cosmetic.

**PS\_ENDCAP\_ROUND:** Line end caps are round.

**PS\_JOIN\_ROUND:** Line joins are round.

**PS\_SOLID:** The pen is solid.

**PS\_DASH:** The pen is dashed.

**PS\_DOT:** The pen is dotted.

**PS\_DASHDOT:** The pen has alternating dashes and dots.

**PS\_DASHDOTDOT:** The pen has dashes and double dots.

**PS\_NULL:** The pen is invisible.

**PS\_INSIDEFRAME:** The pen is solid. When this pen is used in any drawing record that takes a bounding rectangle, the dimensions of the figure are shrunk so that it fits entirely in the bounding rectangle, taking into account the width of the pen.

**PS\_USERSTYLE:** The pen uses a styling array supplied by the user.

**PS\_ALTERNATE:** The pen sets every other pixel (this style is applicable only for cosmetic pens).

**PS\_ENDCAP\_SQUARE:** Line end caps are square.

**PS\_ENDCAP\_FLAT:** Line end caps are flat.

**PS\_JOIN\_BEVEL:** Line joins are beveled.

**PS\_JOIN\_MITER:** Line joins are mitered when they are within the current limit set by the [SETMITERLIMIT META\\_ESCAPE](#) record. A join is beveled when it would exceed the limit.

#### 2.1.1.24 PitchFont Enumeration

The **PitchFont enumeration** defines values that are used for specifying characteristics of a font. The values are used to indicate whether the characters in a font have a fixed or variable width, or pitch.

```
typedef enum
{
    DEFAULT_PITCH = 0,
    FIXED_PITCH = 1,
    VARIABLE_PITCH = 2
} PitchFont;
```

**DEFAULT\_PITCH:** The default pitch, which is implementation-dependent.

**FIXED\_PITCH:** A fixed pitch, which means that all the characters in the font occupy the same width when output in a string.

**VARIABLE\_PITCH:** A variable pitch, which means that the characters in the font occupy widths that are proportional to the actual widths of the glyphs when output in a string. For example, the "i" and space characters usually have much smaller widths than a "W" or "O" character.

In a [Font object \(section 2.2.1.2\)](#), when a [FamilyFont enumeration \(section 2.1.1.8\)](#) value is packed into a byte with a **PitchFont enumeration** value, the result is a [PitchAndFamily object \(section 2.2.2.14\)](#).

#### 2.1.1.25 PolyFillMode Enumeration

The **PolyFillMode Enumeration** specifies the method used for filling a polygon.

```
typedef enum
{
    ALTERNATE = 0x0001,
    WINDING = 0x0002
} PolyFillMode;
```

**ALTERNATE:** Selects alternate mode (fills the area between odd-numbered and even-numbered polygon sides on each scan line).

**WINDING:** Selects winding mode (fills any region with a nonzero winding value).

#### 2.1.1.26 PostScriptCap Enumeration

The **PostScriptCap Enumeration** defines line-ending types for use with a PostScript printer driver.

```
typedef enum
{
    PostScriptNotSet = -2,
    PostScriptFlatCap = 0,
    PostScriptRoundCap = 1,
    PostScriptSquareCap = 2
} PostScriptCap;
```

**PostScriptNotSet:** Specifies that the line-ending style has not been set, and that a default style MAY [<24>](#) be used.

**PostScriptFlatCap:** Specifies that the line ends at the last point. The end is squared off.

**PostScriptRoundCap:** Specifies a circular cap. The center of the circle is the last point in the line. The diameter of the circle is the same as the line width; that is, the thickness of the line.

**PostScriptSquareCap:** Specifies a square cap. The center of the square is the last point in the line. The height and width of the square are the same as the line width; that is, the thickness of the line.

#### 2.1.1.27 PostScriptClipping Enumeration

The [PostScriptClipping Enumeration](#) defines functions that can be applied to the clipping path used for PostScript output.

```
typedef enum
{
    CLIP_SAVE = 0x0000,
    CLIP_RESTORE = 0x0001,
    CLIP_INCLUSIVE = 0x0002
} PostScriptClipping;
```

**CLIP\_SAVE:** Saves the current PostScript clipping path.

**CLIP\_RESTORE:** Restores the PostScript clipping path to the last clipping path that was saved by a previous **CLIP\_SAVE** function applied by a [CLIP TO PATH](#) record (section [2.3.6.6](#)).

**CLIP\_INCLUSIVE:** Intersects the current PostScript clipping path with the current clipping path and saves the result as the new PostScript clipping path.

#### 2.1.1.28 PostScriptFeatureSetting Enumeration

The **PostScriptFeatureSetting Enumeration** defines values that are used to retrieve information about specific features in a PostScript printer driver. [<25>](#)

```
typedef enum
{
    FEATURESETTING_NUP = 0x00000000,
    FEATURESETTING_OUTPUT = 0x00000001,
    FEATURESETTING_PSLEVEL = 0x00000002,
    FEATURESETTING_CUSTPAPER = 0x00000003,
    FEATURESETTING_MIRROR = 0x00000004,
    FEATURESETTING_NEGATIVE = 0x00000005,
    FEATURESETTING_PROTOCOL = 0x00000006,
    FEATURESETTING_PRIVATE_BEGIN = 0x00001000,
    FEATURESETTING_PRIVATE_END = 0x00001FFF
} PostScriptFeatureSetting;
```

**FEATURESETTING\_NUP:** Specifies the **n-up printing** (page layout) setting.

**FEATURESETTING\_OUTPUT:** Specifies PostScript driver output options.

**FEATURESETTING\_PSLEVEL:** Specifies the language level.

**FEATURESETTING\_CUSTPAPER:** Specifies custom paper parameters.

**FEATURESETTING\_MIRROR:** Specifies the mirrored output setting.

**FEATURESETTING\_NEGATIVE:** Specifies the negative output setting.

**FEATURESETTING\_PROTOCOL:** Specifies the output protocol setting.

**FEATURESETTING\_PRIVATE\_BEGIN:** Specifies the start of a range of values that a driver MAY use for retrieving data concerning proprietary features. [<26>](#)

**FEATURESETTING\_PRIVATE\_END:** Specifies the end of a range of values that a driver MAY use for retrieving data concerning proprietary features. [<27>](#)

### 2.1.1.29 PostScriptJoin Enumeration

The **PostScriptJoin Enumeration** defines line-joining capabilities for use with a PostScript printer driver.

```
typedef enum
{
    PostScriptNotSet = -2,
    PostScriptMiterJoin = 0,
    PostScriptRoundJoin = 1,
    PostScriptBevelJoin = 2
} PostScriptJoin;
```

**PostScriptNotSet:** Specifies that the line-joining style has not been set, and that a default style MAY [<28>](#) be used.

**PostScriptMiterJoin:** Specifies a mitered join. This value MUST produce a sharp or clipped corner.

**PostScriptRoundJoin:** Specifies a circular join. This value MUST produce a smooth, circular arc between the lines.

**PostScriptBevelJoin:** Specifies a beveled join. This value MUST produce a diagonal corner.

### 2.1.1.30 StretchMode Enumeration

The **StretchMode Enumeration** specifies the bitmap stretching mode, which defines how the system combines rows or columns of a bitmap with existing pixels.

```
typedef enum
{
    BLACKONWHITE = 0x0001,
    WHITEONBLACK = 0x0002,
    COLORONCOLOR = 0x0003,
    HALFTONE = 0x0004
} StretchMode;
```

**BLACKONWHITE:** Performs a Boolean AND operation by using the color values for the eliminated and existing pixels. If the bitmap is a monochrome bitmap, this mode preserves black pixels at the expense of white pixels. [.<29>](#)

**WHITEONBLACK:** Performs a Boolean OR operation by using the color values for the eliminated and existing pixels. If the bitmap is a monochrome bitmap, this mode preserves white pixels at the expense of black pixels. [.<30>](#)

**COLORONCOLOR:** Deletes the pixels. This mode deletes all eliminated lines of pixels without trying to preserve their information. [.<31>](#)

**HALFTONE:** Maps pixels from the source rectangle into blocks of pixels in the destination rectangle. The average color over the destination block of pixels approximates the color of the source pixels. [.<32>](#)

After setting the **HALFTONE** stretching mode, the brush origin should be set to avoid misalignment artifacts.

### 2.1.1.31 TernaryRasterOperation Enumeration

The **TernaryRasterOperation Enumeration** specifies ternary raster operation codes, which define how to combine the bits in a source bitmap with the bits in a destination bitmap.

```
typedef enum
{
    BLACKNESS = 0x00,
    DPSOON = 0x01,
    DPSONA = 0x02,
    PSOON = 0x03,
    SDPONA = 0x04,
    DPON = 0x05,
    PDSXNON = 0x06,
    PDSAON = 0x07,
    SDPNAA = 0x08,
    PDSXON = 0x09,
    DPNA = 0x0A,
    PSDNAON = 0x0B,
    SPNA = 0x0C,
    PDSNAON = 0x0D,
    PDSNON = 0x0E,
    PN = 0x0F,
    PDSONA = 0x10,
```



NOTSRCERASE = 0x11,  
 SDPXNON = 0x12,  
 SDPAON = 0x13,  
 DPSXNON = 0x14,  
 DPSAON = 0x15,  
 PSDPSANAXX = 0x16,  
 SSPXDSXAXN = 0x17,  
 SPXPDXA = 0x18,  
 SDPSANAXN = 0x19,  
 PDSPAAX = 0x1A,  
 SDPSXAXN = 0x1B,  
 PSDPAOX = 0x1C,  
 DSPDXAXN = 0x1D,  
 PDSOX = 0x1E,  
 PDSOAN = 0x1F,  
 DPSNAA = 0x20,  
 SDPXON = 0x21,  
 DSNA = 0x22,  
 SPDNAON = 0x23,  
 SPXDSXA = 0x24,  
 PDSPANAXN = 0x25,  
 SDPSAAX = 0x26,  
 SDPSXNOX = 0x27,  
 DPSXA = 0x28,  
 PSDPSAAXN = 0x29,  
 DPSANA = 0x2A,  
 SSPXPDAXN = 0x2B,  
 SPDPAOX = 0x2C,  
 PSDNOX = 0x2D,  
 PSDPXAXN = 0x2E,  
 PSDNOAN = 0x2F,  
 PSNA = 0x30,  
 SDPNAON = 0x31,  
 SDPSOAX = 0x32,  
 NOTSRCCOPY = 0x33,  
 SPDPAOX = 0x34,  
 SDPSXNOX = 0x35,  
 SDPOX = 0x36,  
 SDPOAN = 0x37,  
 PSDPOAX = 0x38,  
 SPDNOX = 0x39,  
 SDPSXAXN = 0x3A,  
 SPDNOAN = 0x3B,  
 PSX = 0x3C,  
 SPDSONOX = 0x3D,  
 SDPSNAOX = 0x3E,  
 PSAN = 0x3F,  
 PSDNAA = 0x40,  
 DPSXON = 0x41,  
 SDXPDXA = 0x42,  
 SDPSANAXN = 0x43,  
 SRCERASE = 0x44,  
 DPSNAON = 0x45,  
 DSPDAOX = 0x46,  
 PSDPXAXN = 0x47,  
 SDPXA = 0x48,  
 PSDPDAAXN = 0x49,  
 DPSDOAX = 0x4A,  
 PDSNOX = 0x4B,

SDPANA = 0x4C,  
SSPXDSXOXN = 0x4D,  
PDSPXOX = 0x4E,  
PDSNOAN = 0x4F,  
PDNA = 0x50,  
DSPNAON = 0x51,  
DPSDAOX = 0x52,  
SPDSXAXN = 0x53,  
DPSONON = 0x54,  
DSTINVERT = 0x55,  
DPSOX = 0x56,  
DPSOAN = 0x57,  
PDSPOAX = 0x58,  
DPSNOX = 0x59,  
PATINVERT = 0x5A,  
DPSDONOX = 0x5B,  
DPSDXOX = 0x5C,  
DPSNOAN = 0x5D,  
DPSDNAOX = 0x5E,  
DPAN = 0x5F,  
PDSXA = 0x60,  
DSPDSAOXXN = 0x61,  
DSPDOAX = 0x62,  
SDPNOX = 0x63,  
SDPSOAX = 0x64,  
DSPNOX = 0x65,  
SRCINVERT = 0x66,  
SDPSONOX = 0x67,  
DSPDSNOXXN = 0x68,  
PDSXXN = 0x69,  
DPSAX = 0x6A,  
PSDPSOAXXN = 0x6B,  
SDPAX = 0x6C,  
PDSPDOAXXN = 0x6D,  
SDPSNOAX = 0x6E,  
PDXNAN = 0x6F,  
PDSANA = 0x70,  
SSDXPDXAXN = 0x71,  
SDPSXOX = 0x72,  
SDPNOAN = 0x73,  
DSPDXOX = 0x74,  
DSPNOAN = 0x75,  
SDPSNAOX = 0x76,  
DSAN = 0x77,  
PDSAX = 0x78,  
DSPDSOAXXN = 0x79,  
DPSDNOAX = 0x7A,  
SDPXNAN = 0x7B,  
SPDSNOAX = 0x7C,  
DPSXNAN = 0x7D,  
SPXDSXO = 0x7E,  
DPSAAN = 0x7F,  
DPSAA = 0x80,  
SPXDSXON = 0x81,  
DPSXNA = 0x82,  
SPDSNOAXN = 0x83,  
SDPXNA = 0x84,  
PDSPNOAXN = 0x85,  
DSPDSOAXX = 0x86,

PDSAXN = 0x87,  
 SRCAND = 0x88,  
 SDPSNAOXN = 0x89,  
 DSPNOA = 0x8A,  
 DSPDXOXN = 0x8B,  
 SDPNOA = 0x8C,  
 SDPSXOXN = 0x8D,  
 SSDXPDXAX = 0x8E,  
 PDSANAN = 0x8F,  
 PDSXNA = 0x90,  
 SDPSNOAXN = 0x91,  
 DPSDPOAXX = 0x92,  
 SPDAXN = 0x93,  
 PSDPSOAXX = 0x94,  
 DPSAXN = 0x95,  
 DPSXX = 0x96,  
 PSDPSONOXX = 0x97,  
 SDPSONOXN = 0x98,  
 DSXN = 0x99,  
 DPSNAX = 0x9A,  
 SDPSOAXN = 0x9B,  
 SPDNAX = 0x9C,  
 DSPDOAXN = 0x9D,  
 DSPDSAOXX = 0x9E,  
 PDSXAN = 0x9F,  
 DPA = 0xA0,  
 PDSFNAOXN = 0xA1,  
 DPSNOA = 0xA2,  
 DSPDXOXN = 0xA3,  
 PDSFONOXN = 0xA4,  
 PDXN = 0xA5,  
 DSPNAX = 0xA6,  
 PDSFOAXN = 0xA7,  
 DPSOA = 0xA8,  
 DPSOXN = 0xA9,  
 D = 0xAA,  
 DPSONO = 0xAB,  
 SPDSXAX = 0xAC,  
 DPSDAOXN = 0xAD,  
 DSPNAO = 0xAE,  
 DPNO = 0xAF,  
 PDSNOA = 0xB0,  
 PDSFXOXN = 0xB1,  
 SSPXDSXOX = 0xB2,  
 SDPANAN = 0xB3,  
 PSDNAX = 0xB4,  
 PDSDOAXN = 0xB5,  
 DPSDPAOXX = 0xB6,  
 SDPXAN = 0xB7,  
 PSDPXAX = 0xB8,  
 DSPDAOXN = 0xB9,  
 DPSNAO = 0xBA,  
 MERGEPAINT = 0xBB,  
 SPDSANAX = 0xBC,  
 SDXPDXAN = 0xBD,  
 DPSXO = 0xBE,  
 DPSANO = 0xBF,  
 MERGECOPY = 0xC0,  
 SPDSNAOXN = 0xC1,

SPDSOXN = 0xC2,  
PSXN = 0xC3,  
SPDNOA = 0xC4,  
SPDSXOXN = 0xC5,  
SDPNAX = 0xC6,  
PSDPOAXN = 0xC7,  
SDPOA = 0xC8,  
SPDOXN = 0xC9,  
DPSDXAX = 0xCA,  
SPDSAOXN = 0xCB,  
SRCCOPY = 0xCC,  
SDPONO = 0xCD,  
SDPNAO = 0xCE,  
SPNO = 0xCF,  
PSDNOA = 0xD0,  
PSDPXOXN = 0xD1,  
PDSNAX = 0xD2,  
SPDSOAXN = 0xD3,  
SSPXPDXAX = 0xD4,  
DPSANAN = 0xD5,  
PSDPSAOXX = 0xD6,  
DPSXAN = 0xD7,  
PDSXPXAX = 0xD8,  
SDPSAOXN = 0xD9,  
DPSDANAX = 0xDA,  
SPXDSXAN = 0xDB,  
SPDNAO = 0xDC,  
SDNO = 0xDD,  
SDPXO = 0xDE,  
SDPANO = 0xDF,  
PDSOA = 0xE0,  
PDSOXN = 0xE1,  
DSPDXAX = 0xE2,  
PSDPAOXN = 0xE3,  
SDPSXAX = 0xE4,  
PDSPAOXN = 0xE5,  
SDPSANAX = 0xE6,  
SPXPDXAN = 0xE7,  
SSPXDSXAX = 0xE8,  
DSPDSANAXN = 0xE9,  
DPSAO = 0xEA,  
DPSXNO = 0xEB,  
SDPAO = 0xEC,  
SDPXNO = 0xED,  
SRCPAINT = 0xEE,  
SDPNOO = 0xEF,  
PATCOPY = 0xF0,  
PDSONO = 0xF1,  
PDSNAO = 0xF2,  
PSNO = 0xF3,  
PSDNAO = 0xF4,  
PDNO = 0xF5,  
PDSXO = 0xF6,  
PDSANO = 0xF7,  
PDSAO = 0xF8,  
PDSXNO = 0xF9,  
DPO = 0xFA,  
PATPAINT = 0xFB,  
PSO = 0xFC,

```
PSDNOO = 0xFD,  
DPSOO = 0xFE,  
WHITENESS = 0xFF  
} TernaryRasterOperation;
```

**BLACKNESS:**

**Reverse Polish** = 00000042

**Common** = 0

**DPSOON:**

**Reverse Polish** = 00010289

**Common** = DPSoon

**DPSONA:**

**Reverse Polish** = 00020C89

**Common** = DPSona

**PSON:**

**Reverse Polish** = 000300AA

**Common** = PSON

**SDPONA:**

**Reverse Polish** = 00040C88

**Common** = SDPona

**DPON:**

**Reverse Polish** = 000500A9

**Common** = DPon

**PDSXNON:**

**Reverse Polish** = 00060865

**Common** = PDSxnon

**PDSAON:**

**Reverse Polish** = 000702C5

**Common** = PDSaon

**SDPNAA:**

**Reverse Polish** = 00080F08

**Common** = SDPnaa

**PDSXON:**

**Reverse Polish** = 00090245

**Common** = PDSxon

**DPNA:**

**Reverse Polish** = 000A0329

**Common** = DPna

**PSDNAON:**

**Reverse Polish** = 000B0B2A

**Common** = PSDnaon

**SPNA:**

**Reverse Polish** = 000C0324

**Common** = SPna

**PDSNAON:**

**Reverse Polish** = 000D0B25

**Common** = PDSnaon

**PDSNON:**

**Reverse Polish** = 000E08A5

**Common** = PDSonon

**PN:**

**Reverse Polish** = 000F0001

**Common** = Pn

**PDSONA:**

**Reverse Polish** = 00100C85

**Common** = PDSona

**NOTSRCERASE:**

**Reverse Polish** = 001100A6

**Common** = DSon

**SDPXNON:**

**Reverse Polish** = 00120868

**Common** = SDPxnon

**SDPAON:**

**Reverse Polish** = 001302C8

**Common** = SDPaon

**DPSXNON:**

**Reverse Polish** = 00140869

**Common** = DPSxnon

**DPSAON:**

**Reverse Polish** = 001502C9

**Common** = DPSaon

**PSDPSANAXX:**

**Reverse Polish** = 00165CCA

**Common** = PSDPSanaxx

**SSPXDSXAXN:**

**Reverse Polish** = 00171D54

**Common** = SSPxDSxaxn

**SPXPDXA:**

**Reverse Polish** = 00180D59

**Common** = SPxPDxa

**SDPSANAXN:**

**Reverse Polish** = 00191CC8

**Common** = SDPSanaxn

**PDSPAAX:**

**Reverse Polish** = 001A06C5

**Common** = PDSPaox

**SDPSXAXN:**

**Reverse Polish** = 001B0768

**Common** = SDPSxaxn

**PSDPAOX:**

**Reverse Polish** = 001C06CA

**Common** = PSDPaox

**DSPDXAXN:**

**Reverse Polish** = 001D0766

**Common** = DSPDxaxn

**PDSOX:**

**Reverse Polish** = 001E01A5

**Common** = PDSox

**PDSOAN:**

**Reverse Polish** = 001F0385

**Common** = PDSoan

**DPSNAA:**

**Reverse Polish** = 00200F09

**Common** = DPSnaa

**SDPXON:**

**Reverse Polish** = 00210248

**Common** = SDPxon

**DSNA:**

**Reverse Polish** = 00220326

**Common** = DSna

**SPDNAON:**

**Reverse Polish** = 00230B24

**Common** = SPDnaon

**SPXDSXA:**

**Reverse Polish** = 00240D55

**Common** = SPxDSxa

**PDSPANAXN:**

**Reverse Polish** = 00251CC5

**Common** = PDSPanaxn

**SDPSAOX:**

**Reverse Polish** = 002606C8

**Common** = SDPSaox



**SDPSXNOX:**

**Reverse Polish** = 00271868

**Common** = SDPSxnox

**DPSXA:**

**Reverse Polish** = 00280369

**Common** = DPSxa

**PSDPSAOXXN:**

**Reverse Polish** = 002916CA

**Common** = PSDPSaoxxn

**DPSANA:**

**Reverse Polish** = 002A0CC9

**Common** = DPSana

**SSXPDXAXN:**

**Reverse Polish** = 002B1D58

**Common** = SSPxPDxaxn

**SPDSOAX:**

**Reverse Polish** = 002C0784

**Common** = SPDSoax

**PSDNOX:**

**Reverse Polish** = 002D060A

**Common** = PSDnox

**PSDPXOX:**

**Reverse Polish** = 002E064A

**Common** = PSDPxox

**PSDNOAN:**

**Reverse Polish** = 002F0E2A

**Common** = PSDnoan

**PSNA:**

**Reverse Polish** = 0030032A

**Common** = PSna

**SDPNAON:**

**Reverse Polish** = 00310B28

**Common** = SDPnaon

**SDPSOOX:**

**Reverse Polish** = 00320688

**Common** = SDPSoox

**NOTSRCCOPY:**

**Reverse Polish** = 00330008

**Common** = Sn

**SPDSAUX:**

**Reverse Polish** = 003406C4

**Common** = SPDSaux

**SPDSXNOX:**

**Reverse Polish** = 00351864

**Common** = SPDSxnox

**SDPOX:**

**Reverse Polish** = 003601A8

**Common** = SDPox

**SDPOAN:**

**Reverse Polish** = 00370388

**Common** = SDPoan

**PSDPOAX:**

**Reverse Polish** = 0038078A

**Common** = PSDPoax

**SPDNOX:**

**Reverse Polish** = 0390604

**Common** = SPDnox

**SPDSXOX:**

**Reverse Polish** = 003A0644

**Common** = SPDSxox

**SPDNOAN:**

**Reverse Polish** = 003B0E24

**Common** = SPDnoan

**PSX:**

**Reverse Polish** = 003C004A

**Common** = PSx

**SPDSONOX:**

**Reverse Polish** = 003D18A4

**Common** = SPDSonox

**SPDSNAOX:**

**Reverse Polish** = 003E1B24

**Common** = SPDSnaox

**PSAN:**

**Reverse Polish** = 003F00EA

**Common** = PSan

**PSDNAA:**

**Reverse Polish** = 00400F0A

**Common** = PSDnaa

**DPSXON:**

**Reverse Polish** = 00410249

**Common** = DPSxon

**SDXPDXA:**

**Reverse Polish** = 00420D5D

**Common** = SDxPDxa

**SPDSANAXN:**

**Reverse Polish** = 00431CC4

**Common** = SPDSanaxn

**SRCERASE:**

**Reverse Polish** = 00440328

**Common** = SDna

**DPSNAON:**

**Reverse Polish** = 00450B29

**Common** = DPSnaon

**DSPDAOX:**

**Reverse Polish** = 004606C6

**Common** = DSPDaon

**PSDPXAXN:**

**Reverse Polish** = 0047076A

**Common** = PSDPxaxn

**SDPXA:**

**Reverse Polish** = 00480368

**Common** = SDPxa

**PDSPDAOXXN:**

**Reverse Polish** = 004916C5

**Common** = PDSPDaonxn

**DPSDOAX:**

**Reverse Polish** = 004A0789

**Common** = DPSDoax

**PDSNOX:**

**Reverse Polish** = 004B0605

**Common** = PDSnox

**SDPANA:**

**Reverse Polish** = 004C0CC8

**Common** = SDPana

**SSPXDSXOXN:**

**Reverse Polish** = 004D1954

**Common** = SSPxDSxon

**PDSPXOX:**

**Reverse Polish** = 004E0645

**Common** = PDSPxox

**PDSNOAN:**

**Reverse Polish** = 004F0E25

**Common** = PDSnoan

**PDNA:**

**Reverse Polish** = 00500325

**Common** = PDna

**DSPNAON:**

**Reverse Polish** = 00510B26

**Common** = DSPnaon

**DPSDAOX:**

**Reverse Polish** = 005206C9

**Common** = DPSDaox

**SPDSXAXN:**

**Reverse Polish** = 00530764

**Common** = SPDSxaxn

**DPSNON:**

**Reverse Polish** = 005408A9

**Common** = DPSnon

**DSTINVERT:**

**Reverse Polish** = 00550009

**Common** = Dn

**DPSOX:**

**Reverse Polish** = 005601A9

**Common** = DPSox

**DPSOAN:**

**Reverse Polish** = 000570389

**Common** = DPSoan

**PDSPOAX:**

**Reverse Polish** = 00580785

**Common** = PDSPoax

**DPSNOX:**

**Reverse Polish** = 00590609

**Common** = DPSnox

**PATINVERT:**

**Reverse Polish** = 005A0049

**Common** = DPx

**DPSDONOX:**

**Reverse Polish** = 005B18A9

**Common** = DPSDonox

**DPSDXOX:**

**Reverse Polish** = 005C0649

**Common** = DPSDxox

**DPSNOAN:**

**Reverse Polish** = 005D0E29

**Common** = DPSnoan

**DPSDNAOX:**

**Reverse Polish** = 005E1B29

**Common** = DPSDnaox

**DPAN:**

**Reverse Polish** = 005F00E9

**Common** = DPan

**PDSXA:**

**Reverse Polish** = 00600365

**Common** = PDSxa

**DSPDSA0XXN:**

**Reverse Polish** = 006116C6

**Common** = DSPDSaoxxn

**DSPDOAX:**

**Reverse Polish** = 00620786

**Common** = DSPDoax

**SDPNOX:**

**Reverse Polish** = 00630608

**Common** = SDPnox

**SDPSOAX:**

**Reverse Polish** = 00640788

**Common** = SDPSoax

**DSPNOX:**

**Reverse Polish** = 00650606

**Common** = DSPnox

**SRCINVERT:**

**Reverse Polish** = 00660046

**Common** = DSx

**SDPSONOX:**

**Reverse Polish** = 006718A8

**Common** = SDPSonox

**DSPDSONOXXN:**

**Reverse Polish** = 006858A6

**Common** = DSPDSonoxxn

**PDSXXN:**

**Reverse Polish** = 00690145

**Common** = PDSxxn

**DPSAX:**

**Reverse Polish** = 006A01E9

**Common** = DPSax

**PSDPSOAXXN:**

**Reverse Polish** = 006B178A

**Common** = PSDPSoaxxn

**SDPAX:**

**Reverse Polish** = 006C01E8

**Common** = SDPax

**PDSPDOAXXN:**

**Reverse Polish** = 006D1785

**Common** = PDSPDoaxxn

**SDPSNOAX:**

**Reverse Polish** = 006E1E28

**Common** = SDPSnoax

**PDXNAN:**

**Reverse Polish** = 006F0C65

**Common** = PDXnan

**PDSANA:**

**Reverse Polish** = 00700CC5

**Common** = PDSana

**SSDXPDXAXN:**

**Reverse Polish** = 00711D5C

**Common** = SSDxPDxaxn

**SDPSXOX:**

**Reverse Polish** = 00720648

**Common** = SDPSxox

**SDPNOAN:**

**Reverse Polish** = 00730E28

**Common** = SDPnoan

**DSPDXOX:**

**Reverse Polish** = 00740646

**Common** = DSPDxox

**DSPNOAN:**

**Reverse Polish** = 00750E26

**Common** = DSPnoan

**SDPSNAOX:**

**Reverse Polish** = 00761B28

**Common** = SDPSnaox



**DSAN:**

**Reverse Polish** = 007700E6

**Common** = DSan

**PDSAX:**

**Reverse Polish** = 007801E5

**Common** = PDSax

**DSPDSOAXXN:**

**Reverse Polish** = 00791786

**Common** = DSPDSoaxxn

**DPSDNOAX:**

**Reverse Polish** = 007A1E29

**Common** = DPSDnoax

**SDPXNAN:**

**Reverse Polish** = 007B0C68

**Common** = SDPxnan

**SPDSNOAX:**

**Reverse Polish** = 007C1E24

**Common** = SPDSnoax

**DPSXNAN:**

**Reverse Polish** = 007D0C69

**Common** = DPSxnan

**SPXDSXO:**

**Reverse Polish** = 007E0955

**Common** = SPxDSxo

**DPSAAN:**

**Reverse Polish** = 007F03C9

**Common** = DPSaan

**DPSAA:**

**Reverse Polish** = 008003E9

**Common** = DPSaa

**SPXDSXON:**

**Reverse Polish** = 00810975

**Common** = SPxDSxon

**DPSXNA:**

**Reverse Polish** = 00820C49

**Common** = DPSxna

**SPDSNOAXN:**

**Reverse Polish** = 00831E04

**Common** = SPDSnoaxn

**SDPXNA:**

**Reverse Polish** = 00840C48

**Common** = SDPxna

**PDSPNOAXN:**

**Reverse Polish** = 00851E05

**Common** = PDSPnoaxn

**DSPDSOAXX:**

**Reverse Polish** = 008617A6

**Common** = DSPDSoaxx

**PDSAXN:**

**Reverse Polish** = 008701C5

**Common** = PDSaxn

**SRCAND:**

**Reverse Polish** = 008800C6

**Common** = DSa

**SDPSNAOXN:**

**Reverse Polish** = 00891B08

**Common** = SDPSnaoxn

**DSPNOA:**

**Reverse Polish** = 008A0E06

**Common** = DSPnoa

**DSPDXOXN:**

**Reverse Polish** = 008B0666

**Common** = DSPDxoxn

**SDPNOA:**

**Reverse Polish** = 008C0E08

**Common** = SDPnoa

**SDPSXOXN:**

**Reverse Polish** = 008D0668

**Common** = SDPSxoxn

**SSDXPDXAX:**

**Reverse Polish** = 008E1D7C

**Common** = SSDxPDxax

**PDSANAN:**

**Reverse Polish** = 008F0CE5

**Common** = PDSanan

**PDSXNA:**

**Reverse Polish** = 00900C45

**Common** = PDSxna

**SDPSNOAXN:**

**Reverse Polish** = 00911E08

**Common** = SDPSnoaxn

**DPSDPOAXX:**

**Reverse Polish** = 009217A9

**Common** = DPSDPoaxx

**SPDAXN:**

**Reverse Polish** = 009301C4

**Common** = SPDaxn

**PSDPSOAXX:**

**Reverse Polish** = 009417AA

**Common** = PSDPSoaxx

**DPSAXN:**

**Reverse Polish** = 009501C9

**Common** = DPSaxn

**DPSXX:**

**Reverse Polish** = 00960169

**Common** = DPSxx

**PSDPSONOXX:**

**Reverse Polish** = 0097588A

**Common** = PSDPSonoxx

**SDPSONOXXN:**

**Reverse Polish** = 00981888

**Common** = SDPSonoxn

**DSXN:**

**Reverse Polish** = 00990066

**Common** = DSxn

**DPSNAX:**

**Reverse Polish** = 009A0709

**Common** = DPSnax

**SDPSOAXN:**

**Reverse Polish** = 009B07A8

**Common** = SDPSoaxn

**SPDNAX:**

**Reverse Polish** = 009C0704

**Common** = SPDnax

**DSPDOAXN:**

**Reverse Polish** = 009D07A6

**Common** = DSPDoaxn

**DSPDSA0XX:**

**Reverse Polish** = 009E16E6

**Common** = DSPDSaoxx

**PDSXAN:**

**Reverse Polish** = 009F0345

**Common** = PDSxan

**DPA:**

**Reverse Polish** = 00A000C9

**Common** = DPa

**PDSPNAOXN:**

**Reverse Polish** = 00A11B05

**Common** = PDSPnaoxn

**DPSNOA:**

**Reverse Polish** = 00A20E09

**Common** = DPSnoa

**DPSDXOXN:**

**Reverse Polish** = 00A30669

**Common** = DPSDxoxn

**PDSPONOXN:**

**Reverse Polish** = 00A41885

**Common** = PDSPonoxn

**PDXN:**

**Reverse Polish** = 00A50065

**Common** = PDxn

**DSPNAX:**

**Reverse Polish** = 00A60706

**Common** = DSPnax

**PDSPOAXN:**

**Reverse Polish** = 00A707A5

**Common** = PDSPoaxn

**DPSOA:**

**Reverse Polish** = 00A803A9

**Common** = DPSoa

**DPSOXN:**

**Reverse Polish** = 00A90189

**Common** = DPSoxn

**D:**

**Reverse Polish** = 00AA0029

**Common** = D

**DPSONO:**

**Reverse Polish** = 00AB0889

**Common** = DPSono

**SPDSXAX:**

**Reverse Polish** = 00AC0744

**Common** = SPDSxax

**DPSDAOXN:**

**Reverse Polish** = 00AD06E9

**Common** = DPSDaoxn

**DSPNAO:**

**Reverse Polish** = 00AE0B06

**Common** = DSPnao

**DPNO:**

**Reverse Polish** = 00AF0229

**Common** = DPno

**PDSNOA:**

**Reverse Polish** = 00B00E05

**Common** = PDSnoa

**PDSPXOXN:**

**Reverse Polish** = 00B10665

**Common** = PDSPxoxn

**SSPXDSXOX:**

**Reverse Polish** = 00B21974

**Common** = SSPxDSxox

**SDPANAN:**

**Reverse Polish** = 00B30CE8

**Common** = SDPanan

**PSDNAX:**

**Reverse Polish** = 00B4070A

**Common** = PSDnax

**DPSDOAXN:**

**Reverse Polish** = 00B507A9

**Common** = DPSDoaxn

**DPSDPAOXX:**

**Reverse Polish** = 00B616E9

**Common** = DPSDPaoxx

**SDPXAN:**

**Reverse Polish** = 00B70348

**Common** = SDPxan

**PSDPXAX:**

**Reverse Polish** = 00B8074A

**Common** = PSDPxax

**DSPDAOXN:**

**Reverse Polish** = 00B906E6

**Common** = DSPDaoxn

**DPSNAO:**

**Reverse Polish** = 00BA0B09

**Common** = DPSnao

**MERGEPAINT:**

**Reverse Polish** = 00BB0226

**Common** = DSno

**SPDSANAX:**

**Reverse Polish** = 00BC1CE4

**Common** = SPDSanax

**SDXPDXAN:**

**Reverse Polish** = 00BD0D7D

**Common** = SDxPDxan

**DPSXO:**

**Reverse Polish** = 00BE0269

**Common** = DPSxo

**DPSANO:**

**Reverse Polish** = 00BF08C9

**Common** = DPSano

**MERGECOPY:**

**Reverse Polish** = 00C000CA

**Common** = PSa

**SPDSNAOXN:**

**Reverse Polish** = 00C11B04

**Common** = SPDSnaoxn

**SPDSNOXN:**

**Reverse Polish** = 00C21884

**Common** = SPDSonoxn

**PSXN:**

**Reverse Polish** = 00C3006A

**Common** = PSxn

**SPDNOA:**

**Reverse Polish** = 00C40E04

**Common** = SPDnoa

**SPDSXOXN:**

**Reverse Polish** = 00C50664

**Common** = SPDSxoxn

**SDPNAX:**

**Reverse Polish** = 00C60708

**Common** = SDPnax



**PSDPOAXN:**

**Reverse Polish** = 00C707AA

**Common** = PSDPoaxn

**SDPOA:**

**Reverse Polish** = 00C803A8

**Common** = SDPoa

**SPDOXN:**

**Reverse Polish** = 00C90184

**Common** = SPDoxn

**DPSDXAX:**

**Reverse Polish** = 00CA0749

**Common** = DPSDxax

**SPDSAOXN:**

**Reverse Polish** = 00CB06E4

**Common** = SPDSaoxn

**SRCCOPY:**

**Reverse Polish** = 00CC0020

**Common** = S

**SDPONO:**

**Reverse Polish** = 00CD0888

**Common** = SDPono

**SDPNAO:**

**Reverse Polish** = 00CE0B08

**Common** = SDPnao

**SPNO:**

**Reverse Polish** = 00CF0224

**Common** = SPno

**PSDNOA:**

**Reverse Polish** = 00D00E0A

**Common** = PSDnoa

**PSDPXOXN:**

**Reverse Polish** = 00D1066A

**Common** = PSDPxoxn

**PDSNAX:**

**Reverse Polish** = 00D20705

**Common** = PDSnax

**SPDSOAXN:**

**Reverse Polish** = 00D307A4

**Common** = SPDSoaxn

**SSXPDXAX:**

**Reverse Polish** = 00D41D78

**Common** = SSPxPDxax

**DPSANAN:**

**Reverse Polish** = 00D50CE9

**Common** = DPSanan

**PSDPSAOXX:**

**Reverse Polish** = 00D616EA

**Common** = PSDPSaoxx

**DPSXAN:**

**Reverse Polish** = 00D70349

**Common** = DPSxan

**PDSPXAX:**

**Reverse Polish** = 00D80745

**Common** = PDSPxax

**SDPSAOXN:**

**Reverse Polish** = 00D906E8

**Common** = SDPSaoxn

**DPSDANAX:**

**Reverse Polish** = 00DA1CE9

**Common** = DPSDanax

**SPXDSXAN:**

**Reverse Polish** = 00DB0D75

**Common** = SPxDSxan

**SPDNAO:**

**Reverse Polish** = 00DC0B04

**Common** = SPDnao

**SDNO:**

**Reverse Polish** = 00DD0228

**Common** = SDno

**SDPXO:**

**Reverse Polish** = 00DE0268

**Common** = SDPxo

**SDPANO:**

**Reverse Polish** = 00DF08C8

**Common** = SDPano

**PDSOA:**

**Reverse Polish** = 00E003A5

**Common** = PDSoa

**PDSOXN:**

**Reverse Polish** = 00E10185

**Common** = PDSoxn

**DSPDXAX:**

**Reverse Polish** = 00E20746

**Common** = DSPDxax

**PSDPAOXN:**

**Reverse Polish** = 00E306EA

**Common** = PSDPaoxn

**SDPSXAX:**

**Reverse Polish** = 00E40748

**Common** = SDPSxax

**PDSPAOXN:**

**Reverse Polish** = 00E506E5

**Common** = PDSPaoxn

**SDPSANAX:**

**Reverse Polish** = 00E61CE8

**Common** = SDPSanax

**SPXPDXAN:**

**Reverse Polish** = 00E70D79

**Common** = SPxPDxan

**SSPXDSXAX:**

**Reverse Polish** = 00E81D74

**Common** = SSPxDSxax

**DSPDSANAXXN:**

**Reverse Polish** = 00E95CE6

**Common** = DSPDSanaxxn

**DPSAO:**

**Reverse Polish** = 00EA02E9

**Common** = DPSao

**DPSXNO:**

**Reverse Polish** = 00EB0849

**Common** = DPSxno

**SDPAO:**

**Reverse Polish** = 00EC02E8

**Common** = SDPao

**SDPXNO:**

**Reverse Polish** = 00ED0848

**Common** = SDPxno

**SRCPAINT:**

**Reverse Polish** = 00EE0086

**Common** = DSo

**SDPNOO:**

**Reverse Polish** = 00EF0A08

**Common** = SDPnoo

**PATCOPY:**

**Reverse Polish** = 00F00021

**Common** = P

**PDSONO:**

**Reverse Polish** = 00F10885

**Common** = PDSono

**PDSNAO:**

**Reverse Polish** = 00F20B05

**Common** = PDSnao

**PSNO:**

**Reverse Polish** = 00F3022A

**Common** = PSno

**PSDNAO:**

**Reverse Polish** = 00F40B0A

**Common** = PSDnao

**PDNO:**

**Reverse Polish** = 00F50225

**Common** = PDno

**PDSXO:**

**Reverse Polish** = 00F60265

**Common** = PDSxo

**PDSANO:**

**Reverse Polish** = 00F708C5

**Common** = PDSano

**PDSAO:**

**Reverse Polish** = 00F802E5

**Common** = PDSao

**PDSXNO:**

**Reverse Polish** = 00F90845

**Common** = PDSxno

**DPO:**

**Reverse Polish** = 00FA0089

**Common** = DPO

**PATPAINT:**

**Reverse Polish** = 00FB0A09

**Common** = DPSnno

**PSO:**

**Reverse Polish** = 00FC008A

**Common** = PSo

**PSDNOO:**

**Reverse Polish** = 00FD0A0A

**Common** = PSDnno

**DPSOO:**

**Reverse Polish** = 00FE02A9

**Common** = DPSoo

**WHITENESS:**

**Reverse Polish** = 00FF0062

**Common** = 1

Each ternary raster operation code represents a Boolean operation in which the values of the pixels in the source, the selected brush, and the destination are combined. Following are the three operands used in these operations.

| Operand | Meaning                              |
|---------|--------------------------------------|
| D       | Destination bitmap                   |
| P       | Selected brush (also called pattern) |
| S       | Source bitmap                        |

Following are the Boolean operators used in these operations.

| Operator | Meaning                    |
|----------|----------------------------|
| a        | Bitwise AND                |
| n        | Bitwise NOT (inverse)      |
| o        | Bitwise OR                 |
| x        | Bitwise exclusive OR (XOR) |

All Boolean operations are presented in reverse Polish notation. For example, the following operation replaces the values of the pixels in the destination bitmap with a combination of the pixel values of the source and brush: PSo.

The following operation combines the values of the pixels in the source and brush with the pixel values of the destination bitmap: DPSoo (there are alternative spellings of some functions, so although a particular spelling MAY NOT be listed in the enumeration, an equivalent form SHOULD be).

Each raster operation code is a 32-bit integer whose high-order word is a Boolean operation index and whose low-order word is the operation code. The 16-bit operation index is a zero-extended, 8-bit value that represents the result of the Boolean operation on predefined brush, source, and destination values. For example, the operation indexes for the PSo and DPSoo operations are shown in the following list.

| P | S | D | PSo | DPSoo |
|---|---|---|-----|-------|
| 0 | 0 | 0 | 0   | 0     |
| 0 | 0 | 1 | 0   | 1     |
| 0 | 1 | 0 | 1   | 1     |
| 0 | 1 | 1 | 1   | 1     |
| 1 | 0 | 0 | 1   | 1     |
| 1 | 0 | 1 | 1   | 1     |
| 1 | 1 | 0 | 1   | 1     |
| 1 | 1 | 1 | 1   | 1     |

The operation indexes are determined by reading the binary values in a column of the table from the bottom up. For example, in the PSo column, the binary value is 11111100, which is equivalent to 00FC (hexadecimal is implicit for these values), which is the operation index for PSo.

Using this method, DPSoo can be seen to have the operation index 00FE. Operation indexes define the locations of corresponding raster operation codes in the preceding enumeration. The PSo operation is in line 252 (0x00FC) of the enumeration; DPSoo is in line 254 (0x00FE).

The most commonly used raster operations have been given explicit enumeration names, which SHOULD be used; examples are **PATCOPY** and **WHITENESS**.

When the source and destination bitmaps are monochrome, a bit value of 0 represents a black pixel and a bit value of 1 represents a white pixel. When the source and the destination bitmaps are color, those colors are represented with red green blue (RGB) values.

## 2.1.2 WMF Flags

This section contains constant flag values that are referenced in this specification.

### 2.1.2.1 ClipPrecision Flags

**ClipPrecision Flags** specify clipping precision, which defines how to clip characters that are partially outside a clipping region. These flags can be combined to specify multiple options.

| Constant/value                      | Description  |
|-------------------------------------|--|
| CLIP_DEFAULT_PRECIS<br>0x00000000   | Specifies that default clipping <b>MUST</b> be used.   |
| CLIP_CHARACTER_PRECIS<br>0x00000001 | This value <b>SHOULD NOT</b> be used.  |
| CLIP_STROKE_PRECIS<br>0x00000002    | This value <b>MAY</b> be returned when enumerating rasterized, TrueType and vector fonts. <a href="#">&lt;33&gt;</a>   |
| CLIP_LH_ANGLES<br>0x00000010        | This value is used to control font rotation, as follows: <ul style="list-style-type: none"><li>▪ If set, the rotation for all fonts <b>SHOULD</b> be determined by the orientation of the coordinate system; that is, whether the orientation is left-handed or right-handed.</li><li>▪ If clear, device fonts <b>SHOULD</b> rotate counterclockwise, but the rotation of other fonts <b>SHOULD</b> be determined by the orientation of the coordinate system.</li></ul> |
| CLIP_TT_ALWAYS<br>0x00000020        | This value <b>SHOULD NOT</b> <a href="#">&lt;34&gt;</a> be used.   |
| CLIP_DFA_DISABLE<br>0x00000040      | This value specifies that <b>font association</b> <b>SHOULD</b> <a href="#">&lt;35&gt;</a> be turned off.  |
| CLIP_EMBEDDED<br>0x00000080         | This value specifies that <b>font embedding</b> <b>MUST</b> be used to render document content; embedded fonts are read-only.  |

### 2.1.2.2 ExtTextOutOptions Flags

**ExtTextOutOptions Flags** specify various characteristics of the output of text. These flags can be combined to specify multiple options.

| Constant/value            | Description  |
|---------------------------|--|
| ETO_OPAQUE<br>0x0002      | Indicates that the background color that is defined in the playback device context <b>SHOULD</b> be used to fill the rectangle.  |
| ETO_CLIPPED<br>0x0004     | Indicates that the text <b>SHOULD</b> be clipped to the rectangle.   |
| ETO_GLYPH_INDEX<br>0x0010 | Indicates that the string to be output <b>SHOULD NOT</b> require further processing with respect to the placement of the characters, and an array of character placement values <b>SHOULD</b> be provided. This character placement process is |



| Constant/value              | Description  |
|-----------------------------|--|
|                             | useful for fonts in which diacritical characters affect character spacing. <a href="#">&lt;36&gt;</a>  |
| ETO_RTREADING<br>0x0080     | Indicates that the text MUST be laid out in right-to-left reading order, instead of the default left-to-right order. This SHOULD be applied only when the font that is defined in the playback device context is either Hebrew or Arabic. <a href="#">&lt;37&gt;</a> |
| ETO_NUMERICSLOCAL<br>0x0400 | Indicates that to display numbers, digits appropriate to the locale SHOULD be used. <a href="#">&lt;38&gt;</a>   |
| ETO_NUMERICSLATIN<br>0x0800 | Indicates that to display numbers, European digits SHOULD be used. <a href="#">&lt;39&gt;</a>  |
| ETO_PDY<br>0x2000           | Indicates that both horizontal and vertical character displacement values SHOULD be provided. <a href="#">&lt;40&gt;</a>   |

### 2.1.2.3 TextAlignmentMode Flags

**TextAlignmentMode Flags** specify the relationship between a reference point and a bounding rectangle, for text alignment. These flags can be combined to specify multiple options, with the restriction that only one flag can be chosen that alters the drawing position in the playback device context.

Horizontal text alignment is performed when the font has a horizontal default **baseline**.

| Constant/value          | Description   |
|-------------------------|---|
| TA_NOUPDATECP<br>0x0000 | The drawing position in the playback device context MUST NOT be updated after each text output call. The reference point MUST be passed to the text output function.  |
| TA_LEFT<br>0x0000       | The reference point MUST be on the left edge of the bounding rectangle.   |
| TA_TOP<br>0x0000        | The reference point MUST be on the top edge of the bounding rectangle.  |
| TA_UPDATECP<br>0x0001   | The drawing position in the playback device context MUST be updated after each text output call. It MUST be used as the reference point.  |
| TA_RIGHT<br>0x0002      | The reference point MUST be on the right edge of the bounding rectangle.  |
| TA_CENTER<br>0x0006     | The reference point MUST be aligned horizontally with the center of the bounding rectangle.   |
| TA_BOTTOM<br>0x0008     | The reference point MUST be on the bottom edge of the bounding rectangle.   |
| TA_BASELINE<br>0x0018   | The reference point MUST be on the baseline of the text.  |
| TA_RTREADING<br>0x0100  | The text MUST be laid out in right-to-left reading order, instead of the default left-to-right order. This SHOULD be applied only when the font that is defined in the playback device context is either Hebrew or Arabic. <a href="#">&lt;41&gt;</a> |

**TextAlignmentMode** flags specify three different components of text alignment:

- The horizontal position of the reference point is determined by **TA\_RIGHT** and **TA\_CENTER**; if those bits are clear, the alignment MUST be **TA\_LEFT**.
- The vertical position of the reference point is determined by **TA\_BOTTOM** and **TA\_BASELINE**; if those bits are clear, the alignment MUST be **TA\_TOP**.
- Whether to update the output position in the playback device context after text output is determined by **TA\_UPDATECP**; if that bit is clear, the position MUST NOT be updated.

This is the reason for defining three different zero values in the enumeration; they represent the default states of the three components of text alignment.

#### 2.1.2.4 VerticalTextAlignmentMode Flags

**VerticalTextAlignmentMode** flags specify the relationship between a reference point and a bounding rectangle, for text alignment. These flags can be combined to specify multiple options, with the restriction that only one flag can be chosen that alters the drawing position in the playback device context.

Vertical text alignment is performed when the font has a vertical default baseline, such as Kanji.

| Constant/value         | Description   |
|------------------------|---|
| VTA_TOP<br>0x0000      | The reference point MUST be on the top edge of the bounding rectangle.                    |
| VTA_RIGHT<br>0x0000    | The reference point MUST be on the right edge of the bounding rectangle.                  |
| VTA_BOTTOM<br>0x0002   | The reference point MUST be on the bottom edge of the bounding rectangle.                 |
| VTA_CENTER<br>0x0006   | The reference point MUST be aligned vertically with the center of the bounding rectangle. |
| VTA_LEFT<br>0x0008     | The reference point MUST be on the left edge of the bounding rectangle.                   |
| VTA_BASELINE<br>0x0018 | The reference point MUST be on the baseline of the text.                                  |

When the font that is defined in the playback device context has a vertical default baseline, as with Kanji, **VerticalTextAlignmentMode** flags MUST be used instead of [TextAlignmentMode](#) flags (section [2.1.2.3](#)) where there exists an equivalent.

Both horizontal and vertical flags are named relative to their respective baselines. Thus, **VTA\_LEFT** is the same as **TA\_BOTTOM**, because the bottom edge of the bounding rectangle in normal text orientation becomes the left edge of the bounding rectangle with orientation relative to the vertical baseline.

## 2.2 WMF Objects

This section specifies WMF objects, which are grouped into the following categories:

| Name                   | Section               | Description  |
|------------------------|-----------------------|--|
| Graphics object types  | <a href="#">2.2.1</a> | Specify parameters for graphics output. They are part of the playback device context and can persist over the span of multiple records during the playback of a WMF metafile.                            |
| Structure object types | <a href="#">2.2.2</a> | Specify data structures that are embedded in WMF objects and records. Structure objects, unlike graphics objects, are not explicitly created or deleted; they are components of more complex structures. |

## 2.2.1 Graphics Objects

The WMF Graphics Objects specify parameters for graphics output. They are explicitly created and deleted by records of the [Object Record Types \(section 2.3.4\)](#) during the playback of an WMF metafile. A particular graphics object becomes part of the playback device context (section [3.1.5](#)) when it is selected by an appropriate object record, and it is reused in subsequent graphics operations until a different object is selected.

The following types of Graphics Objects are defined:

| Name    | Section                 | Description  |
|---------|-------------------------|--|
| Brush   | <a href="#">2.2.1.1</a> | Specifies a graphics brush for the filling of figures.   |
| Font    | <a href="#">2.2.1.2</a> | Specifies properties that determine the appearance of text, including typeface, size, and style. |
| Palette | <a href="#">2.2.1.3</a> | Specifies colors as device-independent values, which can be defined entirely by an application.  |
| Pen     | <a href="#">2.2.1.4</a> | Specifies a graphics pen for the drawing of lines.   |
| Region  | <a href="#">2.2.1.5</a> | Specifies line and curve segments that define a shape.   |

An implementation is responsible for keeping track of graphics objects during playback of the metafile. An abstract model for managing WMF graphics objects is described in [WMF Object Table \(section 3.1.4.1\)](#).

### 2.2.1.1 Brush Object

The Brush Object defines the style, color, and pattern of a brush. Brush Objects are created by the [META\\_CREATEBRUSHINDIRECT](#), [META\\_CREATEPATTERNBRUSH](#) and [META\\_DIBCREATEPATTERNBRUSH](#) records.

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                    | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| BrushStyle |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BrushHatch (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**BrushStyle (2 bytes):** A 16-bit unsigned integer that defines the brush style. The value MUST be an enumeration from the [BrushStyle Enumeration](#) table. For the meanings of the different values, see the following table.

**ColorRef (4 bytes):** A 32-bit field that specifies how to interpret color values in the object defined in the **BrushHatch** field. Its interpretation depends on the value of **BrushStyle**, as explained in the following table.

**BrushHatch (variable):** A variable-size field that contains the brush hatch or pattern data. The content depends on the value of **BrushStyle**, as explained below.

The **BrushStyle** field determines how the **ColorRef** and **BrushHatch** fields SHOULD be interpreted, as specified in the following table.

The following table shows the relationship between the **BrushStyle**, **ColorRef**, and **BrushHatch** fields in a Brush Object.

| BrushStyle      | ColorRef   | BrushHatch   |
|-----------------|--|--|
| BS_SOLID        | SHOULD be a <a href="#">ColorRef Object</a> , specified in section <a href="#">2.2.2.8</a> .   | Not used, and SHOULD be ignored.   |
| BS_NULL         | SHOULD be ignored.   | Not used, and SHOULD be ignored.   |
| BS_PATTERN      | SHOULD be ignored.   | SHOULD be a <a href="#">Bitmap16 Object</a> , specified in section <a href="#">2.2.2.1</a> , which defines the brush pattern.                                    |
| BS_DIBPATTERNPT | SHOULD be a 32-bit <a href="#">ColorUsage Enumeration</a> value, specified in section <a href="#">2.1.1.6</a> ; the low-order word specifies the meaning of color values in the DIB. | SHOULD be a <a href="#">DIB Object</a> , specified in section <a href="#">2.2.2.9</a> , which defines the brush pattern.   |
| BS_HATCHED      | SHOULD be a ColorRef Object, specified in section <a href="#">2.2.2.8</a> .  | SHOULD be a 16-bit value from the <a href="#">HatchStyle Enumeration</a> table, specified in section <a href="#">2.1.1.12</a> , which defines the brush pattern. |

### 2.2.1.2 Font Object

The Font object specifies the attributes of a logical font.

|            |   |   |   |   |   |   |   |                |   |    |    |    |    |    |    |                     |    |    |    |    |    |    |    |               |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|----------------|---|----|----|----|----|----|----|---------------------|----|----|----|----|----|----|----|---------------|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8              | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                  | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24            | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Height     |   |   |   |   |   |   |   |                |   |    |    |    |    |    |    | Width               |    |    |    |    |    |    |    |               |    |    |    |    |    |    |    |
| Escapement |   |   |   |   |   |   |   |                |   |    |    |    |    |    |    | Orientation         |    |    |    |    |    |    |    |               |    |    |    |    |    |    |    |
| Weight     |   |   |   |   |   |   |   |                |   |    |    |    |    |    |    | Italic              |    |    |    |    |    |    |    | Underline     |    |    |    |    |    |    |    |
| StrikeOut  |   |   |   |   |   |   |   | CharSet        |   |    |    |    |    |    |    | OutPrecision        |    |    |    |    |    |    |    | ClipPrecision |    |    |    |    |    |    |    |
| Quality    |   |   |   |   |   |   |   | PitchAndFamily |   |    |    |    |    |    |    | Facename (variable) |    |    |    |    |    |    |    |               |    |    |    |    |    |    |    |

|     |
|-----|
| ... |
|-----|

**Height (2 bytes):** A 16-bit signed integer that specifies the height, in logical units, of the font's character cell. The character height is computed as the character cell height minus the internal leading. The font mapper SHOULD interpret the height as follows.

| Value                 | Meaning   |
|-----------------------|---|
| <i>value</i> < 0x0000 | The font mapper SHOULD transform this value into device units and match its absolute value against the character height of available fonts. |
| 0x0000                | A default height value MUST be used when creating a physical font.  |
| 0x0000 < <i>value</i> | The font mapper SHOULD transform this value into device units and match it against the cell height of available fonts.                      |

For all height comparisons, the font mapper SHOULD find the largest physical font that does not exceed the requested size. [<42>](#)

**Width (2 bytes):** A 16-bit signed integer that defines the average width, in logical units, of characters in the font. If **Width** is 0x0000, the aspect ratio of the device SHOULD be matched against the digitization aspect ratio of the available fonts to find the closest match, determined by the absolute value of the difference.

**Escapement (2 bytes):** A 16-bit signed integer that defines the angle, in tenths of degrees, between the escapement vector and the x-axis of the device. The escapement vector is parallel to the base line of a row of text.

**Orientation (2 bytes):** A 16-bit signed integer that defines the angle, in tenths of degrees, between each character's base line and the x-axis of the device.

**Weight (2 bytes):** A 16-bit signed integer that defines the weight of the font in the range 0 through 1000. For example, 400 is normal and 700 is bold. If this value is 0x0000, a default weight SHOULD be used.

**Italic (1 byte):** A 8-bit Boolean value that specifies the italic attribute of the font.

| Value         | Meaning                     |
|---------------|-----------------------------|
| FALSE<br>0x00 | This is not an italic font. |
| TRUE<br>0x01  | This is an italic font.     |

**Underline (1 byte):** An 8-bit Boolean value that specifies the underline attribute of the font.

| Value         | Meaning                        |
|---------------|--------------------------------|
| FALSE<br>0x00 | This is not an underline font. |
| TRUE<br>0x01  | This is an underline font.     |

**StrikeOut (1 byte):** An 8-bit Boolean value that specifies the strikeout attribute of the font.

| Value         | Meaning                       |
|---------------|-------------------------------|
| FALSE<br>0x00 | This is not a strikeout font. |
| TRUE<br>0x01  | This is a strikeout font.     |

**CharSet (1 byte):** An 8-bit unsigned integer that defines the character set. It SHOULD be set to a value in the [CharacterSet Enumeration \(section 2.1.1.5\)](#).

The DEFAULT\_CHARSET value MAY be used to allow the name and size of a font to fully describe the logical font. If the specified font name does not exist, a font in another character set MAY be substituted. The DEFAULT\_CHARSET value is set to a value based on the current system locale. For example, when the system locale is United States, it is set to ANSI\_CHARSET.

If a typeface name in the **FaceName** field is specified, the **CharSet** value MUST match the character set of that typeface.

**OutPrecision (1 byte):** An 8-bit unsigned integer that defines the output precision. The output precision defines how closely the output must match the requested font's height, width, character orientation, escapement, pitch, and font type. It MUST be one of the values from the [OutPrecision Enumeration \(section 2.1.1.21\)](#).

Applications can use the OUT\_DEVICE\_PRECIS, OUT\_RASTER\_PRECIS, OUT\_TT\_PRECIS, and OUT\_PS\_ONLY\_PRECIS values to control how the font mapper selects a font when the operating system contains more than one font with a specified name. For example, if an operating system contains a font named "Symbol" in raster and TrueType forms, specifying OUT\_TT\_PRECIS forces the font mapper to select the TrueType version. Specifying OUT\_TT\_ONLY\_PRECIS forces the font mapper to select a TrueType font, even if it substitutes a TrueType font of another name.

**ClipPrecision (1 byte):** An 8-bit unsigned integer that defines the clipping precision. The clipping precision defines how to clip characters that are partially outside the clipping region. It MUST be a combination of one or more of the bit settings in the [ClipPrecision Flags \(section 2.1.2.1\)](#).

**Quality (1 byte):** An 8-bit unsigned integer that defines the output quality. The output quality defines how carefully to attempt to match the logical font attributes to those of an actual physical font. It MUST be one of the values in the [FontQuality Enumeration \(section 2.1.1.10\)](#).

**PitchAndFamily (1 byte):** A [PitchAndFamily object \(section 2.2.2.14\)](#) that defines the pitch and the family of the font. Font families specify the look of fonts in a general way and are intended for specifying fonts when the exact typeface wanted is not available.

**Facename (variable):** A null-terminated string of 8-bit Latin-1 [ISO/IEC-8859-1](#) ANSI characters that specifies the typeface name of the font. The length of this string MUST NOT exceed 32 8-bit characters, including the terminating null.

### 2.2.1.3 Palette Object

The Palette Object specifies the colors in a logical palette.

|                            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0                          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| Start                      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | NumberOfEntries |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| aPaletteEntries (variable) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...                        |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**Start (2 bytes):** A 16-bit unsigned integer that defines the offset into the Palette Object when used with the [META\\_SETPALENTRIES](#) and [META\\_ANIMATEPALETTE](#) record types. When used with [META\\_CREATEPALETTE](#), it MUST be 0x0300.

**NumberOfEntries (2 bytes):** A 16-bit unsigned integer that defines the number of objects in aPaletteEntries.

**aPaletteEntries (variable):** An array of **NumberOfEntries** 32-bit [PaletteEntry Objects](#).

#### 2.2.1.4 Pen Object

The Pen Object specifies the style, width, and color of a pen.

|          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0        | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| PenStyle |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Width    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**PenStyle (2 bytes):** A 16-bit unsigned integer that specifies the pen style. The value MUST be defined from the [PenStyle Enumeration](#) table.

**Width (4 bytes):** A 32-bit [PointS Object](#) that specifies a point for the object dimensions. The x-coordinate is the pen width. The y-coordinate is ignored.

**ColorRef (4 bytes):** A 32-bit [ColorRef Object](#) that specifies the pen color value.

#### 2.2.1.5 Region Object

The Region Object defines a potentially non-rectilinear shape defined by an array of **scanlines**.

|             |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0           | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| nextInChain |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ObjectType |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ObjectCount |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|            |                   |
|------------|-------------------|
| RegionSize | ScanCount         |
| maxScan    | BoundingBox       |
| ...        |                   |
| ...        | aScans (variable) |
| ...        |                   |

**nextInChain (2 bytes):** A value that MUST be ignored. [<43>](#)

**ObjectType (2 bytes):** A 16-bit signed integer that specifies the region identifier. It MUST be 0x0006.

**ObjectCount (4 bytes):** A value that MUST be ignored. [<44>](#)

**RegionSize (2 bytes):** A 16-bit signed integer that defines the size of the region in bytes plus the size of **aScans** in bytes.

**ScanCount (2 bytes):** A 16-bit signed integer that defines the number of scanlines composing the region.

**maxScan (2 bytes):** A 16-bit signed integer that defines the maximum number of points in any one scan in this region.

**BoundingBox (8 bytes):** A [Rect object \(section 2.2.2.18\)](#) that defines the bounding rectangle.

**aScans (variable):** An array of [Scan objects \(section 2.2.2.21\)](#) that define the scanlines in the region.

## 2.2.2 Structure Objects

The WMF Structure Objects specify data structures that are embedded in WMF objects and records. Structure objects, unlike graphics objects, are not explicitly created or deleted; they are components of more complex structures.

### 2.2.2.1 Bitmap16 Object

The Bitmap16 Object specifies information about the dimensions and color format of a bitmap.

|        |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|---|---|-----------|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8         | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Type   |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    | Width           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Height |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    | WidthBytes      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Planes |   |   |   |   |   |   |   | BitsPixel |   |    |    |    |    |    |    | Bits (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |



...

- Type (2 bytes):** A 16-bit signed integer that defines the bitmap type.
- Width (2 bytes):** A 16-bit signed integer that defines the width of the bitmap in pixels.
- Height (2 bytes):** A 16-bit signed integer that defines the height of the bitmap in scan lines.
- WidthBytes (2 bytes):** A 16-bit signed integer that defines the number of bytes per scan line.
- Planes (1 byte):** An 8-bit unsigned integer that defines the number of color planes in the bitmap. The value of this field MUST be 0x01.
- BitsPixel (1 byte):** An 8-bit unsigned integer that defines the number of adjacent color bits on each plane.
- Bits (variable):** A variable length array of bytes that defines the bitmap pixel data. The length of this field in bytes can be computed as follows.

$$(((Width * BitsPixel + 15) >> 4) << 1) * Height$$

2.2.2.2 BitmapCoreHeader Object

The BitmapCoreHeader Object contains information about the dimensions and color format of a device-independent bitmap (DIB).<45>

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| HeaderSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Planes     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BitCount |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

- HeaderSize (4 bytes):** A 32-bit unsigned integer that defines the size of this object, in bytes.
- Width (2 bytes):** A 16-bit unsigned integer that defines the width of the DIB, in pixels.
- Height (2 bytes):** A 16-bit unsigned integer that defines the height of the DIB, in pixels.
- Planes (2 bytes):** A 16-bit unsigned integer that defines the number of planes for the target device. This value MUST be 0x0001.
- BitCount (2 bytes):** A 16-bit unsigned integer that defines the format of each pixel, and the maximum number of colors in the DIB. This value MUST be in the [BitCount Enumeration \(section 2.1.1.3\)](#).

A DIB is specified by a [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#).

### 2.2.2.3 BitmapInfoHeader Object

The BitmapInfoHeader Object contains information about the dimensions and color format of a device-independent bitmap (DIB).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6        | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| HeaderSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Width          |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Height         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Planes         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | BitCount |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Compression    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ImageSize      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XPelsPerMeter  |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| YPelsPerMeter  |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorUsed      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorImportant |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**HeaderSize (4 bytes):** A 32-bit unsigned integer that defines the size of this object, in bytes.

**Width (4 bytes):** A 32-bit signed integer that defines the width of the DIB, in pixels. This value MUST be positive.

This field SHOULD [≤46>](#) specify the width of the decompressed image file, if the **Compression** value specifies JPEG or PNG format.

**Height (4 bytes):** A 32-bit signed integer that defines the height of the DIB, in pixels. This value MUST NOT be zero.

| Value                     | Meaning  |
|---------------------------|--|
| 0x00000000 < <i>value</i> | If this value is positive, the DIB is a bottom-up bitmap, and its origin is the lower-left corner.<br>This field SHOULD <a href="#">≤47&gt;</a> specify the height of the decompressed image file, if the <b>Compression</b> value specifies JPEG or PNG format. |
| <i>value</i> < 0x00000000 | If this value is negative, the DIB is a top-down bitmap, and its origin is the upper-left corner. Top-down bitmaps do not support compression.   |

**Planes (2 bytes):** A 16-bit unsigned integer that defines the number of planes for the target device. This value MUST be 0x0001.

**BitCount (2 bytes):** A 16-bit unsigned integer that defines the number of bits that define each pixel and the maximum number of colors in the DIB. This value MUST be in the [BitCount Enumeration \(section 2.1.1.3\)](#).

**Compression (4 bytes):** A 32-bit unsigned integer that defines the compression mode of the DIB. This value MUST be in the [Compression Enumeration \(section 2.1.1.7\)](#).

This value MUST NOT specify a compressed format if the DIB is a top-down bitmap, as indicated by the **Height** value.

**ImageSize (4 bytes):** A 32-bit unsigned integer that defines the size, in bytes, of the image.

If the **Compression** value is BI\_RGB, this value SHOULD be zero and MUST be ignored. [<48>](#)

If the **Compression** value is BI\_JPEG or BI\_PNG, this value MUST specify the size of the JPEG or PNG image buffer, respectively.

**XPelsPerMeter (4 bytes):** A 32-bit signed integer that defines the horizontal resolution, in pixels-per-meter, of the target device for the DIB.

**YPelsPerMeter (4 bytes):** A 32-bit signed integer that defines the vertical resolution, in pixels-per-meter, of the target device for the DIB.

**ColorUsed (4 bytes):** A 32-bit unsigned integer that specifies the number of indexes in the color table used by the DIB, as follows:

- If this value is zero, the DIB uses the maximum number of colors that correspond to the **BitCount** value.
- If this value is nonzero and the **BitCount** value is less than 16, this value specifies the number of colors used by the DIB.
- If this value is nonzero and the **BitCount** value is 16 or greater, this value specifies the size of the color table used to optimize performance of the system palette.

**Note** If this value is nonzero and greater than the maximum possible size of the color table based on the **BitCount** value, the maximum color table size SHOULD be assumed.

**ColorImportant (4 bytes):** A 32-bit unsigned integer that defines the number of color indexes that are required for displaying the DIB. If this value is zero, all color indexes are required.

A DIB is specified by a [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#).

When the array of pixels in the DIB immediately follows the BitmapInfoHeader, the DIB is a **packed bitmap**. In a packed bitmap, the **ColorUsed** value MUST be either 0x00000000 or the actual size of the color table.

#### 2.2.2.4 BitmapV4Header Object

The BitmapV4Header Object contains information about the dimensions and color format of a device-independent bitmap (DIB). It is an extension of the [BitmapInfoHeader](#) object (section [2.2.2.3](#)). [<49>](#)

|                                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------------------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                                    | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| BitmapInfoHeader                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| (BitmapInfoHeader cont'd for 2 rows) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RedMask                              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| GreenMask                            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| BlueMask                             |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| AlphaMask                            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ColorSpaceType                       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Endpoints                            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|            |
|------------|
| ...        |
| GammaRed   |
| GammaGreen |
| GammaBlue  |

**BitmapInfoHeader (40 bytes):** A [BitmapInfoHeader](#) object, which defines properties of the DIB.

**RedMask (4 bytes):** A 32-bit unsigned integer that defines the color mask that specifies the red component of each pixel. If the **Compression** value in the [BitmapInfoHeader](#) object is not BI\_BITFIELDS, this value MUST be ignored.

**GreenMask (4 bytes):** A 32-bit unsigned integer that defines the color mask that specifies the green component of each pixel. If the **Compression** value in the [BitmapInfoHeader](#) object is not BI\_BITFIELDS, this value MUST be ignored.

**BlueMask (4 bytes):** A 32-bit unsigned integer that defines the color mask that specifies the blue component of each pixel. If the **Compression** value in the [BitmapInfoHeader](#) object is not BI\_BITFIELDS, this value MUST be ignored.

**AlphaMask (4 bytes):** A 32-bit unsigned integer that defines the color mask that specifies the alpha component of each pixel.

**ColorSpaceType (4 bytes):** A 32-bit unsigned integer that defines the color space of the [Device Independent Bitmap](#) object (section 2.2.2.9). If this value is LCS\_CALIBRATED\_RGB from the [LogicalColorSpace](#) enumeration (section 2.1.1.14), the color values in the DIB are calibrated RGB values, and the endpoints and **gamma** values in this structure SHOULD be used to translate the color values before they are passed to the device.

See the [LogColorSpace](#) objects (sections 2.2.2.11 and 2.2.2.12) for details concerning a logical color space.

**Endpoints (36 bytes):** A [CIEXYZTriple](#) object (section 2.2.2.7) that defines the **CIE** chromaticity x, y, and z coordinates of the three colors that correspond to the red, green, and blue endpoints for the logical color space associated with the DIB. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaRed (4 bytes):** A 32-bit fixed point value that defines the toned response curve for red. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaGreen (4 bytes):** A 32-bit fixed point value that defines the toned response curve for green. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaBlue (4 bytes):** A 32-bit fixed point value that defines the toned response curve for blue. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

The gamma value format is an unsigned "8.8" fixed-point integer that is then left-shifted by 8 bits. "8.8" means "8 integer bits followed by 8 fraction bits": nnnnnnnnffffffff. Taking the shift into account, the required format of the 32-bit DWORD is: 00000000nnnnnnnnffffffff00000000.

2.2.2.5 BitmapV5Header Object

The BitmapV5Header Object contains information about the dimensions and color format of a device-independent bitmap (DIB). It is an extension of the [BitmapV4Header](#) object (section 2.2.2.4). [<50>](#)

|                                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| BitmapV4Header                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| (BitmapV4Header cont'd for 19 rows) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Intent                              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ProfileData                         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ProfileSize                         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved                            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**BitmapV4Header (108 bytes):** A [BitmapV4Header](#) object, which defines properties of the DIB.

When it is part of a BitmapV5Header, the **ColorSpaceType** field of a BitmapV4Header can be a logical color space value in the [LogicalColorSpaceV5](#) enumeration (section 2.1.1.15).

**Intent (4 bytes):** A 32-bit unsigned integer that defines the rendering intent for the DIB. This MUST be defined in the [LogicalColorSpace](#) enumeration (section 2.1.1.14).

**ProfileData (4 bytes):** A 32-bit unsigned integer that defines the offset, in bytes, from the beginning of this structure to the start of the color profile data.

If the color profile is embedded in the DIB, **ProfileData** is the offset to the actual color profile; if the color profile is linked, **ProfileData** is the offset to the null-terminated file name of the color profile. This MUST NOT be a Unicode string, but MUST be composed exclusively of characters from the Windows character set (code page 1252).

If the **ColorSpaceType** field in the BitmapV4Header does not specify LCS\_PROFILE\_LINKED or LCS\_PROFILE\_EMBEDDED, the color profile data SHOULD be ignored.

**ProfileSize (4 bytes):** A 32-bit unsigned integer that defines the size, in bytes, of embedded color profile data.

**Reserved (4 bytes):** A 32-bit unsigned integer that is undefined and SHOULD be ignored.

## 2.2.2.6 CIEXYZ Object

The CIEXYZ Object defines information about the **CIEXYZ** chromaticity object.

|         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|---------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| ciexyzX |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ciexyzY |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ciexyzZ |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**ciexyzX (4 bytes):** A 32-bit 2.30 fixed point type that defines the x chromaticity value.

**ciexyzY (4 bytes):** A 32-bit 2.30 fixed point type that defines the y chromaticity value.

**ciexyzZ (4 bytes):** A 32-bit 2.30 fixed point type that defines the z chromaticity value.

## 2.2.2.7 CIEXYZTriple Object

The CIEXYZTriple Object defines information about the CIEXYZTriple color object.

|             |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|-------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0           | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| ciexyzRed   |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ciexyzGreen |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

|            |
|------------|
| ciexyzBlue |
| ...        |
| ...        |

**ciexyzRed (12 bytes):** A 96-bit [CIEXYZ Object](#) that defines the red chromaticity values.

**ciexyzGreen (12 bytes):** A 96-bit CIEXYZ Object that defines the green chromaticity values.

**ciexyzBlue (12 bytes):** A 96-bit CIEXYZ Object that defines the blue chromaticity values.

### 2.2.2.8 ColorRef Object

The ColorRef Object defines the RGB color.

|     |   |   |   |   |   |   |   |       |   |    |    |    |    |    |    |      |    |    |    |    |    |    |    |          |    |    |    |    |    |    |    |
|-----|---|---|---|---|---|---|---|-------|---|----|----|----|----|----|----|------|----|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|
| 0   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8     | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16   | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24       | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Red |   |   |   |   |   |   |   | Green |   |    |    |    |    |    |    | Blue |    |    |    |    |    |    |    | Reserved |    |    |    |    |    |    |    |

**Red (1 byte):** An 8-bit unsigned integer that defines the relative intensity of red.

**Green (1 byte):** An 8-bit unsigned integer that defines the relative intensity of green.

**Blue (1 byte):** An 8-bit unsigned integer that defines the relative intensity of blue.

**Reserved (1 byte):** An 8-bit unsigned integer that MUST be 0x00.

### 2.2.2.9 DeviceIndependentBitmap Object

The DeviceIndependentBitmap Object defines an image in device-independent bitmap (DIB) format.

|                          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                        | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| DIBHeaderInfo (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Colors (variable)        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| BitmapBuffer (variable)  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**DIBHeaderInfo (variable):** Either a [BitmapCoreHeader Object \(section 2.2.2.2\)](#) or a [BitmapInfoHeader Object \(section 2.2.2.3\)](#) that specifies information about the image.



The first 32 bits of this field is the **HeaderSize** value. If it is 0x0000000C, then this is a BitmapCoreHeader; otherwise, this is a BitmapInfoHeader.

**Colors (variable):** An optional array of either [RGBQuad Objects \(section 2.2.2.20\)](#) or 16-bit unsigned integers that define a color table.

The size and contents of this field SHOULD be determined from the metafile record or object that contains this DeviceIndependentBitmap and from information in the **DIBHeaderInfo** field. See [ColorUsage Enumeration \(section 2.1.1.6\)](#) and [BitCount Enumeration \(section 2.1.1.3\)](#) for additional details.

**BitmapBuffer (variable):** A buffer containing the image, which is not required to be contiguous with the DIB header, unless this is a packed bitmap.

|                           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                         | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| UndefinedSpace (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| aData (variable)          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**UndefinedSpace (variable):** An optional field that MUST be ignored. If this DIB is a packed bitmap, this field MUST NOT be present.

**aData (variable):** An array of bytes that define the image.

The size and format of this data is determined by information in the **DIBHeaderInfo** field. If it is a BitmapCoreHeader, the size in bytes MUST be calculated as follows:

$((\text{Width} * \text{Planes} * \text{BitCount} + 31) \& \sim 31) / 8 * \text{abs}(\text{Height})$

This formula SHOULD also be used to calculate the size of **aData** when **DIBHeaderInfo** is a BitmapInfoHeader Object, using values from that object, but only if its **Compression** value is BI\_RGB, BI\_BITFIELDS, or BI\_CMYK.

Otherwise, the size of **aData** MUST be the BitmapInfoHeader Object value **ImageSize**.

## 2.2.2.10 LogBrush Object

The LogBrush Object defines the style, color, and pattern of a brush. This object is used only in the [META\\_CREATEBRUSHINDIRECT Record \(section 2.3.4.1\)](#) to create a [Brush Object \(section 2.2.1.1\)](#).

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| BrushStyle |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|     |            |
|-----|------------|
| ... | BrushHatch |
|-----|------------|

**BrushStyle (2 bytes):** A 16-bit unsigned integer that defines the brush style. This MUST be a value from the [BrushStyle Enumeration \(section 2.1.1.4\)](#). For the meanings of different values, see the following table. The BS\_NULL style specifies a brush that has no effect. [<51>](#)

**ColorRef (4 bytes):** A 32-bit [ColorRef Object \(section 2.2.2.8\)](#) that specifies a color. Its interpretation depends on the value of **BrushStyle**, as explained in the following.

**BrushHatch (2 bytes):** A 16-bit field that specifies the brush hatch type. Its interpretation depends on the value of **BrushStyle**, as explained in the following.

The following table shows the relationship between values in the **BrushStyle**, **ColorRef** and **BrushHatch** fields in a LogBrush Object. Only supported brush styles are listed.

| BrushStyle      | ColorRef   | BrushHatch   |
|-----------------|--|--|
| BS_SOLID        | SHOULD be a ColorRef Object, which determines the color of the brush.                    | Not used, and SHOULD be ignored.   |
| BS_NULL         | Not used, and SHOULD be ignored.   | Not used, and SHOULD be ignored.   |
| BS_PATTERN      | Not used, and SHOULD be ignored.   | Not used. A default object, such as a solid-color black Brush Object, MAY be created. <a href="#">&lt;52&gt;</a>                             |
| BS_DIBPATTERN   | Not used, and SHOULD be ignored.   | Not used. A default object, such as a solid-color black Brush Object, MAY be created.  |
| BS_DIBPATTERNPT | Not used, and SHOULD be ignored.   | Not used. A default object, such as a solid-color black Brush Object, MAY be created.  |
| BS_HATCHED      | SHOULD be a ColorRef Object, which determines the foreground color of the hatch pattern. | A value from the <a href="#">HatchStyle Enumeration (section 2.1.1.12)</a> that specifies the orientation of lines used to create the hatch. |

### 2.2.2.11 LogColorSpace Object

The LogColorSpace object specifies a logical color space for the playback device context, which can be the name of a color profile in ASCII characters.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Signature      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Version        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Size           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ColorSpaceType |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                     |
|---------------------|
| Intent              |
| Endpoints           |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| GammaRed            |
| GammaGreen          |
| GammaBlue           |
| Filename (variable) |
| ...                 |

**Signature (4 bytes):** A 32-bit unsigned integer that specifies the signature of color space objects; it MUST be set to the value 0x50534F43, which is the ASCII encoding of the string "PSOC".

**Version (4 bytes):** A 32-bit unsigned integer that defines a version number; it MUST be 0x00000400.

**Size (4 bytes):** A 32-bit unsigned integer that defines the size of this object, in bytes.

**ColorSpaceType (4 bytes):** A 32-bit signed integer that specifies the color space type. It MUST be defined in the [LogicalColorSpace](#) enumeration (section [2.1.1.14](#)). If this value is LCS\_sRGB or LCS\_WINDOWS\_COLOR\_SPACE, the sRGB color space MUST be used.

**Intent (4 bytes):** A 32-bit signed integer that defines the gamut mapping intent. It MUST be defined in the [GamutMappingIntent](#) enumeration (section [2.1.1.11](#)).

**Endpoints (36 bytes):** A [CIEXYZTriple](#) object (section [2.2.2.7](#)) that defines the CIE **chromaticity** x, y, and z coordinates of the three colors that correspond to the RGB endpoints for the logical color space associated with the bitmap. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaRed (4 bytes):** A 32-bit fixed point value that defines the toned response curve for red. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaGreen (4 bytes):** A 32-bit fixed point value that defines the toned response curve for green. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaBlue (4 bytes):** A 32-bit fixed point value that defines the toned response curve for blue. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**Filename (variable):** An optional, ASCII character string that specifies the name of a file that contains a color profile. If a file name is specified, and the **ColorSpaceType** field is set to LCS\_CALIBRATED\_RGB, the other fields of this structure SHOULD be ignored.

The **Endpoints**, **GammaRed**, **GammaGreen**, and **GammaBlue** fields are used to specify a logical color space. The **Endpoints** field is a CIEXYZTriple object that contains the x, y, and z values of the RGB endpoint of the color space.

The relation between **tri-stimulus** values X,Y,Z and chromaticity values x,y,z is expressed as follows.

$$\begin{aligned}x &= X / (X+Y+Z) \\y &= Y / (X+Y+Z) \\z &= Z / (X+Y+Z)\end{aligned}$$

The **GammaRed**, **GammaGreen**, and **GammaBlue** fields contain values in "8.8 fixed point" format, which is a technique for representing non-integer numbers. Each value consists of a zero-extended 8-bit magnitude followed by an 8-bit fraction, with the combined 16 bits left-shifted by 8 bits. Thus, in 32-bits, the real value N.F is 00000000nnnnnnnnffffffff00000000, where "nnnnnnnn" and "ffffffff" are binary representations of N and F, respectively. For example, for the real number 10.5, nnnnnnnn would be 00001010 (binary 10) and ffffffff would be 00000101 (binary 5), and the complete 32-bit binary value would be 00000000000001010000001010000000, which is the hexadecimal value 0x0A50.

2.2.2.12 LogColorSpaceW Object

The [LogColorSpaceW](#) object specifies a logical color space, which can be defined by a color profile file with a name consisting of **Unicode** 16-bit characters.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| Signature      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Version        |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Size           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorSpaceType |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

|                     |
|---------------------|
| Intent              |
| Endpoints           |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| ...                 |
| GammaRed            |
| GammaGreen          |
| GammaBlue           |
| Filename (variable) |
| ...                 |

**Signature (4 bytes):** A 32-bit unsigned integer that specifies the signature of color space objects. This MUST be set to the value 0x50534F43, which is the ASCII encoding of the string "PSOC".

**Version (4 bytes):** A 32-bit unsigned integer that defines a version number; it MUST be 0x00000400.

**Size (4 bytes):** A 32-bit unsigned integer that defines the size of this object, in bytes.

**ColorSpaceType (4 bytes):** A 32-bit signed integer that specifies the color space type. It MUST be defined in the [LogicalColorSpace](#) enumeration (section [2.1.1.14](#)). If this value is LCS\_sRGB or LCS\_WINDOWS\_COLOR\_SPACE, the sRGB color space MUST be used.

**Intent (4 bytes):** A 32-bit signed integer that defines the gamut mapping intent. It MUST be defined in the [GamutMappingIntent](#) enumeration (section [2.1.1.11](#)).

**Endpoints (36 bytes):** A [CIEXYZTriple](#) object (section [2.2.2.7](#)) that defines the CIE chromaticity x, y, and z coordinates of the three colors that correspond to the RGB endpoints for the logical color space associated with the bitmap. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaRed (4 bytes):** A 32-bit fixed point value that defines the toned response curve for red. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaGreen (4 bytes):** A 32-bit fixed point value that defines the toned response curve for green. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**GammaBlue (4 bytes):** A 32-bit fixed point value that defines the toned response curve for blue. If the **ColorSpaceType** field does not specify LCS\_CALIBRATED\_RGB, this field MUST be ignored.

**Filename (variable):** An optional, null-terminated Unicode **UTF16-LE** character string, which specifies the name of a file that contains a color profile. If a file name is specified, and the **ColorSpaceType** field is set to LCS\_CALIBRATED\_RGB, the other fields of this structure SHOULD be ignored.

See the LogColorSpace object (section [2.2.2.11](#)) for additional details concerning the interpretation of field values of this object.

2.2.2.13 PaletteEntry Object

The PaletteEntry Object defines the color and usage of an entry in a palette.

|        |   |   |   |   |   |   |   |      |   |    |    |    |    |    |    |       |    |    |    |    |    |    |    |     |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|---|---|------|---|----|----|----|----|----|----|-------|----|----|----|----|----|----|----|-----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8    | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16    | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24  | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Values |   |   |   |   |   |   |   | Blue |   |    |    |    |    |    |    | Green |    |    |    |    |    |    |    | Red |    |    |    |    |    |    |    |

**Values (1 byte):** An 8-bit unsigned integer that defines how the palette entry is to be used. The **Values** field MUST be 0x00 or one of the values in the [PaletteEntryFlag Enumeration](#) table.

**Blue (1 byte):** An 8-bit unsigned integer that defines the blue intensity value for the palette entry.

**Green (1 byte):** An 8-bit unsigned integer that defines the green intensity value for the palette entry.

**Red (1 byte):** An 8-bit unsigned integer that defines the red intensity value for the palette entry.

2.2.2.14 PitchAndFamily Object

The PitchAndFamily object specifies the pitch and family properties of a [Font object \(section 2.2.1.2\)](#). Pitch refers to the width of the characters, and family refers to the general appearance of a font.

|        |   |   |   |   |   |       |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|-------|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6     | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Family |   |   |   | 0 | 0 | Pitch |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Family (4 bits):** A property of a font that describes its general appearance. This MUST be a value in the [FamilyFont enumeration \(section 2.1.1.8\)](#).

**Pitch (2 bits):** A property of a font that describes the pitch, of the characters. This MUST be a value in the [PitchFont enumeration \(section 2.1.1.24\)](#).

### 2.2.2.15 PointL Object

The PointL Object defines the coordinates of a point.

|   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| x |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| y |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**x (4 bytes):** A 32-bit signed integer that defines the horizontal (x) coordinate of the point.

**y (4 bytes):** A 32-bit signed integer that defines the vertical (y) coordinate of the point.

### 2.2.2.16 PointS Object

The PointS Object defines the x- and y-coordinates of a point.

|   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| x |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**x (2 bytes):** A 16-bit signed integer that defines the horizontal (x) coordinate of the point.

**y (2 bytes):** A 16-bit signed integer that defines the vertical (y) coordinate of the point.

### 2.2.2.17 PolyPolygon Object

The PolyPolygon Object defines a series of closed polygons.

|                    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|--------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
| 0                  | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                           | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| NumberOfPolygons   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | aPointsPerPolygon (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| ...                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| aPoints (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
| ...                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |

**NumberOfPolygons (2 bytes):** A 16-bit unsigned integer that defines the number of polygons in the object.

**aPointsPerPolygon (variable):** A **NumberOfPolygons** array of 16-bit unsigned integers that define the number of points for each polygon in the object.

**aPoints (variable):** An array of 16-bit unsigned integers that define the coordinates of the polygons.

### 2.2.2.18 Rect Object

The Rect Object defines a rectangle.

|       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0     | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Left  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Top    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Right |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Bottom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Left (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the upper-left corner of the rectangle

**Top (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the upper-left corner of the rectangle.

**Right (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the lower-right corner of the rectangle.

**Bottom (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the lower-right corner of the rectangle.

### 2.2.2.19 RectL Object

The RectL Object defines a rectangle.

|        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Left   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Top    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Right  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Bottom |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Left (4 bytes):** A 32-bit signed integer that defines the x coordinate, in logical coordinates, of the upper-left corner of the rectangle.

**Top (4 bytes):** A 32-bit signed integer that defines the y coordinate, in logical coordinates, of the upper-left corner of the rectangle.

**Right (4 bytes):** A 32-bit signed integer that defines the x coordinate, in logical coordinates, of the lower-right corner of the rectangle.



**Bottom (4 bytes):** A 32-bit signed integer that defines y coordinate, in logical coordinates, of the lower-right corner of the rectangle.

A rectangle defined with a RectL Object is filled up to— but not including—the right column and bottom row of pixels.

### 2.2.2.20 RGBQuad Object

The RGBQuad Object defines the pixel color values in an uncompressed [DIB](#).

|      |   |   |   |   |   |   |   |       |   |    |    |    |    |    |    |     |    |    |    |    |    |    |    |          |    |    |    |    |    |    |    |
|------|---|---|---|---|---|---|---|-------|---|----|----|----|----|----|----|-----|----|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|
| 0    | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8     | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16  | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24       | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Blue |   |   |   |   |   |   |   | Green |   |    |    |    |    |    |    | Red |    |    |    |    |    |    |    | Reserved |    |    |    |    |    |    |    |

**Blue (1 byte):** An 8-bit unsigned integer that defines the relative intensity of blue.

**Green (1 byte):** An 8-bit unsigned integer that defines the relative intensity of green.

**Red (1 byte):** An 8-bit unsigned integer that defines the relative intensity of red.

**Reserved (1 byte):** An 8-bit unsigned integer that MUST be 0x00.

### 2.2.2.21 Scan Object

The Scan Object specifies a collection of scanlines.

|        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                   | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Count  |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Top                  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Bottom |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ScanLines (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Count2               |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Count (2 bytes):** A 16-bit unsigned integer that specifies the number of horizontal (x-axis) coordinates in the **ScanLines** array. This value MUST be a multiple of 2, since left and right endpoints are required to specify each scanline.

**Top (2 bytes):** A 16-bit unsigned integer that defines the vertical (y-axis) coordinate, in logical units, of the top scanline.

**Bottom (2 bytes):** A 16-bit unsigned integer that defines the vertical (y-axis) coordinate, in logical units, of the bottom scanline.

**ScanLines (variable):** An array of scanlines, each specified by left and right horizontal (x-axis) coordinates of its endpoints.

|      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0    | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16    | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Left |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Right |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Left (2 bytes):** A 16-bit unsigned integer that defines the horizontal (x-axis) coordinate, in logical units, of the left endpoint of the scanline.

**Right (2 bytes):** A 16-bit unsigned integer that defines the horizontal (x-axis) coordinate, in logical units, of the right endpoint of the scanline.

**Count2 (2 bytes):** A 16-bit unsigned integer that MUST be the same as the value of the **Count** field; it is present to allow upward travel in the structure.

### 2.2.2.22 SizeL Object

The SizeL Object defines the x- and y-extents of a rectangle.

|    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0  | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| cx |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| cy |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**cx (4 bytes):** A 32-bit unsigned integer that defines the x-coordinate of the point.

**cy (4 bytes):** A 32-bit unsigned integer that defines the y-coordinate of the point.

## 2.3 WMF Records

This section specifies the WMF Records, which can be grouped into the following general categories.

| Name                 | Section               | Description   |
|----------------------|-----------------------|---|
| Bitmap record types  | <a href="#">2.3.1</a> | Manage and output bitmaps.  |
| Control record types | <a href="#">2.3.2</a> | Define the start and end of a WMF metafile.   |
| Drawing record types | <a href="#">2.3.3</a> | Perform graphics drawing orders.  |
| Object record types  | <a href="#">2.3.4</a> | Create and manage graphics objects.   |
| State record types   | <a href="#">2.3.5</a> | Specify and manage the graphics configuration.  |
| Escape record types  | <a href="#">2.3.6</a> | Specify extensions to functionality that are not directly available through other records defined in the WMF <a href="#">RecordType Enumeration (section 2.1.1.1)</a> . |

During the playback of a WMF metafile, a playback device context exists that can be described as a processing state in which every graphics object and property is defined. In the descriptions of WMF records that follow in this section, an element of the playback device context can be referred to as a "currently selected" graphics object or property. If a graphics object or property that is used in the output operation specified by a record has not been explicitly selected, a default value **MUST** be used. See [Playback Device Context \(section 3.1.5\)](#) for more information.

When a WMF metafile is processed, the order in which graphics output is performed **MUST** be the same as the order of drawing records in the metafile. Thus, a given drawing command is always rendered on top of the renderings of preceding commands.

The following packet definition specifies the generic structure of all WMF records except Control records.

|                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                    |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |  |
|----------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|--------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|--|
|                |   |   |   |   |   |   |   |   |   | 1 |   |   |   |   |   |                    |   |   |   | 2 |   |   |   |   |   |   |   |   |   |   |   | 3 |  |
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6                  | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 |   |  |
| RecordSize     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                    |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |  |
| RecordFunction |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | rdParam (variable) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |  |
| ...            |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                    |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |  |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the type of this record. The low-order byte **MUST** match the low-order byte of one of the values in the **RecordType Enumeration**.

**rdParam (variable):** An optional place holder that is provided for record-specific fields.

### 2.3.1 Bitmap Record Types

This section defines the Bitmap Record Types, which specify records that manage and output bitmaps.

The following are the Bitmap Record Types.

| Name               | Section                 | Description   |
|--------------------|-------------------------|---|
| META_BITBLT        | <a href="#">2.3.1.1</a> | Specifies the transfer of a block of pixels according to a raster operation.  |
| META_DIBBITBLT     | <a href="#">2.3.1.2</a> | Specifies the transfer of a block of pixels in device-independent format according to a raster operation.   |
| META_DIBSTRETCHBLT | <a href="#">2.3.1.3</a> | Specifies the transfer of a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction. |
| META_SETDIBTODEV   | <a href="#">2.3.1.4</a> | Sets a block of pixels in the playback device context using device-independent color data.  |
| META_STRETCHBLT    | <a href="#">2.3.1.5</a> | Specifies the transfer of a block of pixels according to a raster   |

| Name            | Section                 | Description   |
|-----------------|-------------------------|---|
|                 |                         | operation, with possible expansion or contraction.  |
| META_STRETCHDIB | <a href="#">2.3.1.6</a> | Specifies the transfer of color data from a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction. |

### 2.3.1.1 META\_BITBLT Record

The META\_BITBLT record specifies the transfer of a block of pixels according to a raster operation. The destination of the transfer is the current output region in the playback device context.

There are two forms of META\_BITBLT, one which specifies a bitmap as the source, and the other which uses the playback device context as the source. The fields that are the same in the two forms of META\_BITBLT are defined below. The subsections that follow specify the packet structures of the two forms of META\_BITBLT.

**RecordSize:** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction:** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_BITBLT**.

**RasterOperation:** A 32-bit unsigned integer that defines how the source pixels, the current brush in the playback device context, and the destination pixels are to be combined to form the new image. This code MUST be one of the values in the [Ternary Raster Operation enumeration \(section 2.1.1.31\)](#).

**YSrc:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the source rectangle.

**XSrc:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the source rectangle.

**Height:** A 16-bit signed integer that defines the height, in logical units, of the source and destination rectangles.

**Width:** A 16-bit signed integer that defines the width, in logical units, of the source and destination rectangles.

**YDest:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**XDest:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

The **RecordSize** and **RecordFunction** fields SHOULD be used to differentiate between the two forms of META\_BITBLT. If the following Boolean expression is TRUE, a source bitmap is not specified in the record.

```
RecordSize == ((RecordFunction >> 8) + 3)
```

See section [2.3.1](#) for the specification of additional bitmap records.

### 2.3.1.1.1 With Bitmap

This section specifies the structure of the [META\\_BITBLT](#) record when it contains an embedded bitmap.

Fields not specified in this section are specified in the preceding META\_BITBLT section.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YSrc              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XSrc           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YDest             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XDest          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Target (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_BITBLT**. The high-order byte MUST contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **Target** fields. That is:

$$\text{RecordSize} - (2 + (\text{sizeof}(\text{Target})/2))$$

**Target (variable):** A variable-sized [Bitmap16 Object \(section 2.2.2.1\)](#) that defines source image content. This object MUST be specified, even if the raster operation does not require a source.

### 2.3.1.1.2 Without Bitmap

This section specifies the structure of the [META\\_BITBLT](#) record when it does not contain an embedded source bitmap. The source for this operation is the current region in the playback device context.

Fields not specified in this section are specified in the preceding META\_BITBLT section above.

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                |                 |
|----------------|-----------------|
| RecordFunction | RasterOperation |
| ...            | YSrc            |
| XSrc           | Reserved        |
| Height         | Width           |
| YDest          | XDest           |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_BITBLT**. The high-order byte MUST contain a value equal to the number of 16-bit [WORDS](#) in the record minus the number of **WORDS** in the **RecordSize** and **RecordFunction** fields. That is:

$$\text{RecordSize} - 3$$

**Reserved (2 bytes):** This field MUST be ignored.

If the raster operation specified in this record requires a source, the processing of this record fails.

### 2.3.1.2 META\_DIBBITBLT Record

The META\_DIBBITBLT record specifies the transfer of a block of pixels in device-independent format according to a raster operation.

The destination of the transfer is the current output region in the playback device context.

There are two forms of META\_DIBBITBLT, one which specifies a device-independent bitmap (DIB) as the source, and the other which uses the playback device context as the source. Definitions follow for the fields that are the same in the two forms of META\_DIBBITBLT. The subsections that follow specify the packet structures of the two forms of META\_DIBBITBLT.

**RecordSize:** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction:** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_DIBBITBLT**.

**RasterOperation:** A 32-bit unsigned integer that defines how the source pixels, the current brush in the playback device context, and the destination pixels are to be combined to form the new image. This code MUST be one of the values in the [Ternary Raster Operation Enumeration \(section 2.1.1.31\)](#).

**YSrc:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the source rectangle.

**XSrc:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the source rectangle.

**Height:** A 16-bit signed integer that defines the height, in logical units, of the source and destination rectangles.

**Width:** A 16-bit signed integer that defines the width, in logical units, of the source and destination rectangles.

**YDest:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**XDest:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

The **RecordSize** and **RecordFunction** fields SHOULD be used to differentiate between the two forms of META\_DIBBITBLT. If the following Boolean expression is TRUE, a source DIB is not specified in the record.

```
RecordSize == ((RecordFunction >> 8) + 3)
```

See section [2.3.1](#) for the specification of additional bitmap records.

2.3.1.2.1 With Bitmap

This section specifies the structure of the [META\\_DIBBITBLT](#) record when it contains an embedded device-independent bitmap (DIB).

Fields not specified in this section are specified in the preceding META\_DIBBITBLT section.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YSrc              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XSrc           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YDest             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XDest          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Target (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_DIBBITBLT**. The high-order byte MUST contain a value equal to the number of 16-bit [WORDS](#) in the record minus the number of **WORDS** in the **RecordSize** and **Target** fields. That is:

```
RecordSize - (2 + (sizeof(Target)/2))
```

**Target (variable):** A variable-sized [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#) that defines image content. This object **MUST** be specified, even if the raster operation does not require a source.

2.3.1.2.2 Without Bitmap

This section specifies the structure of the [META\\_DIBBITBLT](#) record when it does not contain an embedded source device-independent bitmap (DIB). The source for this operation is the current region in the playback device context.

Fields not specified in this section are specified in the preceding META\_DIBBITBLT section.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YSrc            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XSrc           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Reserved        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Height         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Width           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| YDest          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | XDest           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte **MUST** match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_DIBBITBLT**. The high-order byte **MUST** contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **RecordFunction** fields. That is:

$$\text{RecordSize} - 3$$

**Reserved (2 bytes):** This field **MUST** be ignored.

If the raster operation specified in this record requires a source, the processing of this record fails.

2.3.1.3 META\_DIBSTRETCHBLT Record

The META\_DIBSTRETCHBLT record specifies the transfer of a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction.

The destination of the transfer is the current output region in the playback device context.

There are two forms of META\_DIBSTRETCHBLT, one which specifies a device-independent bitmap (DIB) as the source, and the other which uses the playback device context as the source. Definitions follow for the fields that are the same in the two forms of META\_DIBSTRETCHBLT. The subsections that follow specify the packet structures of the two forms of META\_DIBSTRETCHBLT.



The expansion or contraction is performed according to the stretching mode currently set in the playback device context, which MUST be a value from the [StretchMode Enumeration \(section 2.1.1.30\)](#).

**RecordSize:** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction:** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_DIBSTRETCHBLT**.

**RasterOperation:** A 32-bit unsigned integer that defines how the source pixels, the current brush in the playback device context, and the destination pixels are to be combined to form the new image. This code MUST be one of the values in the [Ternary Raster Operation Enumeration \(section 2.1.1.31\)](#).

**SrcHeight:** A 16-bit signed integer that defines the height, in logical units, of the source rectangle.

**SrcWidth:** A 16-bit signed integer that defines the width, in logical units, of the source rectangle.

**YSrc:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the source rectangle.

**XSrc:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the source rectangle.

**DestHeight:** A 16-bit signed integer that defines the height, in logical units, of the destination rectangle.

**DestWidth:** A 16-bit signed integer that defines the width, in logical units, of the destination rectangle.

**YDest:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**XDest:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

The **RecordSize** and **RecordFunction** fields SHOULD be used to differentiate between the two forms of META\_DIBSTRETCHBLT. If the following Boolean expression is TRUE, a source DIB is not specified in the record.

```
RecordSize == ((RecordFunction >> 8) + 3)
```

See section [2.3.1](#) for the specification of additional bitmap records.

#### 2.3.1.3.1 With Bitmap

This section specifies the structure of the [META\\_DIBSTRETCHBLT](#) record when it contains an embedded device-independent bitmap (DIB).

Fields not specified in this section are specified in the preceding META\_DIBSTRETCHBLT section.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | RasterOperation   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | SrcHeight         |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| SrcWidth       |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YSrc              |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XSrc           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | DestHeight        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| DestWidth      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YDest             |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XDest          |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Target (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_DIBSTRETCHBLT**. The high-order byte MUST contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **Target** fields. That is:

$$\text{RecordSize} - (2 + (\text{sizeof}(\text{Target})/2))$$

**Target (variable):** A variable-sized [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#) that defines image content. This object MUST be specified, even if the raster operation does not require a source.

### 2.3.1.3.2 Without Bitmap

This section specifies the structure of the [META\\_DIBSTRETCHBLT](#) record when it does not contain an embedded source device-independent bitmap (DIB). The source for this operation is the current region in the playback device context.

Fields not specified in this section are specified in the preceding META\_DIBSTRETCHBLT section.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | SrcHeight       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|            |           |
|------------|-----------|
| SrcWidth   | YSrc      |
| XSrc       | Reserved  |
| DestHeight | DestWidth |
| YDest      | XDest     |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte **MUST** match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_DIBSTRETCHBLT**. The high-order byte **MUST** contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **RecordFunction** fields. That is:

$$\text{RecordSize} - 3$$

**Reserved (2 bytes):** This field **MUST** be ignored.

If the raster operation specified in this record requires a source, the processing of this record fails.

#### 2.3.1.4 META\_SETDIBTODEV Record

The META\_SETDIBTODEV record sets a block of pixels in the playback device context using device-independent color data.

The source of the color data is a DIB.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6          | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | ColorUsage |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ScanCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | StartScan  |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| yDib           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | xDib       |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Height         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Width      |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| yDest          |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | xDest      |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| DIB (variable) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETDIBTODEV.

**ColorUsage (2 bytes):** A 16-bit unsigned integer that defines whether the **Colors** field of the DIB contains explicit RGB values or indexes into a palette. This MUST be one of the values in the [ColorUsage Enumeration \(section 2.1.1.6\)](#).

**ScanCount (2 bytes):** A 16-bit unsigned integer that defines the number of scan lines in the source.

**StartScan (2 bytes):** A 16-bit unsigned integer that defines the starting scan line in the source.

**yDib (2 bytes):** A 16-bit unsigned integer that defines the y-coordinate, in logical units, of the source rectangle.

**xDib (2 bytes):** A 16-bit unsigned integer that defines the x-coordinate, in logical units, of the source rectangle.

**Height (2 bytes):** A 16-bit unsigned integer that defines the height, in logical units, of the source and destination rectangles.

**Width (2 bytes):** A 16-bit unsigned integer that defines the width, in logical units, of the source and destination rectangles.

**yDest (2 bytes):** A 16-bit unsigned integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**xDest (2 bytes):** A 16-bit unsigned integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**DIB (variable):** A variable-sized [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#) that is the source of the color data.

The source image in the DIB is specified in one of the following formats:

- An array of pixels with a structure specified by the **ColorUsage** field and information in the [DeviceIndependentBitmap](#) header.
- A JPEG image [\[JFIF\]](#). [<53>](#)
- A PNG image [\[W3C-PNG\]](#). [<54>](#)

See section [2.3.1](#) for the specification of additional bitmap records.

### 2.3.1.5 META\_STRETCHBLT Record

The META\_STRETCHBLT record specifies the transfer of a block of pixels according to a raster operation, with possible expansion or contraction.

The destination of the transfer is the current output region in the playback device context.

There are two forms of META\_STRETCHBLT, one which specifies a bitmap as the source, and the other which uses the playback device context as the source. Definitions follow for the fields that are

the same in the two forms of META\_STRETCHBLT are defined below. The subsections that follow specify the packet structures of the two forms of META\_STRETCHBLT.

The expansion or contraction is performed according to the stretching mode currently set in the playback device context, which MUST be a value from the [StretchMode Enumeration \(section 2.1.1.30\)](#).

**RecordSize:** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction:** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_STRETCHBLT**.

**RasterOperation:** A 32-bit unsigned integer that defines how the source pixels, the current brush in the playback device context, and the destination pixels are to be combined to form the new image. This code MUST be one of the values in the [Ternary Raster Operation Enumeration \(section 2.1.1.31\)](#).

**SrcHeight:** A 16-bit signed integer that defines the height, in logical units, of the source rectangle.

**SrcWidth:** A 16-bit signed integer that defines the width, in logical units, of the source rectangle.

**YSrc:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the source rectangle.

**XSrc:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the source rectangle.

**DestHeight:** A 16-bit signed integer that defines the height, in logical units, of the destination rectangle.

**DestWidth:** A 16-bit signed integer that defines the width, in logical units, of the destination rectangle.

**YDest:** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**XDest:** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

The **RecordSize** and **RecordFunction** fields SHOULD be used to differentiate between the two forms of META\_STRETCHBLT. If the following Boolean expression is TRUE, a source bitmap is not specified in the record.

```
RecordSize == ((RecordFunction >> 8) + 3)
```

See section [2.3.1](#) for the specification of additional bitmap records.

#### 2.3.1.5.1 With Bitmap

This section specifies the structure of the [META\\_STRETCHBLT](#) record when it contains an embedded bitmap.

Fields not specified in this section are specified in the preceding META\_STRETCHBLT section.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | RasterOperation   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | SrcHeight         |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| SrcWidth       |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YSrc              |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XSrc           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | DestHeight        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| DestWidth      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YDest             |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XDest          |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Target (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte MUST match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_STRETCHBLT**. The high-order byte MUST contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **Target** fields. That is:

$$\text{RecordSize} - (2 + (\text{sizeof}(\text{Target})/2))$$

**Target (variable):** A variable-sized [Bitmap16 Object \(section 2.2.2.1\)](#) that defines source image content. This object MUST be specified, even if the raster operation does not require a source.

### 2.3.1.5.2 Without Bitmap

This section specifies the structure of the [META\\_STRETCHBLT](#) record when it does not contain an embedded source bitmap. The source for this operation is the current region in the playback device context.

Fields not specified in this section are specified in the preceding META\_STRETCHBLT section.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | SrcHeight       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|            |           |
|------------|-----------|
| SrcWidth   | YSrc      |
| XSrc       | Reserved  |
| DestHeight | DestWidth |
| YDest      | XDest     |

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The low-order byte **MUST** match the low-order byte of the [RecordType enumeration \(section 2.1.1.1\)](#) value **META\_STRETCHBLT**. The high-order byte **MUST** contain a value equal to the number of 16-bit **WORDS** in the record minus the number of **WORDS** in the **RecordSize** and **RecordFunction** fields. That is:

`RecordSize - 3`

**Reserved (2 bytes):** This field **MUST** be ignored.

If the raster operation specified in this record requires a source, the processing of this record fails.

#### 2.3.1.6 META\_STRETCHDIB Record

The META\_STRETCHDIB record specifies the transfer of color data from a block of pixels in device-independent format according to a raster operation, with possible expansion or contraction.

The source of the color data is a DIB, and the destination of the transfer is the current output region in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | RasterOperation |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | ColorUsage      |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| SrcHeight      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | SrcWidth        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| YSrc           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | XSrc            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| DestHeight     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | DestWidth       |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| yDst           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | xDst            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| DIB (variable) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

...

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_STRETCHDIB.

**RasterOperation (4 bytes):** A 32-bit unsigned integer that defines how the source pixels, the current brush in the playback device context, and the destination pixels are to be combined to form the new image. This code MUST be one of the values in the [Ternary Raster Operation Enumeration \(section 2.1.1.31\)](#).

**ColorUsage (2 bytes):** A 16-bit unsigned integer that defines whether the **Colors** field of the DIB contains explicit RGB values or indexes into a palette. This value MUST be in the [ColorUsage Enumeration \(section 2.1.1.6\)](#).

**SrcHeight (2 bytes):** : A 16-bit signed integer that defines the height, in logical units, of the source rectangle.

**SrcWidth (2 bytes):** : A 16-bit signed integer that defines the width, in logical units, of the source rectangle.

**YSrc (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the source rectangle.

**XSrc (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the source rectangle.

**DestHeight (2 bytes):** A 16-bit signed integer that defines the height, in logical units, of the destination rectangle.

**DestWidth (2 bytes):** A 16-bit signed integer that defines the width, in logical units, of the destination rectangle.

**yDst (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**xDst (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the destination rectangle.

**DIB (variable):** A variable-sized [DeviceIndependentBitmap Object \(section 2.2.2.9\)](#) that is the source of the color data.

The source image in the DIB is specified in one of the following formats:

- An array of pixels with a structure specified by the **ColorUsage** field and information in the [DeviceIndependentBitmap](#) header.
- A JPEG image [\[JFIF\]](#). [<55>](#)
- A PNG image [\[W3C-PNG\]](#). [<56>](#)

If the image format is JPEG or PNG, the **ColorUsage** field in this record MUST be set to **DIB\_RGB\_COLORS**, and the **RasterOperation** field MUST be set to **SRCCOPY**.



See section [2.3.1](#) for the specification of additional bitmap records.

## 2.3.2 Control Record Types

This section defines the Control Record Types, which specify records that begin and end a WMF metafile.

The following are the Control Record Types.

| Name           | Section                 | Description                                      |
|----------------|-------------------------|--|
| META_EOF       | <a href="#">2.3.2.1</a> | Specifies the end of a WMF metafile.             |
| META_HEADER    | <a href="#">2.3.2.2</a> | Specifies the start of a WMF metafile.           |
| META_PLACEABLE | <a href="#">2.3.2.3</a> | Specifies the start of a placeable WMF metafile. |

### 2.3.2.1 META\_EOF Record

The META\_EOF record indicates the end of the WMF metafile.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of 16-bit [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the type of this record. For META\_EOF, this value MUST be 0x0000, as specified in the [RecordType Enumeration](#) table.

See section [2.3.2](#) for the specification of similar records.

### 2.3.2.2 META\_HEADER Record

The META\_HEADER record is the first record in a standard (nonplaceable) WMF metafile.

|           |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|-----------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0         | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| Type      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | HeaderSize      |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Version   |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | SizeLow         |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| SizeHigh  |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | NumberOfObjects |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| MaxRecord |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

|                 |
|-----------------|
| NumberOfMembers |
|-----------------|

**Type (2 bytes):** A 16-bit unsigned integer that defines the type of metafile. It MUST be a value in the [MetafileType](#) enumeration (section [2.1.1.18](#)).

**HeaderSize (2 bytes):** A 16-bit unsigned integer that defines the number of 16-bit words in the header.

**Version (2 bytes):** A 16-bit unsigned integer that defines the metafile version. It MUST be a value in the [MetafileVersion](#) enumeration (section [2.1.1.19](#)).<57>

**SizeLow (2 bytes):** A 16-bit unsigned integer that defines the low-order word of the number of 16-bit words in the entire metafile.

**SizeHigh (2 bytes):** A 16-bit unsigned integer that defines the high-order word of the number of 16-bit words in the entire metafile.

**NumberOfObjects (2 bytes):** A 16-bit unsigned integer that specifies the number of graphics objects that are defined in the entire metafile. These objects include brushes, pens, and the other objects specified in section [2.2.1](#).

**MaxRecord (4 bytes):** A 32-bit unsigned integer that specifies the size of the largest record used in the metafile (in 16-bit elements).

**NumberOfMembers (2 bytes):** A 16-bit unsigned integer that is not used. It SHOULD be 0x0000.

See section [2.3.2](#) for the specification of similar records.

### 2.3.2.3 META\_PLACEABLE Record

The META\_PLACEABLE record is the first record in a placeable WMF metafile, which is an extension to the WMF metafile format.<58> The information in this extension allows the specification of the placement and size of the target image, which makes it adaptable to different output devices.

The META\_PLACEABLE record MUST be the first record of the metafile, located immediately before the [META\\_HEADER record](#) (section [2.3.2.2](#)).

|          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0        | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16          | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Key      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| HWmf     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BoundingBox |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Inch        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Checksum |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Key (4 bytes):** Identification value that indicates the presence of a placeable metafile header. This value MUST be 0x9AC6CDD7.

**HWmf (2 bytes):** The resource handle to the metafile, when the metafile is in memory. When the metafile is on disk, this field MUST contain 0x0000. This attribute of the metafile is specified in the **Type** field of the META\_HEADER record.

**BoundingBox (8 bytes):** The destination rectangle, measured in logical units, for displaying the metafile. The size of a logical unit is specified by the **Inch** field.

**Inch (2 bytes):** The number of logical units per inch used to represent the image. This value can be used to scale an image.

By convention, an image is considered to be recorded at 1440 logical units (twips) per inch. Thus, a value of 720 specifies that the image SHOULD be rendered at twice its normal size, and a value of 2880 specifies that the image SHOULD be rendered at half its normal size.

**Reserved (4 bytes):** A field that is not used and MUST be set to 0x00000000.

**Checksum (2 bytes):** A checksum for the previous 10 16-bit values in the header. This value can be used to determine whether the metafile has become corrupted.

See section [2.3.2](#) for the specification of similar records.

### 2.3.3 Drawing Record Types

This section defines the Drawing Record Types, which specify records that perform graphics output. These records use graphics objects and properties specified in the [Playback Device Context \(section 3.1.5\)](#).

The following are the Drawing Record Types.

| Name              | Section                  | Description   |
|-------------------|--------------------------|---|
| META_ARC          | <a href="#">2.3.3.1</a>  | Draws an elliptical arc.  |
| META_CHORD        | <a href="#">2.3.3.2</a>  | Draws a chord.  |
| META_ELLIPSE      | <a href="#">2.3.3.3</a>  | Draws an ellipse.   |
| META_EXTFLOODFILL | <a href="#">2.3.3.4</a>  | Fills an area with the brush that is defined in the playback device context.  |
| META_EXTTEXTOUT   | <a href="#">2.3.3.5</a>  | Outputs a character string with optional opaquing and clipping.   |
| META_FILLREGION   | <a href="#">2.3.3.6</a>  | Fills a region using a specified brush.   |
| META_FLOODFILL    | <a href="#">2.3.3.7</a>  | Fills an area of the output surface with the brush that is defined in the playback device context.                                    |
| META_FRAMEREGION  | <a href="#">2.3.3.8</a>  | Draws a border around a specified region using a specified brush.   |
| META_INVERTREGION | <a href="#">2.3.3.9</a>  | Draws a region in which the colors are inverted.  |
| META_LINETO       | <a href="#">2.3.3.10</a> | Draws a line from the drawing position that is defined in the playback device context up to, but not including, a specified position. |
| META_PAINTREGION  | <a href="#">2.3.3.11</a> | Paints the specified region using the brush that is defined in the  |

| Name             | Section                  | Description   |
|------------------|--------------------------|---|
|                  |                          | playback device context.  |
| META_PATBLT      | <a href="#">2.3.3.12</a> | Paints a specified rectangle by using the brush that is defined in the playback device context. |
| META_PIE         | <a href="#">2.3.3.13</a> | Draws a pie-shaped wedge bounded by the intersection of an ellipse and two radial lines.        |
| META_POLYLINE    | <a href="#">2.3.3.14</a> | Draws a series of line segments by connecting the points in the specified array.                |
| META_POLYGON     | <a href="#">2.3.3.15</a> | Paints a polygon consisting of two or more vertices connected by straight lines.                |
| META_POLYPOLYGON | <a href="#">2.3.3.16</a> | Paints a series of closed polygons.   |
| META_RECTANGLE   | <a href="#">2.3.3.17</a> | Paints a rectangle.   |
| META_ROUNDRECT   | <a href="#">2.3.3.18</a> | Paints a rectangle with rounded corners.  |
| META_SETPIXEL    | <a href="#">2.3.3.19</a> | Sets the pixel at specified coordinates to a specified color.                                   |
| META_TEXTOUT     | <a href="#">2.3.3.20</a> | Outputs a character string.   |

### 2.3.3.1 META\_ARC Record

The META\_ARC record draws an elliptical arc.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6          | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YEndArc    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XEndArc        |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | YStartArc  |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| XStartArc      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | BottomRect |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RightRect      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | TopRect    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| LeftRect       |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |            |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of **WORDS** in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte **MUST** match the lower byte of the **RecordType Enumeration** table value META\_ARC.

**YEndArc (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the ending point of the radial line defining the ending point of the arc.

**XEndArc (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the ending point of the radial line defining the ending point of the arc.

**YStartArc (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the ending point of the radial line defining the starting point of the arc.

**XStartArc (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the ending point of the radial line defining the starting point of the arc.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.2 META\_CHORD Record

The META\_CHORD record draws a chord, which is defined by a region bounded by the intersection of an ellipse with a line segment. The chord is outlined using the pen and filled using the brush that are defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YRadial2   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XRadial2       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YRadial1   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XRadial1       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BottomRect |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RightRect      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TopRect    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| LeftRect       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_CHORD.

**YRadial2 (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the endpoint of the second radial.

**XRadial2 (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the endpoint of the second radial.

**YRadial1 (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the endpoint of the first radial.

**XRadial1 (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the endpoint of the first radial.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.3 META\_ELLIPSE Record

The META\_ELLIPSE record draws an ellipse. The center of the ellipse is the center of the specified bounding rectangle. The ellipse is outlined by using the pen and is filled by using the brush; these are defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BottomRect |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RightRect      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TopRect    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| LeftRect       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_ELLIPSE.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

#### 2.3.3.4 META\_EXTFLOODFILL Record

The META\_EXTFLOODFILL record fills an area with the brush that is defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |      |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------|----|----|----|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16   | 17 | 18 | 19 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |      |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Mode |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorRef       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |      |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| Y              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | X    |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_EXTFLOODFILL.

**Mode (2 bytes):** A 16-bit unsigned integer that defines the fill operation to be performed. This member MUST be one of the values in the [FloodFill Enumeration](#) table.

**ColorRef (4 bytes):** A 32-bit [ColorRef Object](#) that defines the color value.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the point to be set.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the point to be set.

See section [2.3.3](#) for the specification of other Drawing records.

#### 2.3.3.5 META\_EXTTEXTOUT Record

The META\_EXTTEXTOUT record outputs text by using the font, background color, and text color that are defined in the playback device context. Optionally, dimensions can be provided for clipping, opaquing, or both.

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                |                      |
|----------------|----------------------|
| RecordFunction | Y                    |
| X              | StringLength         |
| fwOpts         | Rectangle (optional) |
| ...            |                      |
| ...            | String (variable)    |
| ...            |                      |
| Dx (variable)  |                      |
| ...            |                      |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_EXTTEXTOUT.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, where the text string is to be located.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, where the text string is to be located.

**StringLength (2 bytes):** A 16-bit signed integer that defines the length of the string.

**fwOpts (2 bytes):** A 16-bit unsigned integer that defines the use of the application-defined rectangle. This member can be a combination of one or more values in the [ExtTextOutOptions Flags \(section 2.1.2.2\)](#).

**Rectangle (8 bytes):** An optional 8-byte [Rect Object \(section 2.2.2.18\)](#) that defines the dimensions, in logical coordinates, of a rectangle that is used for clipping, opaquing, or both.

**String (variable):** A variable-length string that specifies the text to be drawn. The string does not need to be null-terminated, because **StringLength** specifies the length of the string. If the length is odd, an extra byte is placed after it so that the following member (optional **Dx**) is aligned on a 16-bit boundary.

**Dx (variable):** An optional array of 16-bit signed integers that indicate the distance between origins of adjacent character cells. For example, **Dx[i]** logical units separate the origins of character cell i and character cell i + 1. If this field is present, there MUST be the same number of values as there are characters in the string.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.6 META\_FILLREGION Record

The META\_FILLREGION record fills a region using a specified brush.



|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Region |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Brush          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_FILLREGION.

**Region (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the region to be filled.

**Brush (2 bytes):** A 16-bit unsigned integer used to index into the WMF Object Table to get the brush to use for filling the region.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.7 META\_FLOODFILL Record

The META\_FLOODFILL record fills an area of the output surface with the brush that is defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YStart   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XStart         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_FLOODFILL.

**ColorRef (4 bytes):** A 32-bit [ColorRef Object](#) that defines the color value.

**YStart (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the point where filling is to start.

**XStart (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the point where filling is to start.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.8 META\_FRAMEREGION Record

The META\_FRAMEREGION record draws a border around a specified region using a specified brush.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Region |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Brush          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_FRAMEREGION.

**Region (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the region to be framed.

**Brush (2 bytes):** A 16-bit unsigned integer used to index into the WMF Object Table to get the Brush to use for filling the region.

**Height (2 bytes):** A 16-bit signed integer that defines the height, in logical units, of the region frame.

**Width (2 bytes):** A 16-bit signed integer that defines the width, in logical units, of the region frame.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.9 META\_INVERTREGION Record

The META\_INVERTREGION record draws a region in which the colors are inverted.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Region |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_INVERTREGION.

**Region (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the region to be inverted.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.3](#) for the specification of other Drawing records.

#### 2.3.3.10 META\_LINETO Record

The META\_LINETO record draws a line from the drawing position that is defined in the playback device context up to, but not including, the specified point.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_LINETO.

**Y (2 bytes):** A 16-bit signed integer that defines the vertical component of the drawing destination position, in logical units.

**X (2 bytes):** A 16-bit signed integer that defines the horizontal component of the drawing destination position, in logical units.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.11 META\_PAINTREGION Record

The META\_PAINTREGION record paints the specified region by using the brush that is defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Region |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_PAINTREGION.

**Region (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the region to be inverted.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.12 META\_PATBLT Record

The META\_PATBLT record paints a specified rectangle using the brush that is defined in the playback device context. The brush color and the surface color or colors are combined using the specified raster operation.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | RasterOperation |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YLeft           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XLeft          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_PATBLT.

**RasterOperation (4 bytes):** A 32-bit unsigned integer that defines the raster operation code. This code MUST be one of the values in the [Ternary Raster Operation](#) enumeration table.

**Height (2 bytes):** A 16-bit signed integer that defines the height, in logical units, of the rectangle.

**Width (2 bytes):** A 16-bit signed integer that defines the width, in logical units, of the rectangle.

**YLeft (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the rectangle to be filled.

**XLeft (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the rectangle to be filled.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.13 META\_PIE Record

The META\_PIE record draws a pie-shaped wedge bounded by the intersection of an ellipse and two radials. The pie is outlined by using the pen and filled by using the brush that are defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YRadial2   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XRadial2       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YRadial1   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XRadial1       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BottomRect |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RightRect      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TopRect    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| LeftRect       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_PIE.

**YRadial2 (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the endpoint of the second radial.

**XRadial2 (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the endpoint of the second radial.

**YRadial1 (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical coordinates, of the endpoint of the first radial.

**XRadial1 (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical coordinates, of the endpoint of the first radial.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the bounding rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the bounding rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

#### 2.3.3.14 META\_POLYLINE Record

The META\_POLYLINE record draws a series of line segments by connecting the points in the specified array.

|                    |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
|--------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|----------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0                  | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 |
| RecordSize         |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| RecordFunction     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | NumberOfPoints |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| aPoints (variable) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_POLYLINE.

**NumberOfPoints (2 bytes):** A 16-bit signed integer that defines the number of points in the array.

**aPoints (variable):** A **NumberOfPoints** array of 32-bit [PointS Objects](#), in logical units.

See section [2.3.3](#) for the specification of other Drawing records.

#### 2.3.3.15 META\_POLYGON Record

The META\_POLYGON record paints a polygon consisting of two or more vertices connected by straight lines. The polygon is outlined by using the pen and filled by using the brush and polygon fill mode that are defined in the playback device context.

|                    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|--------------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0                  | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | NumberOfPoints |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| aPoints (variable) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_POLYGON.

**NumberOfPoints (2 bytes):** A 16-bit signed integer that defines the number of points in the array.

**aPoints (variable):** A **NumberOfPoints** array of 32-bit [PointS Objects \(section 2.2.2.16\)](#), in logical units.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.16 META\_POLYPOLYGON Record

The META\_POLYPOLYGON record paints a series of closed polygons. Each polygon is outlined by using the pen and filled by using the brush and polygon fill mode; these are defined in the playback device context. The polygons drawn by this function can overlap.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|------------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                      | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | PolyPolygon (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_POLYPOLYGON.

**PolyPolygon (variable):** A variable-sized [PolyPolygon Object \(section 2.2.2.17\)](#) that defines the point information.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.17 META\_RECTANGLE Record

The META\_RECTANGLE record paints a rectangle. The rectangle is outlined by using the pen and filled by using the brush that are defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BottomRect |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RightRect      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TopRect    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| LeftRect       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_RECTANGLE.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.18 META\_ROUNDRECT Record

The META\_ROUNDRECT record paints a rectangle with rounded corners. The rectangle is outlined using the pen and filled using the brush, as defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Height     |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Width          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BottomRect |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RightRect      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TopRect    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |



|          |
|----------|
| LeftRect |
|----------|

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_ROUNDRECT.

**Height (2 bytes):** A 16-bit signed integer that defines the height, in logical coordinates, of the ellipse used to draw the rounded corners.

**Width (2 bytes):** A 16-bit signed integer that defines the width, in logical coordinates, of the ellipse used to draw the rounded corners.

**BottomRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the rectangle.

**RightRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the rectangle.

**TopRect (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the rectangle.

**LeftRect (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the rectangle.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.19 META\_SETPIXEL Record

The META\_SETPIXEL record sets the pixel at the specified coordinates to the specified color.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETPIXEL.

**ColorRef (4 bytes):** A [ColorRef Object \(section 2.2.2.8\)](#) that defines the color value.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the point to be set.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the point to be set.

See section [2.3.3](#) for the specification of other Drawing records.

### 2.3.3.20 META\_TEXTOUT Record

The META\_TEXTOUT record outputs a character string at the specified location by using the font, background color, and text color that are defined in the playback device context.

|                   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16           | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | StringLength |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| String (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...               |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| YStart            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | XStart       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of **WORDS** in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_TEXTOUT.

**StringLength (2 bytes):** A 16-bit signed integer that defines the length of the string, in bytes, pointed to by **String**.

**String (variable):** The size of this field MUST be a multiple of two. If StringLength is an odd number, then this field MUST be of a size greater than or equal to StringLength + 1. A variable-length string that specifies the text to be drawn. The string does not need to be null-terminated, because **StringLength** specifies the length of the string. The string is written at the location specified by the **XStart** and **YStart** fields.

**YStart (2 bytes):** A 16-bit signed integer that defines the vertical (y-axis) coordinate, in logical units, of the point where drawing is to start.

**XStart (2 bytes):** A 16-bit signed integer that defines the horizontal (x-axis) coordinate, in logical units, of the point where drawing is to start.

See section [2.3.3](#) for the specification of other Drawing records.

## 2.3.4 Object Record Types

This section defines the Object Record Types, which create and manage the graphics objects specified in the [Playback Device Context \(section 3.1.5\)](#).

The following are the Object Record Types.

| Name                       | Section                  | Description  |
|----------------------------|--------------------------|--|
| META_CREATEBRUSHINDIRECT   | <a href="#">2.3.4.1</a>  | Creates a <a href="#">Brush Object (section 2.2.1.1)</a> from a <a href="#">LogBrush Object (section 2.2.2.10)</a> . |
| META_CREATEFONTINDIRECT    | <a href="#">2.3.4.2</a>  | Creates a <a href="#">Font Object (section 2.2.1.2)</a> .  |
| META_CREATEPALETTE         | <a href="#">2.3.4.3</a>  | Creates a <a href="#">Palette Object (section 2.2.1.3)</a> .   |
| META_CREATEPATTERNBRUSH    | <a href="#">2.3.4.4</a>  | Creates a Brush Object with a pattern specified by a bitmap.   |
| META_CREATEPENINDIRECT     | <a href="#">2.3.4.5</a>  | Creates a <a href="#">Pen Object (section 2.2.1.4)</a> .   |
| META_CREATEREGION          | <a href="#">2.3.4.6</a>  | Creates a <a href="#">Region Object (section 2.2.1.5)</a> .  |
| META_DELETEOBJECT          | <a href="#">2.3.4.7</a>  | Deletes an existing object.  |
| META_DIBCREATEPATTERNBRUSH | <a href="#">2.3.4.8</a>  | Creates a Brush Object with a pattern specified by a DIB.  |
| META_SELECTCLIPREGION      | <a href="#">2.3.4.9</a>  | Specifies the clipping region in the playback device context with a specified Region Object.                         |
| META_SELECTOBJECT          | <a href="#">2.3.4.10</a> | Specifies a graphics object in the playback device context.  |
| META_SELECTPALETTE         | <a href="#">2.3.4.11</a> | Specifies the palette in the playback device context with a specified Palette Object.                                |

Whenever a graphics object is created by one of the preceding metafile records, the following actions are implied:

- The object MUST always be assigned the lowest-numbered available index in the [WMF Object Table \(section 3.1.4.1\)](#).
- Subsequent WMF records MUST refer to the object by its assigned WMF Object Table index.
- The object MUST NOT be used in drawing operations until a [META\\_SELECTOBJECT](#) record is received that specifies the object's index.
- The object MUST remain available for selection until a [META\\_DELETEOBJECT \(section 2.3.4.7\)](#) record is received that specifies the object's index.

For further information concerning object indexes and the WMF Object Table, see [Managing Objects \(section 3.1.4\)](#).

#### 2.3.4.1 META\_CREATEBRUSHINDIRECT Record

The META\_CREATEBRUSHINDIRECT record creates a [Brush Object \(section 2.2.1.1\)](#) from a [LogBrush Object \(section 2.2.2.10\)](#).

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                |          |
|----------------|----------|
| RecordFunction | LogBrush |
| ...            |          |
| ...            |          |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_CREATEBRUSHINDIRECT**.

**LogBrush (8 bytes):** [LogBrush Object](#) data that defines the brush to create. The **BrushStyle** field specified in the LogBrush Object SHOULD be BS\_SOLID, BS\_NULL, or BS\_HATCHED; otherwise, a default Brush Object MAY be created. See the following table for details.

The following table shows the types of Brush Objects created by the META\_CREATEBRUSHINDIRECT record, according to the [BrushStyle Enumeration \(section 2.1.1.4\)](#) value in the LogBrush Object specified by the **LogBrush** field.

| BrushStyle      | Brush Object created   |
|-----------------|--|
| BS_SOLID        | A solid-color Brush Object.  |
| BS_NULL         | An empty Brush Object.   |
| BS_PATTERN      | A default object, such as a solid-color black Brush Object, MAY be created. <a href="#">&lt;59&gt;</a> |
| BS_DIBPATTERNPT | Same as preceding BS_PATTERN.  |
| BS_HATCHED      | A hatched Brush Object.  |

See section [2.3.4](#) for the specification of other object records.

### 2.3.4.2 META\_CREATEFONTINDIRECT Record

The META\_CREATEFONTINDIRECT record creates a [Font Object \(section 2.2.1.2\)](#).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Font (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) value **META\_CREATEFONTINDIRECT**.

**Font (variable):** Font Object data that defines the font to create.

See section [2.3.4](#) for the specification of other object records.

#### 2.3.4.3 META\_CREATEPALETTE Record

The META\_CREATEPALETTE record creates a [Palette Object \(section 2.2.1.3\)](#).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|--------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                  | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Palette (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) value **META\_CREATEPALETTE**.

**Palette (variable):** [Palette Object](#) data that defines the palette to create. The **Start** field in the Palette Object MUST be set to 0x0300.

See section [2.3.4](#) for the specification of other object records.

#### 2.3.4.4 META\_CREATEPATTERNBRUSH Record

The META\_CREATEPATTERNBRUSH record creates a brush object with a pattern specified by a bitmap.

|  |  |  |  |  |  |  |  |  |  |  |   |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|--|--|--|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|
|  |  |  |  |  |  |  |  |  |  |  | 1 |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |  |
|--|--|--|--|--|--|--|--|--|--|--|---|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|--|

|          |                    |
|----------|--------------------|
| Reserved |                    |
| ...      |                    |
| ...      |                    |
| ...      |                    |
| ...      | Pattern (variable) |
| ...      |                    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_CREATEPATTERNBRUSH**.

**Bitmap16 (14 bytes):** A partial [Bitmap16](#) object (section [2.2.2.1](#)), which defines parameters for the bitmap that specifies the pattern for the brush. Fields not described below are specified in section [2.2.2.1](#).

|        |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------|---|---|---|---|---|---|---|-----------|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0      | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8         | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Type   |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    | Width      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Height |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    | WidthBytes |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Planes |   |   |   |   |   |   |   | BitsPixel |   |    |    |    |    |    |    | Bits       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...    |   |   |   |   |   |   |   |           |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Bits (4 bytes):** This field MUST be ignored.

**Reserved (18 bytes):** This field MUST be ignored.

**Pattern (variable):** A variable-length array of bytes that defines the bitmap pixel data that composes the brush pattern. The length of this field, in bytes, can be computed from bitmap parameters as follows.

$$(((\text{Width} * \text{BitsPixel} + 15) \gg 4) \ll 1) * \text{Height}$$

The **Width**, **BitsPixel**, and **Height** values are specified in the **Bitmap16** field of this record.

The [BrushStyle](#) enumeration (section [2.1.1.4](#)) value for the brush object created by this record MUST be BS\_PATTERN.

See section [2.3.4](#) for the specification of other [WMF object](#) records.

### 2.3.4.5 META\_CREATEPENINDIRECT Record

The META\_CREATEPENINDIRECT record creates a [Pen Object \(section 2.2.1.4\)](#).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |     |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6   | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |     |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Pen |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |     |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |     |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) value **META\_CREATEPENINDIRECT**.

**Pen (10 bytes):** [Pen Object](#) data that defines the pen to create.

See section [2.3.4](#) for the specification of other object records.

### 2.3.4.6 META\_CREATEREGION Record

The META\_CREATEREGION record creates a [Region Object \(section 2.2.1.5\)](#).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Region (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) value **META\_CREATEREGION**.

**Region (variable):** [Region Object](#) data that defines the region to create.

See section [2.3.4](#) for the specification of other object records.

### 2.3.4.7 META\_DELETEOBJECT Record

The META\_DELETEOBJECT record deletes an object, including [Bitmap16](#), [Brush](#), [DeviceIndependentBitmap](#), [Font](#), [Palette](#), [Pen](#), and [Region](#). After the object is deleted, its index in the [WMF Object Table](#) is no longer valid but is available to be reused.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16          | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ObjectIndex |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_DELETEOBJECT.

**ObjectIndex (2 bytes):** A 16-bit unsigned integer used to index into the WMF Object Table to get the object to be deleted.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.4](#) for the specification of other Object records.

### 2.3.4.8 META\_DIBCREATEPATTERNBRUSH Record

The META\_DIBCREATEPATTERNBRUSH record creates a [Brush Object \(section 2.2.1.1\)](#) with a pattern specified by a [DeviceIndependentBitmap \(DIB\) Object \(section 2.2.2.9\)](#).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Style             |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorUsage     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Target (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_DIBCREATEPATTERNBRUSH.



**Style (2 bytes):** A 16-bit unsigned integer that defines the brush style. The legal values for this field are defined as follows: if the value is not BS\_PATTERN, BS\_DIBPATTERNPT MUST be assumed. These values are specified in the [BrushStyle Enumeration \(section 2.1.1.4\)](#).

**ColorUsage (2 bytes):** A 16-bit unsigned integer that defines whether the **Colors** field of a DIB Object contains explicit RGB values, or indexes into a palette.

If the **Style** field specifies BS\_PATTERN, a **ColorUsage** value of DIB\_RGB\_COLORS MUST be used regardless of the contents of this field.

If the **Style** field specified anything but BS\_PATTERN, this field MUST be one of the values in the [ColorUsage Enumeration \(section 2.1.1.6\)](#).

**Target (variable):** Variable-bit DIB Object data that defines the pattern to use in the brush.

The following table shows the types of Brush Objects created by the META\_DIBCREATEPATTERNBRUSH record, according to **BrushStyle Enumeration** values.

| BrushStyle      | ColorUsage   | Brush Object created   |
|-----------------|--|--|
| BS_SOLID        | Same as the following BS_DIBPATTERNPT.   | Same as the following BS_DIBPATTERNPT.   |
| BS_NULL         | Same as the following BS_DIBPATTERNPT.   | Same as the following BS_DIBPATTERNPT.   |
| BS_PATTERN      | A <b>ColorUsage Enumeration</b> value, which SHOULD define how to interpret the logical color values in the brush pattern. | A BS_PATTERN Brush Object that SHOULD contain a pattern defined by a <a href="#">Bitmap16 Object</a> . |
| BS_DIBPATTERNPT | A <b>ColorUsage Enumeration</b> value, which SHOULD define how to interpret the logical color values in the brush pattern. | A BS_DIBPATTERNPT Brush Object that SHOULD contain a pattern defined by a DIB Object.                  |
| BS_HATCHED      | Same as the preceding BS_DIBPATTERNPT.   | Same as preceding BS_DIBPATTERNPT.   |

See section [2.3.4](#) for the specification of other object records.

#### 2.3.4.9 META\_SELECTCLIPREGION Record

The META\_SELECTCLIPREGION record specifies a [Region Object \(section 2.2.1.5\)](#) to be the current clipping region.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Region |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SELECTCLIPREGION.

**Region (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the region to be inverted.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.4](#) for the specification of other Object records.

#### 2.3.4.10 META\_SELECTOBJECT Record

The META\_SELECTOBJECT record specifies a graphics object for the playback device context. The new object replaces the previous object of the same type, unless if the previous object is a palette object. If the previous object is a [palette object](#), then the [META\\_SELECTPALETTE](#) record must be used instead of the META\_SELECTOBJECT record, as the META\_SELECTOBJECT record does not support replacing the palette object type.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16          | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ObjectIndex |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SELECTOBJECT.

**ObjectIndex (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the object to be selected.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.4](#) for the specification of other Object records.

#### 2.3.4.11 META\_SELECTPALETTE Record

The META\_SELECTPALETTE record defines the current logical palette with a specified [Palette Object](#).

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16      | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Palette |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SELECTPALETTE.

**Palette (2 bytes):** A 16-bit unsigned integer used to index into the [WMF Object Table](#) to get the Palette Object to be selected.

The WMF Object Table refers to an indexed table of [WMF Objects](#) that are defined in the metafile. See section [3.1.4.1](#) for more information.

See section [2.3.4](#) for the specification of other Object records.

### 2.3.5 State Record Types

This section defines the State record types, which define and manage the graphics properties specified in the [Playback Device Context \(section 3.1.5\)](#).

The following are the State record types.

| Name                   | Section                  | Description   |
|------------------------|--------------------------|---|
| META_ANIMATEPALETTE    | <a href="#">2.3.5.1</a>  | Redefines entries in the logical palette that is defined in the playback device context with a specified <a href="#">Palette Object (section 2.2.1.3)</a> . |
| META_EXCLUDECLIPRECT   | <a href="#">2.3.5.2</a>  | Sets the clipping region that is defined in the playback device context to the existing clipping region minus a specified rectangle.                        |
| META_INTERSECTCLIPRECT | <a href="#">2.3.5.3</a>  | Sets the clipping region that is defined in the playback device context to the intersection of the existing clipping region and a specified rectangle.      |
| META_MOVETO            | <a href="#">2.3.5.4</a>  | Sets the output position in the playback device context to a specified point.   |
| META_OFFSETCLIPRGN     | <a href="#">2.3.5.5</a>  | Moves the clipping region that is defined in the playback device context by specified offsets.  |
| META_OFFSETVIEWPORTORG | <a href="#">2.3.5.6</a>  | Moves the viewport origin in the playback device context by specified horizontal and vertical offsets.  |
| META_OFFSETWINDOWORG   | <a href="#">2.3.5.7</a>  | Moves the output window origin in the playback device context by specified horizontal and vertical offsets.   |
| META_REALIZEPALETTE    | <a href="#">2.3.5.8</a>  | Maps entries from the logical palette that is defined in the playback device context to the system palette.   |
| META_RESIZEPALETTE     | <a href="#">2.3.5.9</a>  | Redefines the size of the logical palette that is defined in the playback device context.   |
| META_RESTOREDC         | <a href="#">2.3.5.10</a> | Restores the playback device context from a previously saved device context.  |
| META_SAVEDC            | <a href="#">2.3.5.11</a> | Saves the playback device context for later retrieval.  |

| Name                      | Section                  | Description   |
|---------------------------|--------------------------|---|
| META_SCALEVIEWPORTEXT     | <a href="#">2.3.5.12</a> | Scales the horizontal and vertical extents of the viewport that is defined in the playback device context using the ratios formed by specified multiplicands and divisors.      |
| META_SCALEWINDOWEXT       | <a href="#">2.3.5.13</a> | Scales the horizontal and vertical extents of the output window that is defined in the playback device context using the ratios formed by specified multiplicands and divisors. |
| META_SETBKCOLOR           | <a href="#">2.3.5.14</a> | Sets the background color in the playback device context to a specified color.  |
| META_SETBKMODE            | <a href="#">2.3.5.15</a> | Sets the background mix mode in the playback device context.  |
| META_SETLAYOUT            | <a href="#">2.3.5.16</a> | Defines the layout orientation in the playback device context.  |
| META_SETMAPMODE           | <a href="#">2.3.5.17</a> | Defines the mapping mode in the playback device context.  |
| META_SETMAPPERFLAGS       | <a href="#">2.3.5.18</a> | Defines the algorithm that the font mapper uses when it maps logical fonts to physical fonts.   |
| META_SETPALENTRIES        | <a href="#">2.3.5.19</a> | Defines RGB color values in a range of entries in the logical palette that is defined in the playback device context.   |
| META_SETPOLYFILLMODE      | <a href="#">2.3.5.20</a> | Defines polygon fill mode in the playback device context for graphics operations that fill polygons.  |
| META_SETRELABS            | <a href="#">2.3.5.21</a> | Undefined and MUST be ignored.  |
| META_SETROP2              | <a href="#">2.3.5.22</a> | Defines the foreground raster operation mixing mode in the playback device context.   |
| META_SETSTRETCHBLTMODE    | <a href="#">2.3.5.23</a> | Defines the bitmap stretching mode in the playback device context.  |
| META_SETTEXTALIGN         | <a href="#">2.3.5.24</a> | Defines text-alignment values in the playback device context.   |
| META_SETTEXTCHAREXTRA     | <a href="#">2.3.5.25</a> | Defines inter-character spacing for text justification in the playback device context.  |
| META_SETTEXTCOLOR         | <a href="#">2.3.5.26</a> | Defines the text foreground color in the playback device context.   |
| META_SETTEXTJUSTIFICATION | <a href="#">2.3.5.27</a> | Defines the amount of space to add to break characters in a string of justified text.   |
| META_SETVIEWPORTEXT       | <a href="#">2.3.5.28</a> | Defines the horizontal and vertical extents of the viewport in the playback device context.   |
| META_SETVIEWPORTORG       | <a href="#">2.3.5.29</a> | Defines the viewport origin in the playback device context.   |
| META_SETWINDOWEXT         | <a href="#">2.3.5.30</a> | Defines the horizontal and vertical extents of the output window in the playback device context.  |
| META_SETWINDOWORG         | <a href="#">2.3.5.31</a> | Defines the output window origin in the playback device context.  |

### 2.3.5.1 META\_ANIMATEPALETTE Record

The META\_ANIMATEPALETTE record redefines entries in the logical palette that is defined in the playback device context with the specified [Palette](#) object (section [2.2.1.3](#)).

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|--------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                  | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Palette (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ANIMATEPALETTE.

**Palette (variable):** A variable-sized [Palette object](#) that specifies a logical palette.

The logical palette that is specified by the [Palette object](#) in this record is the source of the palette changes, and the logical palette that is currently selected into the playback device context is the destination. Entries in the destination palette with the **PC\_RESERVED** [PaletteEntryFlag](#) (section [2.1.1.22](#)) set SHOULD be modified by this record, and entries with that flag clear SHOULD NOT be modified. If none of the entries in the destination palette have the **PC\_RESERVED** flag set, then this record SHOULD have no effect.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.2 META\_EXCLUDECLIPRECT Record

The META\_EXCLUDECLIPRECT record sets the clipping region in the playback device context to the existing clipping region minus the specified rectangle.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Bottom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Right          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Top    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Left           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_EXCLUDECLIPRECT.

**Bottom (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the rectangle.

**Right (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the rectangle.

**Top (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the rectangle.

**Left (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the rectangle.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.3 META\_INTERSECTCLIPRECT Record

The META\_INTERSECTCLIPRECT record sets the clipping region in the playback device context to the intersection of the existing clipping region and the specified rectangle.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Bottom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Right          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Top    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Left           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_INTERSECTCLIPRECT.

**Bottom (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the lower-right corner of the rectangle.

**Right (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the lower-right corner of the rectangle.

**Top (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units, of the upper-left corner of the rectangle.

**Left (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units, of the upper-left corner of the rectangle.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.4 META\_MOVEETO Record

The META\_MOVEETO record sets the output position in the playback device context to a specified point.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_MOVEETO.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.5 META\_OFFSETCLIPRGN Record

The META\_OFFSETCLIPRGN record moves the clipping region in the playback device context by the specified offsets.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16      | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YOffset |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XOffset        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_OFFSETCLIPRGN.

**YOffset (2 bytes):** A 16-bit signed integer that defines the number of logical units to move up or down.

**XOffset (2 bytes):** A 16-bit signed integer that defines the number of logical units to move left or right.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.6 META\_OFFSETVIEWPORTORG Record

The META\_OFFSETVIEWPORTORG record moves the viewport origin in the playback device context by specified horizontal and vertical offsets.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16      | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YOffset |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XOffset        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_OFFSETVIEWPORTORG.

**YOffset (2 bytes):** A 16-bit signed integer that defines the vertical offset, in device units.

**XOffset (2 bytes):** A 16-bit signed integer that defines the horizontal offset, in device units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.7 META\_OFFSETWINDOWORG Record

The META\_OFFSETWINDOWORG record moves the output window origin in the playback device context by specified horizontal and vertical offsets.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16      | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | YOffset |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| XOffset        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_OFFSETWINDOWORG.

**YOffset (2 bytes):** A 16-bit signed integer that defines the vertical offset, in device units.



**XOffset (2 bytes):** A 16-bit signed integer that defines the horizontal offset, in device units.

See section [2.3.5](#) for the specification of other State record types.

#### 2.3.5.8 META\_REALIZEPALETTE Record

The META\_REALIZEPALETTE record maps entries from the logical palette that is defined in the playback device context to the system palette.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_REALIZEPALETTE.

See section [2.3.5](#) for the specification of other State record types.

#### 2.3.5.9 META\_RESIZEPALETTE Record

The META\_RESIZEPALETTE record redefines the size of the logical palette that is defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | NumberOfEntries |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_RESIZEPALETTE.

**NumberOfEntries (2 bytes):** A 16-bit unsigned integer that defines the number of entries in the logical palette.

See section [2.3.5](#) for the specification of other State record types.

#### 2.3.5.10 META\_RESTOREDC Record

The META\_RESTOREDC record restores the playback device context from a previously saved device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | nSavedDC |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_RESTOREDC.

**nSavedDC (2 bytes):** A 16-bit signed integer that defines the saved state to be restored. If this member is positive, **nSavedDC** represents a specific instance of the state to be restored. If this member is negative, **nSavedDC** represents an instance relative to the current state.

See section [3.1.5](#) for a description of the state defined by the playback device context.

See section [2.3.5](#) for the specification of other State record types.

#### 2.3.5.11 META\_SAVEDC Record

The META\_SAVEDC record saves the playback device context for later retrieval.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SAVEDC.

See section [3.1.5](#) for a description of the state defined by the playback device context.

See section [State Record Types \(section 2.3.5\)](#) for the specification of other State record types.

#### 2.3.5.12 META\_SCALEVIEWPORTEXT Record

The META\_SCALEVIEWPORTEXT record scales the horizontal and vertical extents of the viewport that is defined in the playback device context by using the ratios formed by the specified multiplicands and divisors.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | yDenom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| yNum           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | xDenom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| xNum           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SCALEVIEWPORTEXT.

**yDenom (2 bytes):** A 16-bit signed integer that defines the amount by which to divide the result of multiplying the current y-extent by the value of the **yNum** member.

**yNum (2 bytes):** A 16-bit signed integer that defines the amount by which to multiply the current y-extent.

**xDenom (2 bytes):** A 16-bit signed integer that defines the amount by which to divide the result of multiplying the current x-extent by the value of the **xNum** member.

**xNum (2 bytes):** A 16-bit signed integer that defines the amount by which to multiply the current x-extent.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.13 META\_SCALEWINDOWEXT Record

The META\_SCALEWINDOWEXT record scales the horizontal and vertical extents of the output window that is defined in the playback device context by using the ratios formed by specified multiplicands and divisors.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | yDenom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| yNum           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | xDenom |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| xNum           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SCALEWINDOWEXT.

**yDenom (2 bytes):** A 16-bit signed integer that defines the amount by which to divide the result of multiplying the current y-extent by the value of the **yNum** member.

**yNum (2 bytes):** A 16-bit signed integer that defines the amount by which to multiply the current y-extent.

**xDenom (2 bytes):** A 16-bit signed integer that defines the amount by which to divide the result of multiplying the current x-extent by the value of the **xNum** member.

**xNum (2 bytes):** A 16-bit signed integer that defines the amount by which to multiply the current x-extent.

See section [2.3.5](#) for the specification of other State record types.

**2.3.5.14 META\_SETBKCOLOR Record**

The META\_SETBKCOLOR record sets the background color in the playback device context to a specified color, or to the nearest physical color if the device cannot represent the specified color.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6        | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | ColorRef |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETBKCOLOR.

**ColorRef (4 bytes):** A 32-bit [ColorRef Object](#) that defines the color value.

See section [2.3.5](#) for the specification of other State record types.

**2.3.5.15 META\_SETBKMODE Record**

The META\_SETBKMODE record defines the background raster operation mix mode in the playback device context. The background mix mode is the mode for combining pens, text, hatched brushes, and interiors of filled objects with background colors on the output surface.

|            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

|                     |        |
|---------------------|--------|
| RecordFunction      | BkMode |
| Reserved (optional) |        |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETBKMODE.

**BkMode (2 bytes):** A 16-bit unsigned integer that defines background mix mode. This MUST be one of the values in the [MixMode Enumeration \(section 2.1.1.20\)](#).

**Reserved (2 bytes):** An optional 16-bit field that MUST be ignored. [<60>](#)

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.16 META\_SETLAYOUT Record

The META\_SETLAYOUT record defines the layout orientation in the playback device context. [<61>](#)  
The layout orientation determines the direction in which text and graphics are drawn

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16     | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Layout |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETLAYOUT.

**Layout (2 bytes):** A 16-bit unsigned integer that defines the layout of text and graphics. This MUST be one of the values in the [Layout Enumeration \(section 2.1.1.13\)](#).

**Reserved (2 bytes):** A 16-bit field that MUST be ignored.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.17 META\_SETMAPMODE Record

The META\_SETMAPMODE record defines the mapping mode in the playback device context. The mapping mode defines the unit of measure used to transform page-space units into device-space units, and also defines the orientation of the device's x and y axes.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16      | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |         |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | MapMode |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETMAPMODE.

**MapMode (2 bytes):** A 16-bit unsigned integer that defines the mapping mode. This MUST be one of the values enumerated in the [MapMode Enumeration](#) table.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.18 META\_SETMAPPERFLAGS Record

The META\_SETMAPPERFLAGS record defines the algorithm that the font mapper uses when it maps logical fonts to physical fonts.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16           | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | MapperValues |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETMAPPERFLAGS.

**MapperValues (4 bytes):** A 32-bit unsigned integer that defines whether the font mapper should attempt to match a font's aspect ratio to the current device's aspect ratio. If bit 0 is set, the mapper selects only matching fonts.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.19 META\_SETPALENTRIES Record

The META\_SETPALENTRIES record defines RGB color values in a range of entries in the logical palette that is defined in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|--------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                  | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Palette (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                    |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETPALENTRIES.

**Palette (variable):** A [Palette](#) object (section [2.2.1.3](#)), which defines the palette information.

The META\_SETPALENTRIES record modifies the logical palette that is currently selected in the playback device context. A [META\\_SELECTPALETTE record \(section 2.3.4.11\)](#) MUST have been used to specify that logical palette in the form of a Palette object (section 2.2.1.3) prior to the occurrence of the META\_SETPALENTRIES record in the metafile. A Palette object is one of the graphics objects that is maintained in the playback device context during playback of the metafile. See [Graphics Objects \(section 1.3.2\)](#) for more information.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.20 META\_SETPOLYFILLMODE Record

The META\_SETPOLYFILLMODE record sets polygon fill mode in the playback device context for graphics operations that fill polygons.

|                     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |              |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|---------------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|--------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6            | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize          |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |              |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | PolyFillMode |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| Reserved (optional) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |              |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETPOLYFILLMODE.

**PolyFillMode (2 bytes):** A 16-bit unsigned integer that defines polygon fill mode. This MUST be one of the values in the [PolyFillMode Enumeration \(section 2.1.1.25\)](#).

**Reserved (2 bytes):** An optional 16-bit field that MUST be ignored. [<62>](#)

See section [2.3.5](#) for the specification of other State record types.

**2.3.5.21 META\_SETRELABS Record**

The META\_SETRELABS record is reserved and not supported.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETRELABS.

See section [2.3.5](#) for the specification of other State record types.

**2.3.5.22 META\_SETROP2 Record**

The META\_SETROP2 record defines the foreground raster operation mix mode in the playback device context. The foreground mix mode is the mode for combining pens and interiors of filled objects with foreground colors on the output surface.

|                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | DrawMode |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved (optional) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value META\_SETROP2.

**DrawMode (2 bytes):** A 16-bit unsigned integer that defines the foreground binary raster operation mixing mode. This MUST be one of the values in the [Binary Raster Operation Enumeration \(section 2.1.1.2\)](#).

**Reserved (2 bytes):** An optional 16-bit field that MUST be ignored.[<63>](#)

See section [2.3.5](#) for the specification of other State record types.



### 2.3.5.23 META\_SETSTRETCHBLTMODE Record

The META\_SETSTRETCHBLTMODE record defines the bitmap stretching mode in the playback device context.

|                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16          | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | StretchMode |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved (optional) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |             |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_SETSTRETCHBLTMODE**.

**StretchMode (2 bytes):** A 16-bit unsigned integer that defines bitmap stretching mode. This MUST be one of the values in the [StretchMode Enumeration \(section 2.1.1.30\)](#).

**Reserved (2 bytes):** An optional 16-bit field that MUST be ignored.[<64>](#)

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.24 META\_SETTEXTALIGN Record

The META\_SETTEXTALIGN record defines text-alignment values in the playback device context.

|                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | TextAlignmentMode |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved (optional) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration \(section 2.1.1.1\)](#) value **META\_SETTEXTALIGN**.

**TextAlignmentMode (2 bytes):** A 16-bit unsigned integer that defines text alignment. This value MUST be a combination of one or more [TextAlignmentMode Flags \(section 2.1.2.3\)](#) for text with a horizontal baseline, and [VerticalTextAlignmentMode Flags \(section 2.1.2.4\)](#) for text with a vertical baseline.

**Reserved (2 bytes):** An optional 16-bit field that MUST be ignored. [<65>](#)

See section [2.3.5](#) for the specification of other State record types.

#### 2.3.5.25 META\_SETTEXTCHAREXTRA Record

The META\_SETTEXTCHAREXTRA record defines inter-character spacing for text justification in the playback device context. Spacing is added to the white space between each character, including break characters, when a line of justified text is output.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |           |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6         | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |           |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | CharExtra |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value **META\_SETTEXTCHAREXTRA**.

**CharExtra (2 bytes):** A 16-bit unsigned integer that defines the amount of extra space, in logical units, to be added to each character. If the current mapping mode is not MM\_TEXT, this value is transformed and rounded to the nearest pixel. For details about setting the mapping mode, see META\_SETMAPMODE (section 2.3.5.17).

See section [2.3.5](#) for the specification of other state record types.

#### 2.3.5.26 META\_SETTEXTCOLOR Record

The META\_SETTEXTCOLOR record defines the text foreground color in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6        | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | ColorRef |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value **META\_SETTEXTCOLOR**.

**ColorRef (4 bytes):** A 32-bit [ColorRef Object](#) that defines the color value.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.27 META\_SETTEXTJUSTIFICATION Record

The META\_SETTEXTJUSTIFICATION record defines the amount of space to add to break characters in a string of justified text.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16         | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BreakCount |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| BreakExtra     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) value **META\_SETTEXTJUSTIFICATION**.

**BreakCount (2 bytes):** A 16-bit unsigned integer that specifies the number of space characters in the line.

**BreakExtra (2 bytes):** A 16-bit unsigned integer that specifies the total extra space, in logical units, to be added to the line of text. If the current mapping mode is not MM\_TEXT, the value identified by the **BreakExtra** member is transformed and rounded to the nearest pixel. For details about setting the mapping mode, see [META\\_SETMAPMODE \(section 2.3.5.17\)](#).

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.28 META\_SETVIEWPORTEXT Record

The META\_SETVIEWPORTEXT record sets the horizontal and vertical extents of the viewport in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETVIEWPORTEXT.

**Y (2 bytes):** A 16-bit signed integer that defines the vertical extent of the viewport in device units.

**X (2 bytes):** A 16-bit signed integer that defines the horizontal extent of the viewport in device units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.29 META\_SETVIEWPORTORG Record

The META\_SETVIEWPORTORG record defines the viewport origin in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETVIEWPORTORG.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.30 META\_SETWINDOWEXT Record

The META\_SETWINDOWEXT record defines the horizontal and vertical extents of the output window in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETWINDOWEXT.

**Y (2 bytes):** A 16-bit signed integer that defines the vertical extent of the window in logical units.

**X (2 bytes):** A 16-bit signed integer that defines the horizontal extent of the window in logical units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.5.31 META\_SETWINDOWORG Record

The META\_SETWINDOWORG record defines the output window origin in the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Y  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| X              |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this WMF record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_SETWINDOWORG.

**Y (2 bytes):** A 16-bit signed integer that defines the y-coordinate, in logical units.

**X (2 bytes):** A 16-bit signed integer that defines the x-coordinate, in logical units.

See section [2.3.5](#) for the specification of other State record types.

### 2.3.6 Escape Record Types

This section defines the Escape Record Types, which specify extensions to metafile functionality. The generic format of all escape records is specified by the [META\\_ESCAPE \(section 2.3.6.1\)](#) record.

The following are the escape record types.

| Name             | Section                 | Description                                     |
|------------------|-------------------------|---|
| ABORTDOC         | <a href="#">2.3.6.2</a> | Stops processing the current document.          |
| BEGIN_PATH       | <a href="#">2.3.6.3</a> | Opens a path.                                   |
| CHECK_JPEGFORMAT | <a href="#">2.3.6.4</a> | Determines whether it can handle the given JPEG |

| Name                          | Section                  | Description   |
|-------------------------------|--------------------------|---|
|                               |                          | image.  |
| CHECK_PNGFORMAT               | <a href="#">2.3.6.5</a>  | Determines whether it can handle the given PNG image.   |
| CLIP_TO_PATH                  | <a href="#">2.3.6.6</a>  | Applies a function to the current PostScript clipping path.   |
| CLOSE_CHANNEL                 | <a href="#">2.3.6.7</a>  | Same as <b>ENDDOC</b> .   |
| DOWNLOAD_FACE                 | <a href="#">2.3.6.8</a>  | Sets the font face name on the output device.   |
| DOWNLOAD_HEADER               | <a href="#">2.3.6.9</a>  | Downloads sets of PostScript procedures.  |
| DRAW_PATTERNRECT              | <a href="#">2.3.6.10</a> | Draws a rectangle with a defined pattern.   |
| ENCAPSULATED_POSTSCRIPT       | <a href="#">2.3.6.11</a> | Sends arbitrary encapsulated PostScript (EPS) data directly to the printer driver.                                |
| END_PATH                      | <a href="#">2.3.6.12</a> | Ends a path.  |
| ENDDOC                        | <a href="#">2.3.6.13</a> | Notifies the printer driver that a new print job is ending.   |
| EPS_PRINTING                  | <a href="#">2.3.6.14</a> | Indicates the start and end of EPS printing.  |
| EXTTEXTOUT                    | <a href="#">2.3.6.15</a> | Draws text using the currently selected font, background color, and text color.                                   |
| GET_COLORTABLE                | <a href="#">2.3.6.16</a> | Gets color table values from the printer driver.  |
| GET_DEVICEUNITS               | <a href="#">2.3.6.17</a> | Gets the device units currently configured on the output device.  |
| GET_EXTENDED_TEXTMETRICS      | <a href="#">2.3.6.18</a> | Gets the extended text metrics that are currently configured on the printer driver.                               |
| GET_FACENAME                  | <a href="#">2.3.6.19</a> | Gets the font face name currently configured on the output device.  |
| GET_PAIRKERNTABLE             | <a href="#">2.3.6.20</a> | Gets the font kern table currently defined on the output device.  |
| GET_PHYSPAGESIZE              | <a href="#">2.3.6.21</a> | Retrieves the physical page size currently selected on the output device.   |
| GET_PRINTINGOFFSET            | <a href="#">2.3.6.22</a> | Retrieves the offset from the upper-left corner of the physical page where the actual printing or drawing begins. |
| GET_PS_FEATURESETTING         | <a href="#">2.3.6.23</a> | Queries the printer driver for information about PostScript features supported on the output device.              |
| GET_SCALINGFACTOR             | <a href="#">2.3.6.24</a> | Retrieves the scaling factors for the x-axis and the y-axis of a printer.   |
| META_ESCAPE_ENHANCED_METAFILE | <a href="#">2.3.6.25</a> | Used to embed an EMF metafile within a WMF metafile.  |

| Name                   | Section                  | Description   |
|------------------------|--------------------------|---|
| METAFILE_DRIVER        | <a href="#">2.3.6.26</a> | Queries the printer driver about its support for metafiles on the output device.  |
| NEWFRAME               | <a href="#">2.3.6.27</a> | Notifies the printer driver that the application has finished writing to a page.  |
| NEXTBAND               | <a href="#">2.3.6.28</a> | Notifies the printer driver that the application has finished writing to a band.  |
| PASSTHROUGH            | <a href="#">2.3.6.29</a> | Passes through arbitrary data to the printer driver.  |
| POSTSCRIPT_DATA        | <a href="#">2.3.6.30</a> | Sends arbitrary PostScript data to the output device.   |
| POSTSCRIPT_IDENTIFY    | <a href="#">2.3.6.31</a> | Sets the printer driver to either PostScript-centric or GDI-centric mode.   |
| POSTSCRIPT_IGNORE      | <a href="#">2.3.6.32</a> | Notifies the output device to ignore PostScript data.   |
| POSTSCRIPT_INJECTION   | <a href="#">2.3.6.33</a> | Inserts a block of raw data into a PostScript stream.   |
| POSTSCRIPT_PASSTHROUGH | <a href="#">2.3.6.34</a> | Sends arbitrary data directly to a printer driver, which is expected to process this data only when in PostScript mode. |
| OPEN_CHANNEL           | <a href="#">2.3.6.35</a> | Acts the same as <b>STARTDOC</b> , with a NULL document and output filename, and data in raw mode.                      |
| QUERY_DIBSUPPORT       | <a href="#">2.3.6.36</a> | Queries the printer driver about its support for DIBs on the output device.   |
| QUERY_ESCSUPPORT       | <a href="#">2.3.6.37</a> | Queries the printer driver to determine whether a specific WMF escape function is supported on the output device.       |
| SET_COLORTABLE         | <a href="#">2.3.6.38</a> | Sets color table values.  |
| SET_COPYCOUNT          | <a href="#">2.3.6.39</a> | Sets the number of copies.  |
| SET_LINECAP            | <a href="#">2.3.6.40</a> | Specifies the line-ending mode to use in drawing to the output device.  |
| SET_LINEJOIN           | <a href="#">2.3.6.41</a> | Specifies the line-joining mode to use in drawing to the output device.   |
| SET_MITERLIMIT         | <a href="#">2.3.6.42</a> | Sets the limit for the length of miter joins to use in drawing to the output device.                                    |
| SPCLPASSTHROUGH2       | <a href="#">2.3.6.43</a> | Enables documents to include private procedures and other arbitrary data in documents.                                  |
| STARTDOC               | <a href="#">2.3.6.44</a> | Notifies the printer driver that a new print job is starting.   |

### 2.3.6.1 META\_ESCAPE Record

The META\_ESCAPE record specifies extensions to WMF functionality that are not directly available through other records defined in the [RecordType](#) enumeration (section [2.1.1.1](#)). The [MetafileEscapes](#) enumeration (section [2.1.1.17](#)) lists these extensions.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                       |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6                     | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                       |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeData (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                       |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the **RecordType** enumeration value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be from the **MetafileEscapes** enumeration.

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **EscapeData** field.

**EscapeData (variable):** An array of bytes of size **ByteCount**.

Every META\_ESCAPE record MUST include a **MetafileEscapes** function specifier, followed by arbitrary data. The data SHOULD NOT contain position-specific data that assumes the location of a particular record within the metafile, because one metafile might be embedded within another.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.2 ABORTDOC Record

The ABORTDOC record stops processing the current document and erases everything drawn since the last [STARTDOC](#) record was processed.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |



**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0002 (ABORTDOC) from [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.3 BEGIN\_PATH Record

The BEGIN\_PATH record opens a path.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1000 (BEGIN\_PATH) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.4 CHECK\_JPEGFORMAT Record

The CHECK\_JPEGFORMAT record specifies whether the printer driver supports JPEG image output.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|           |                       |
|-----------|-----------------------|
| ByteCount | JPEGBuffer (variable) |
| ...       |                       |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1017 (**CHECK\_JPEGFORMAT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **JPEGBuffer** field.

**JPEGBuffer (variable):** A buffer of JPEG image data.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.5 CHECK\_PNGFORMAT Record

The CHECK\_PNGFORMAT record queries the driver to see if it can handle the given PNG image and parses the PNG image to determine whether the driver can support it.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                   | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | PNGBuffer (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1018 (**CHECK\_PNGFORMAT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **PNGBuffer** field.

**PNGBuffer (variable):** A buffer of PNG image data.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.6 CLIP\_TO\_PATH Record

The CLIP\_TO\_PATH record applies a function to the current PostScript clipping path.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ClipFunction   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Reserved1      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in this record. This value MUST be 0x0000000E.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1001 (**CLIP\_TO\_PATH**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows. This value MUST be 0x0004.

**ClipFunction (2 bytes):** A 16-bit unsigned integer that defines the function to apply to the PostScript clipping path. This value MUST be a [PostScriptClipping](#) enumeration (section [2.1.1.27](#)) value.

| Name           | Value  |
|----------------|--------|
| CLIP_SAVE      | 0x0000 |
| CLIP_RESTORE   | 0x0001 |
| CLIP_INCLUSIVE | 0x0002 |

**Reserved1 (2 bytes):** This value SHOULD be zero and SHOULD be ignored by the client.[<66>](#)

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.7 CLOSE\_CHANNEL Record

The CLOSE\_CHANNEL record notifies the printer driver that the current print job is ending. This is the same function as the [ENDDOC](#) record. A CLOSE\_CHANNEL record MUST be preceded by an [OPEN\\_CHANNEL](#) record.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The low-order byte MUST match the low-order byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1010 (CLOSE\_CHANNEL) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.8 DOWNLOAD\_FACE Record

The DOWNLOAD\_FACE record sends the font face.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The low-order byte MUST match the low-order byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0202 (DOWNLOAD\_FACE) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.9 DOWNLOAD\_HEADER Record

The DOWNLOAD\_HEADER record instructs the driver to download all sets of PostScript procedures.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be set to 0x100F (DOWNLOAD\_HEADER) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.10 DRAW\_PATTERNRECT Record

The DRAW\_PATTERNRECT record draws a rectangle with a defined pattern.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Position       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Size           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Style          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Pattern        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0019 (**DRAW\_PATTERNRECT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows. This MUST be 0x0014.

**Position (8 bytes):** A [PointL](#) object (section [2.2.2.15](#)) that defines the position of the rectangle.

**Size (8 bytes):** A [PointL](#) object that defines the dimensions of the rectangle.

**Style (2 bytes):** A 16-bit unsigned integer that defines the style.

**Pattern (2 bytes):** A 16-bit unsigned integer that defines the pattern.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.11 ENCAPSULATED\_POSTSCRIPT Record

The ENCAPSULATED\_POSTSCRIPT record sends arbitrary PostScript data directly to a printer driver.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Size           |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Version        |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Points         |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

|     |                 |
|-----|-----------------|
| ... | Data (variable) |
| ... |                 |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The low-order byte MUST match the low-order byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1014 (**ENCAPSULATED\_POSTSCRIPT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows. This value SHOULD be greater than or equal to the value of the **Size** field. [<67>](#)

**Size (4 bytes):** A 32-bit unsigned integer that specifies the total size, in bytes, of the **Size**, **Version**, **Points**, and **Data** fields.

**Version (4 bytes):** A 32-bit unsigned integer that defines the PostScript language level.

**Points (24 bytes):** An array of three [PointL](#) objects (section [2.2.2.15](#)) that define the output parallelogram in **28.4 FIX** device coordinates.

**Data (variable):** The PostScript data.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.12 END\_PATH Record

The END\_PATH record specifies the end of a path.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1002 (END\_PATH) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.13 ENDDOC Record

The ENDDOC record notifies the printer driver that the current print job is ending.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000B (ENDDOC) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.14 EPS\_PRINTING Record

The EPS\_PRINTING record indicates the start or end of Encapsulated PostScript (EPS) printing.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | SetEpsPrinting |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value META\_ESCAPE.



**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0021 (**EPS\_PRINTING**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **SetEpsPrinting** field. This MUST be 0x0002.

**SetEpsPrinting (2 bytes):** A 16-bit unsigned integer that indicates the start or end of EPS printing. If the value is nonzero, the start of EPS printing is indicated; otherwise, the end is indicated.

| Value                          | Meaning                    |
|--------------------------------|----------------------------|
| Start<br>0x0000 < <i>value</i> | The start of EPS printing. |
| End<br>0x0000                  | The end of EPS printing.   |

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.15 EXTTEXTOUT Record

The EXTTEXTOUT record draws text using the currently selected font, background color, and text color.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0200 (EXTTEXTOUT) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.16 GET\_COLORTABLE Record

The GET\_COLORTABLE record gets color table values from the printer driver.

|                             |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|-----------------------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0                           | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize                  |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction              |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount                   |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Start          |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ColorTableBuffer (variable) |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...                         |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in this record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0005 (**GET\_COLORTABLE**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows.

**Start (2 bytes):** A 16-bit unsigned integer that defines the offset from the beginning of the record to the start of the color table data in the **ColorTable** field.

**ColorTableBuffer (variable):** A buffer containing the color table that is obtained from the printer driver, which is not required to be contiguous with the static part of the record.

|                           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                         | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| UndefinedSpace (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ColorTable (variable)     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**UndefinedSpace (variable):** An optional field that MUST be ignored.

**ColorTable (variable):** An array of bytes that define the color table. The location of this field within the record is specified by the **Start** field.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.17 GET\_DEVICEUNITS Record

The GET\_DEVICEUNITS record gets the current device units.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x002A (GET\_DEVICEUNITS) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.18 GET\_EXTENDED\_TEXTMETRICS Record

The GET\_EXTENDED\_TEXTMETRICS record gets the extended text metrics that are currently configured on the printer driver and applies them to the playback device context.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0100 (GET\_EXTENDED\_TEXTMETRICS) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.19 GET\_FACENAME Record

The GET\_FACENAME record gets the font face name.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0201 (GET\_FACENAME) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.20 GET\_PAIRKERNTABLE Record

The GET\_PAIRKERNTABLE record gets the font kern table.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0102 (GET\_PAIRKERNTABLE) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.21 GET\_PHYSPAGESIZE Record

The GET\_PHYSPAGESIZE record retrieves the physical page size and copies it to a specified location.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000C (GET\_PHYSPAGESIZE) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.22 GET\_PRINTINGOFFSET Record

The GET\_PRINTINGOFFSET record retrieves the offset from the upper-left corner of the physical page where the actual printing or drawing begins.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000D (GET\_PRINTINGOFFSET) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.23 GET\_PS\_FEATURESETTING Record

The GET\_PS\_FEATURESETTING record is used to query the driver concerning PostScript features.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Feature        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1019 (**GET\_PS\_FEATURESETTING**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Feature** field. This MUST be 0x0004.

**Feature (4 bytes):** A 32-bit signed integer that identifies the feature setting being queried. Possible values are defined in the [PostScriptFeatureSetting](#) enumeration (section [2.1.1.28](#)).

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.24 GET\_SCALINGFACTOR Record

The GET\_SCALINGFACTOR record retrieves the scaling factors for the x-axis and the y-axis of a printer.

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                |                |
|----------------|----------------|
| RecordFunction | EscapeFunction |
| ByteCount      |                |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000E (GET\_SCALINGFACTOR) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.25 META\_ESCAPE\_ENHANCED\_METAFILE Record

The META\_ESCAPE\_ENHANCED\_METAFILE record is used to embed an EMF metafile within a WMF metafile. The EMF metafile is broken up into sections, each represented by one **META\_ESCAPE\_ENHANCED\_METAFILE** record.

|                          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                        | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize               |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | CommentIdentifier |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | CommentType       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Version           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Checksum          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Flags                    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| CommentRecordCount       |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| CurrentRecordSize        |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RemainingBytes           |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| EnhancedMetafileDataSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                                 |
|---------------------------------|
| EnhancedMetafileData (variable) |
| ...                             |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of WORDs in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000F (**META\_ESCAPE\_ENHANCED\_METAFILE**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows. This value MUST be 34 plus the value of the **EnhancedMetafileDataSize** field.

**CommentIdentifier (4 bytes):** A 32-bit unsigned integer that defines this record as a WMF Comment record. This value MUST be 0x43464D57.

**CommentType (4 bytes):** A 32-bit unsigned integer that identifies the type of comment in this record. This value MUST be 0x00000001.

**Version (4 bytes):** A 32-bit unsigned integer that specifies EMF metafile interoperability. This SHOULD be 0x00010000 [<68>](#).

**Checksum (2 bytes):** A 16-bit unsigned integer used to validate the correctness of the embedded EMF stream. This value MUST be the one's-complement of the result of applying an XOR operation to all WORDs in the EMF stream.

**Flags (4 bytes):** This 32-bit unsigned integer is unused and MUST be set to zero.

**CommentRecordCount (4 bytes):** A 32-bit unsigned integer that specifies the total number of consecutive **META\_ESCAPE\_ENHANCED\_METAFILE** records that contain the embedded EMF metafile.

**CurrentRecordSize (4 bytes):** A 32-bit unsigned integer that specifies the size, in bytes, of the **EnhancedMetafileData** field. This value MUST be less than or equal to 8,192.

**RemainingBytes (4 bytes):** A 32-bit unsigned integer that specifies the number of bytes in the EMF stream that remain to be processed after this record. Those additional EMF bytes MUST follow in the **EnhancedMetafileData** fields of subsequent **META\_ESCAPE\_ENHANCED\_METAFILE** escape records.

**EnhancedMetafileDataSize (4 bytes):** A 32-bit unsigned integer that specifies the total size of the EMF stream embedded in this sequence of **META\_ESCAPE\_ENHANCED\_METAFILE** records.

**EnhancedMetafileData (variable):** A segment of an EMF file. The bytes in consecutive **META\_ESCAPE\_ENHANCED\_METAFILE** records MUST be concatenated to represent the entire embedded EMF file.

See section [2.3.6](#) for the specification of other escape record types.



### 2.3.6.26 METAFILE\_DRIVER Record

The METAFILE\_DRIVER record queries the printer driver about its support for metafiles on the output device.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in this record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines the record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0801 (**METAFILE\_DRIVER**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.27 NEWFRAME Record

The NEWFRAME record informs the printer that the application has finished writing to a page.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0001 (**NEWFRAME**) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.28 NEXTBAND Record

The NEXTBAND record informs the printer that the application has finished writing to a band.

Band information is no longer used.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0003 (NEXTBAND) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.29 PASSTHROUGH Record

The PASSTHROUGH record passes through arbitrary data to the printer driver.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction  |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Data (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0013 (**PASSTHROUGH**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Data** field.

**Data (variable):** An array of bytes of size **ByteCount**.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.30 POSTSCRIPT\_DATA Record

The POSTSCRIPT\_DATA record sends arbitrary PostScript data to the printer driver.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Data (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0025 (**POSTSCRIPT\_DATA**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Data** field.

**Data (variable):** An array of bytes of size **ByteCount**.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.31 POSTSCRIPT\_IDENTIFY Record

The POSTSCRIPT\_IDENTIFY record sets the printer driver to either PostScript-centric or GDI-centric mode.

|            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|                |                 |
|----------------|-----------------|
| RecordFunction | EscapeFunction  |
| ByteCount      | Data (variable) |
| ...            |                 |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1005 (**POSTSCRIPT\_IDENTIFY**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Data** field.

**Data (variable):** An array of bytes of size **ByteCount**.

**Note** This record MUST be processed before the [STARTDOC](#) record.

See section [Escape Record Types \(section 2.3.6\)](#) for the specification of other escape record types.

### 2.3.6.32 POSTSCRIPT\_IGNORE Record

The POSTSCRIPT\_IGNORE record informs the device to ignore the PostScript data.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0026 (**POSTSCRIPT\_IGNORE**) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.33 POSTSCRIPT\_INJECTION Record

The POSTSCRIPT\_INJECTION record inserts a block of raw data into a PostScript stream. The input **MUST** be a 32-bit quantity specifying the number of bytes to inject, a 16-bit quantity specifying the injection point, and a 16-bit quantity specifying the page number, followed by the bytes to inject.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|-----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction  |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Data (variable) |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                 |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte **MUST** match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value **MUST** be 0x1006 (**POSTSCRIPT\_INJECTION**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Data** field.

**Data (variable):** An array of bytes of size **ByteCount**.

**Note** This record **MUST** be processed before a [STARTDOC](#) record (section [2.3.6.44](#)).

See section [Escape Record Types \(section 2.3.6\)](#) for the specification of other escape record types.

### 2.3.6.34 POSTSCRIPT\_PASSTHROUGH Record

The POSTSCRIPT\_PASSTHROUGH record sends arbitrary data directly to the driver. The driver is expected to only process this data when in PostScript mode. For more information, see the [POSTSCRIPT\\_IDENTIFY \(section 2.3.6.31\)](#) Escape record.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16              | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                 |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction  |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Data (variable) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

|     |
|-----|
| ... |
|-----|

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x1013 (**POSTSCRIPT\_PASSTHROUGH**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Data** field.

**Data (variable):** An array of bytes of size **ByteCount**.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.35 OPEN\_CHANNEL Record

The OPEN\_CHANNEL notifies the printer driver that a new print job is starting. This is the same function as a [STARTDOC](#) record specified with a NULL document and output file name, data in raw mode, and a type of zero.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x100E (**OPEN\_CHANNEL**) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.36 QUERY\_DIBSUPPORT Record

The QUERY\_DIBSUPPORT record queries the driver about its support for [DIBs](#).

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the WMF record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType Enumeration](#) table value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0C01 (QUERY\_DIBSUPPORT) from the [MetafileEscapes Enumeration](#) table.

**ByteCount (2 bytes):** A 16-bit unsigned integer that MUST be 0x0000.

See section [2.3.6](#) for the specification of other Escape record types.

### 2.3.6.37 QUERY\_ESCSUPPORT Record

The QUERY\_ESCSUPPORT record queries the printer driver to determine whether a specific WMF escape function is supported on the output device.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Query          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value META\_ESCAPE.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0008 (QUERY\_ESCSUPPORT) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Query** field. This MUST be 0x0002.

**Query (2 bytes):** A 16-bit unsigned integer that MUST be a value from the **MetafileEscapes**. This record specifies a query of whether this escape is supported.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.38 SET\_COLORTABLE Record

The SET\_COLORTABLE record sets the color table.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------------|----|----|----|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                    | 17 | 18 | 19 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction        |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorTable (variable) |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of **WORDS** in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the **RecordType** enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0004 (**SET\_COLORTABLE**) from the **MetafileEscapes** enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **ColorTable** field.

**ColorTable (variable):** A **ByteCount** length byte array containing the color table.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.39 SET\_COPYCOUNT Record

The SET\_COPYCOUNT record sets the number of copies.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | CopyCount      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |



**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0011 (**SET\_COPYCOUNT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **CopyCount** field. This MUST be 0x0002.

**CopyCount (2 bytes):** A 16-bit unsigned integer that specifies the number of copies to print.

See section [2.3.6](#) for the specification of other escape record types.

#### 2.3.6.40 SET\_LINECAP Record

The SET\_LINECAP record specifies the type of line-ending to use in subsequent graphics operations.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Cap            |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The low-order byte MUST match the low-order byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0015 (**SET\_LINECAP**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Cap** field. This MUST be 0x0004.

**Cap (4 bytes):** A 32-bit signed integer that defines the type of line cap. Possible values are specified in the [PostScriptCap Enumeration](#) table.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.41 SET\_LINEJOIN Record

The SET\_LINEJOIN record specifies the type of line-joining to use in subsequent graphics operations.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | Join           |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0016 (**SET\_LINEJOIN**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **Join** field. This MUST be 0x0004.

**Join (4 bytes):** A 32-bit signed integer that specifies the type of line join. Possible values are specified in [PostScriptJoin Enumeration](#) table.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.42 SET\_MITERLIMIT Record

The SET\_MITERLIMIT record sets the limit for the length of miter joins to use in subsequent graphics operations.

|                |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
|----------------|---|---|---|---|---|---|---|---|---|----|---|---|---|---|---|----------------|---|---|---|----|---|---|---|---|---|---|---|---|---|----|---|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 1 | 2 | 3 | 4 | 5 | 6              | 7 | 8 | 9 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 30 | 1 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | EscapeFunction |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   | MiterLimit     |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |
| ...            |   |   |   |   |   |   |   |   |   |    |   |   |   |   |   |                |   |   |   |    |   |   |   |   |   |   |   |   |   |    |   |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x0017 (**SET\_MITERLIMIT**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#))

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **MiterLimit** field. This MUST be 0x0004.

**MiterLimit (4 bytes):** A 32-bit signed integer that specifies the miter limit.

See section [2.3.6](#) for the specification of other escape record types.

### 2.3.6.43 SPCLPASSTHROUGH2 Record

The SPCLPASSTHROUGH2 record enables documents to include private procedures and other resources to send to the printer driver.

|                    |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                  | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16             | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ByteCount          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Reserved       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Size           |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RawData (variable) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x11D8 (**SPCLPASSTHROUGH2**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the record data that follows.

**Reserved (4 bytes):** A 32-bit unsigned integer that is not used and MUST be ignored.

**Size (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **RawData** field.

**RawData (variable):** The **Size**-length byte array of unprocessed private data to send to the printer driver.

See section [2.3.6](#) for the specification of other escape record types.

#### 2.3.6.44 STARTDOC Record

The STARTDOC record informs the printer driver that a new print job is starting.

|                |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                    |    |    |    |    |   |   |   |   |   |   |   |   |   |    |    |
|----------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------------------|----|----|----|----|---|---|---|---|---|---|---|---|---|----|----|
| 0              | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                 | 17 | 18 | 19 | 20 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 |
| RecordSize     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                    |    |    |    |    |   |   |   |   |   |   |   |   |   |    |    |
| RecordFunction |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | EscapeFunction     |    |    |    |    |   |   |   |   |   |   |   |   |   |    |    |
| ByteCount      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | DocName (variable) |    |    |    |    |   |   |   |   |   |   |   |   |   |    |    |
| ...            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                    |    |    |    |    |   |   |   |   |   |   |   |   |   |    |    |

**RecordSize (4 bytes):** A 32-bit unsigned integer that defines the number of [WORDS](#) in the record.

**RecordFunction (2 bytes):** A 16-bit unsigned integer that defines this record type. The lower byte MUST match the lower byte of the [RecordType](#) enumeration (section [2.1.1.1](#)) value **META\_ESCAPE**.

**EscapeFunction (2 bytes):** A 16-bit unsigned integer that defines the escape function. The value MUST be 0x000A (**STARTDOC**) from the [MetafileEscapes](#) enumeration (section [2.1.1.17](#)).

**ByteCount (2 bytes):** A 16-bit unsigned integer that specifies the size, in bytes, of the **DocName** field. This size MUST be less than 260.

**DocName (variable):** A string of **ByteCount** 8-bit characters that contains the name of the document.

See section [2.3.6](#) for the specification of other escape record types.

## 3 Structure Examples

### 3.1 Metafile Design

#### 3.1.1 Device Independence

WMF metafiles are useful for transferring images between applications. Most applications support the Clipboard format associated with metafiles, called **METAFILEPICT** (for more information, see [\[MSDN-CLIPFORM\]](#)). When treated as a single graphics primitive, a metafile is easy to paste into an application without that application needing to know the specific content of the picture. An application can store a metafile in global memory or to disk.

The mapping mode of a metafile can be altered during playback. Thus, the image can be scaled arbitrarily, with every component scaling separately, which minimizes the loss of information for the image as a whole, which is not characteristic of bitmaps.

To ensure that metafiles can be transported between different computers and applications, any application that creates a metafile needs to ensure that the metafile is device independent and sizable. The following guidelines help ensure that every metafile can be accepted and manipulated by other applications:

- Set the mapping mode as one of the first records. Some applications only accept metafiles that are in MM\_ANISOTROPIC mode.
- Set the [META\\_SETWINDOWORG](#) and [META\\_SETWINDOWEXT](#) records. Do not use the [META\\_SETVIEWPORTTEXT](#) or [META\\_SETVIEWPORTORG](#) record if the user will be able to resize or change the dimensions of the object.
- Do not use any of the region records, because they are device dependent.
- Use [META\\_STRETCHBLT](#) or [META\\_STRETCHDIB](#) instead of [META\\_BITBLT](#).
- Terminate the metafile with a [META\\_EOF](#) (0x0000) record.

#### 3.1.2 Byte Ordering Example

The following code snippet illustrates how the use of the big-endian and little-endian methods can affect the compatibility of applications.

```
#include <unistd.h>
#include <sys/stat.h>
#include <fcntl.h>
int main()
{
    int buf;
    int in;
    int nread;
    in = open("file.in", O_RDONLY);
    nread = read(in, (int *) &buf, sizeof(buf));
    printf("First Integer in file.in = %x\n", buf);
    exit(0);
}
```

In the preceding code, if the first integer word stored in the file.in file on a big-endian computer was the hexadecimal number 0x12345678, the resulting output on that computer would be as follows.

```
% ./test
First Integer in file.in = 12345678
%
```

If the file.in file were read by the same program running on a little-endian computer, the resulting output would be as follows.

```
% ./test
First Integer in file.in = 78563412
%
```

Because of the difference in output, metafile record processing SHOULD be implemented so that it can read integers from a file based on the endian method that the output computer uses.

Because metafiles were developed and written with little-endian computers, computers that are big-endian based will have to perform this necessary compensation.

### 3.1.3 Mapping Modes

When an application pastes a WMF metafile from the clipboard, it can determine the size of metafile output. For this to work cleanly between applications, be aware of the following:

- The metafile is responsible for specifying the window part of the mapping mode.
- The player of the metafile is responsible for the viewport part of the mapping mode.

To perform a simple playback of the metafile, an application SHOULD perform the following initialization before processing records.

1. Set the mapping mode to the mode specified in the METAFILEPICT structure (for more information, see [\[MSDN-CLIPFORM\]](#)).
2. Convert the horizontal and vertical extents of the viewport to logical units, if necessary (see the following).
3. Perform scaling computations, if required (see below).
4. Set the viewport origin according to the desired placement of the metafile.

If the mapping mode in a metafile is MM\_ANISOTROPIC or MM\_ISOTROPIC, coordinate conversion MAY be required, as mentioned earlier. If the horizontal and vertical extents of the image are given in MM\_HIMETRIC coordinates, they MUST be converted to pixel values. Before playback, the application needs to set the viewport origin to the desired location, set the mapping mode to the specified mode, and compute the viewport extents. If no extents are specified in the METAFILEPICT structure, the application performing the playback MAY arbitrarily choose a size.

Thus, scaling a metafile that uses the MM\_ANISOTROPIC or MM\_ISOTROPIC mapping modes MAY be performed by changing the viewport extents to the appropriate dimensions before playback. The viewport defines the size of the metafile image.

To scale metafiles that use any other mapping mode, first convert the metafile to use MM\_ANISOTROPIC mapping mode. The metafile itself does not need to change, but the mapping mode setup does need to be correct before beginning the playback.

### 3.1.4 Managing Objects

#### 3.1.4.1 WMF Object Table

The WMF Object Table is a conceptual element of WMF graphics objects management. [Graphics Objects \(section 2.2.1\)](#) include [Brushes](#), [Fonts](#), [Palettes](#), [Pens](#), and [Regions](#); they can be defined, used, reused, and deleted by records in a WMF metafile. This section describes a hypothetical WMF Object Table to keep track of graphics objects during the processing of a WMF metafile.

The WMF Object Table is simply an array of indexes assigned to graphics object structures defined during the processing of a WMF metafile. The maximum number of indexes needed in a WMF Object Table for a given metafile can be computed from the total number of objects defined in the metafile, which is specified by the **NumberOfObjects** field in the WMF [META\\_HEADER](#) record (section [2.3.2.2](#)). An implementation of the WMF Object Table will store and manage that number of objects.

Whenever a graphics object is created by one of the [Object Record Types](#) listed in section [2.3.4](#), the following actions are implied:

- Every object is assigned the lowest available index—that is, the smallest numerical value—in the WMF Object Table. This binding happens at object creation, not when the object is used. Moreover, each object table index uniquely refers to an object. Indexes in the WMF Object Table always start at 0.
- Subsequent WMF records refer to an object by its assigned WMF Object Table index. However, there is no requirement that every object defined in the metafile will be used.
- An object is not used in drawing operations until a [META\\_SELECTOBJECT](#) record (section [2.3.4.10](#)) is received that specifies its WMF Object Table index. This record activates the object and makes it current in the [Playback Device Context \(section 3.1.5\)](#).
- Later in the processing of the metafile, another META\_SELECTOBJECT record might be encountered that selects a different object of the same object type into the playback device context. When that happens, the previously defined object is not deleted, and its index is not returned to the pool of available indexes.
- When a [META\\_DELETEOBJECT](#) record (section [2.3.4.7](#)) is received that specifies this object's particular index, the object's resources are released, the binding to its WMF Object Table index is ended, and the index value is returned to the pool of available indexes. The index will be reused, if needed, by a subsequent object created by another Object Record Type record.

Thus, graphics object creation, use, and deletion depend on the correct order of records during playback to achieve the expected results.

**Note** This specification does not mandate that implementations adhere to the implementation of the WMF Object Table presented in this section, as long as the implementation of external behavior is compatible with the behavior described in this specification.

#### 3.1.4.2 Object Scaling

A metafile that is created by an application and then passed to another application is likely to be scaled. Scaling may alter the desired image in a way that was not anticipated by the originating

application, which does not scale the image. Every logical measure defined in a **logical object** is scaled before the object is realized into physical form.

For a logical object such as pens, the width is transformed from logical to physical as an x-scalar value. If the metafile is scaled in y but not in x, the pen width is unchanged. If the metafile is scaled in x but not in y, the pen width does scale. Thus, using a pen of width 1 in a metafile results in a pen that is wider (thick and slow) when the metafile is scaled. If a nominal width pen (width of 1 at all times) is wanted, use 0 as the width because it is not affected by mapping modes. A 0-width pen is drawn as having a width of 1.

Font sizing is more complicated. The two values that scale in a logical font are the height and the width. Most applications use a width of 0 to define a font, which results in a physical font with a width that was designed for the given height. As the metafile is stretched in x, the font remains the same size. As the metafile is stretched in y, however, the physical font grows bigger and probably wider. In and of itself, this is not bad, but problems arise when the metafile makes assumptions about the width of the font by placing the characters of a text string individually, using [META\\_EXTTEXTOUT](#) with a width array, or using a [META\\_TEXTOUT](#) for each character. In either case, the x-placement of each character scales with the metafile, but the font's width does not necessarily scale accordingly, which causes characters to overlap or be widely spaced.

The simplest way to overcome this problem is not to place the characters individually but to use [META\\_TEXTOUT](#) (or [META\\_EXTTEXTOUT](#) with no width array) to output the whole string. The text string remains intact, but its size may change in relation to the rest of the image when x and y are not scaled identically. Another possibility is to define the font with a nonzero width so that it scales in x as well as in y. However, doing so is problematic, because its bitmapped fonts may not scale independently in x and y. Scaling a font's width is also possible; unfortunately, any time a font's width is scaled, the look of the typeface changes in ways not necessarily intended by the designers, and a typographically "incorrect" typeface results.

### 3.1.5 Playback Device Context

The playback device context is an abstract data structure that defines the state of graphics at any point in time during playback of a WMF metafile. The graphics state includes:

- A complete set of [Graphics Objects \(section 2.2.1\)](#), including a brush, font, palette, pen, and region, which are created and managed by WMF [Object Record Types \(section 2.3.4\)](#).
- A set of selected [Structure Objects \(section 2.2.2\)](#), which define parameters of the output surface. These elements of the playback device context are not explicitly created by any record, but they can be modified.
- A vector of graphics properties, which are numerical values that specify modes and parameters for graphics operations.

Although the state defined by the playback device context can be modified by WMF records, there is no guarantee that every graphics object and property will be explicitly initialized by records in a given metafile before any output takes place. Thus, whenever a metafile is played back, it is necessary to define initial conditions consisting of a set of default values for the playback device context. These initial conditions are dependent on multiple factors, including the operating system and the device that is the destination for output. [<69>](#)

The following table lists the graphics objects that are defined in the playback device context.



| Graphic<br>s object  | Created by record(s)  | Used by record(s)  | Notes   |
|--|---|--|---|
| <a href="#">Brush</a><br>graphics<br>object<br>(section<br><a href="#">2.2.1.1</a> )   | <a href="#">META_CREATEBRUSHINDIRECT</a> record<br>(section <a href="#">2.3.4.1</a> )<br><a href="#">META_CREATEPATTERNBRUSH</a> record<br>(section <a href="#">2.3.4.4</a> )<br><a href="#">META_DIBCREATEPATTERNBRUSH</a> record<br>(section <a href="#">2.3.4.8</a> )  | <a href="#">Bitmap Record Types</a><br>(section <a href="#">2.3.1</a> ), when<br>the raster operation<br>involves a brush.<br><a href="#">Drawing Record Types</a><br>(section <a href="#">2.3.3</a> ) that<br>perform area filling. | This object is not used<br>until it is specified in a<br><a href="#">META_SELECTOBJECT</a><br>record section <a href="#">2.3.4.10</a> ).<br>The default is a solid color<br>brush <b>stock object</b> . |
| <a href="#">Font</a><br>graphics<br>object<br>(section<br><a href="#">2.2.1.2</a> )    | <a href="#">META_CREATEFONTINDIRECT</a> record<br>(section <a href="#">2.3.4.2</a> )  | <a href="#">META_EXTTEXTOUT</a><br>record (section <a href="#">2.3.3.5</a> )<br><a href="#">META_TEXTOUT</a> record<br>(section <a href="#">2.3.3.20</a> )   | This object is not used<br>until it is specified in a<br><a href="#">META_SELECTOBJECT</a><br>record (section <a href="#">2.3.4.10</a> ).<br>The default is a stock<br>object.                          |
| <a href="#">Palette</a><br>graphics<br>object<br>(section<br><a href="#">2.2.1.3</a> ) | <a href="#">META_ANIMATEPALETTE</a> record (section<br><a href="#">2.3.5.1</a> )<br><a href="#">META_CREATEPALETTE</a> record (section<br><a href="#">2.3.4.3</a> )<br><a href="#">META_RESIZEPALETTE</a> record (section<br><a href="#">2.3.5.9</a> )<br><a href="#">META_SETPALENTRIES</a> record (section<br><a href="#">2.3.5.19</a> )    | <a href="#">META_REALIZEPALETTE</a><br>record (section<br><a href="#">2.3.5.8</a> )  | This object is not used<br>until it is specified in a<br><a href="#">META_SELECTPALETTE</a><br>record (section <a href="#">2.3.4.11</a> ).<br>The default is a stock<br>object.                         |
| <a href="#">Pen</a><br>graphics<br>object<br>(section<br><a href="#">2.2.1.4</a> )     | <a href="#">META_CREATEPENINDIRECT</a> record<br>(section <a href="#">2.3.4.5</a> )   | Drawing Record Types<br>(section 2.3.3) that<br>perform line drawing.  | This object is not used<br>until it is specified in a<br><a href="#">META_SELECTOBJECT</a><br>record (section <a href="#">2.3.4.10</a> ).<br>The default is a stock<br>object.                          |
| <a href="#">Region</a><br>graphics<br>object<br>(section<br><a href="#">2.2.1.5</a> )  | <a href="#">META_CREATEREGION</a> record (section<br><a href="#">2.3.4.6</a> )<br><a href="#">META_EXCLUDECLIPRECT</a> record<br>(section <a href="#">2.3.5.2</a> )<br><a href="#">META_INTERSECTCLIPRECT</a> record<br>(section <a href="#">2.3.5.3</a> )<br><a href="#">META_OFFSETCLIPRGN</a> record (section<br><a href="#">2.3.5.5</a> ) | Bitmap Record Types<br>(section 2.3.1)<br>Drawing Record Types<br>(section 2.3.3) that<br>allow clipping.  | This object is not used<br>until it is specified in a<br><a href="#">META_SELECTCLIPREGION</a><br>record (section <a href="#">2.3.4.9</a> ).<br>The default is the entire<br>drawing surface.           |

The following table lists the structure objects that are defined in the playback device context.

| Structure<br>object      | Description   | Data type   | Modified by record(s)   |
|--------------------------|---|---|---|
| Background<br>text color | The color used as<br>background for text.   | <a href="#">ColorRef</a> object (section<br><a href="#">2.2.2.8</a> ) | <a href="#">META_SETBKCOLOR</a> record<br>(section <a href="#">2.3.5.14</a> ) |
| Drawing<br>position      | The (x,y) coordinates<br>of the current drawing<br>position in the output<br>window | <a href="#">PointS</a> object (section<br><a href="#">2.2.2.16</a> )  | <a href="#">META_MOVETO</a> record (section<br><a href="#">2.3.5.4</a> )      |

| Structure object      | Description   | Data type   | Modified by record(s)  |
|-----------------------|---|---|--|
| Foreground text color | The color used for text.  | ColorRef object (section <a href="#">2.2.2.8</a> )                                | <a href="#">META_SETTEXTCOLOR</a> record (section <a href="#">2.3.5.26</a> )   |
| Output surface        | An array of pixels in a device-independent format that correspond to the logical units of the output surface. | <a href="#">DeviceIndependentBitmap</a> object (section <a href="#">2.2.2.9</a> ) | Bitmap Record Types (section 2.3.1)  |
| Viewport extent       | The horizontal and vertical dimensions of the visible part of the output window                               | PointS object (section <a href="#">2.2.2.16</a> )                                 | <a href="#">META_SCALEVIEWPORTEXT</a> record (section <a href="#">2.3.5.12</a> )<br><a href="#">META_SETVIEWPORTEXT</a> record (section <a href="#">2.3.5.28</a> ) |
| Viewport origin       | The (x,y) coordinates of the left, top corner of the visible part of the output window.                       | PointS object (section <a href="#">2.2.2.16</a> )                                 | <a href="#">META_OFFSETVIEWPORTORG</a> record (section <a href="#">2.3.5.6</a> )<br><a href="#">META_SETVIEWPORTORG</a> record (section <a href="#">2.3.5.29</a> ) |
| Window extent         | The horizontal and vertical dimensions of the output window on the output surface.                            | PointS object (section <a href="#">2.2.2.16</a> )                                 | <a href="#">META_SCALEWINDOWEXT</a> record (section <a href="#">2.3.5.13</a> )<br><a href="#">META_SETWINDOWEXT</a> record (section <a href="#">2.3.5.30</a> )     |
| Window origin         | The (x,y) coordinates of the left, top corner of the output window on the output surface.                     | PointS object (section <a href="#">2.2.2.16</a> )                                 | <a href="#">META_OFFSETWINDOWORG</a> (section <a href="#">2.3.5.7</a> )<br><a href="#">META_SETWINDOWORG</a> record (section <a href="#">2.3.5.31</a> )            |

The following table lists the graphics properties that are defined in the playback device context.

| Property            | Description  | Modified by record(s)   |
|---------------------|--|---|
| Background mix mode | The mode for combining pens, text, hatched brushes, and interiors of filled objects with background colors on the output surface.          | <a href="#">META_SETBKMODE</a> record (section <a href="#">2.3.5.15</a> )             |
| Break extra space   | The total extra space to be added to a line of text for justification.   | <a href="#">META_SETTEXTJUSTIFICATION</a> record (section <a href="#">2.3.5.27</a> )  |
| Font matching mode  | A Boolean value that specifies whether the font mapper should attempt to match a font's aspect ratio to the current device's aspect ratio. | <a href="#">META_SETMAPPERFLAGS</a> Record record (section <a href="#">2.3.5.18</a> ) |
| Foreground mix mode | The mode for combining pens and interiors of filled objects with foreground colors on the output surface.                                  | <a href="#">META_SETROP2</a> record (section <a href="#">2.3.5.22</a> )               |
| Layout mode         | The direction in which text and graphics are drawn.  | <a href="#">META_SETLAYOUT</a> record (section <a href="#">2.3.5.16</a> )             |
| Mapping mode        | How logical units are mapped to physical units.  | <a href="#">META_SETMAPMODE</a> record (section                                       |

| Property            | Description  | Modified by record(s)   |
|---------------------|--|---|
|                     |  | <a href="#">2.3.5.17</a> )  |
| Polygon fill mode   | The method used for filling a polygon.   | <a href="#">META_SETPOLYFILLMODE</a> record (section <a href="#">2.3.5.20</a> )   |
| Stretchblt mode     | How the system combines rows or columns of pixels when shrinking a bitmap.               | <a href="#">META_SETSTRETCHBLTMODE</a> record (section <a href="#">2.3.5.23</a> ) |
| Text alignment mode | The relationship between a reference point and a bounding rectangle, for text alignment. | <a href="#">META_SETTEXTALIGN</a> record (section <a href="#">2.3.5.24</a> )      |
| Text extra space    | The amount of extra space to add to each character when writing a line of text.          | <a href="#">META_SETTEXTCHAREXTRA</a> record (section <a href="#">2.3.5.25</a> )  |

**Note** This specification does not mandate that implementations adhere to the implementation of the playback device context presented in this section, as long as the implementation of external behavior is compatible with the behavior described in this specification.

### 3.1.6 Run-Length Encoding (RLE) Compression

In general, run-length encoding (RLE) compression makes it possible to specify an arbitrary number of identical values without a proportional increase in storage requirements. The compressed format usually defines a run count and a value, and expansion amounts to replicating that value a number of times equal to the run count.

Metafile records can contain bitmaps that are compressed with an enhanced RLE compression algorithm. Compression of bitmaps that are defined with 4 and 8 bits per pixel are described in the sections which follow.

#### 3.1.6.1 Bitmaps with 4 Bits per Pixel

When the **Compression** field of a [BitmapInfoHeader Object \(section 2.2.2.3\)](#) is **BI\_RLE4**, an RLE compression algorithm is used to compress a 4-bit bitmap. This format specifies encoded and absolute modes, and either mode can occur anywhere in a given bitmap.

Encoded mode involves two bytes. If the first byte of a pair is greater than zero, it specifies the number of consecutive pixels to be drawn using the two color indexes that are contained in the high-order and low-order bits of the second byte.

The first pixel is drawn using the color specified by the high-order 4 bits, the second is drawn using the color in the low-order 4 bits, the third is drawn using the color in the high-order 4 bits, and so on, until all the pixels specified by the first byte have been drawn.

If the first byte of a pair is zero and the second byte is 0x02 or less, the second byte is an escape value that can denote the end of a line, the end of the bitmap, or a relative pixel position, as follows.

| Second byte value | Meaning       |
|-------------------|---------------|
| 0x00              | End of line   |
| 0x01              | End of bitmap |

| Second byte value | Meaning |
|-------------------|---------|
| 0x02              | Delta   |

When a delta is specified, the 2 bytes following the escape value contain unsigned values indicating the horizontal and vertical offsets of the next pixel relative to the current position.

In absolute mode, the first byte is zero, and the second byte is a value in the range 0x03 through 0xFF. The second byte contains the number of 4-bit color indexes that follow. Subsequent bytes contain color indexes in their high and low-order 4 bits, one color index for each pixel. In absolute mode, each run must be aligned on a word boundary.

The following example shows the hexadecimal contents of a 4-bit compressed bitmap:

```
03 04 05 06 00 06 45 56 67 00 04 78 00 02 05 01
04 78 00 00 09 1E 00 01
```

This bitmap is interpreted as follows:

- 03 04: Encoded mode, specifying 3 pixels with the values 0x0, 0x4, and 0x0.
- 05 06: Encoded mode, specifying 5 pixels with the values 0x0, 0x6, 0x0, 0x6, and 0x0.
- 00 06 45 56 67 00: Absolute mode, specifying 6 pixels with the values 0x4, 0x5, 0x5, 0x6, 0x6, and 0x7, padded to a word boundary.
- 04 78: Encoded mode, specifying 4 pixels with the values 0x7, 0x8, 0x7, and 0x8.
- 00 02 05 01: Encoded mode, specifying a new relative position 5 pixels to the right and one line down.
- 04 78: Encoded mode, specifying 4 pixels with the values 0x7, 0x8, 0x7, and 0x8.
- 00 00: Encoded mode, specifying the end of a line.
- 09 1E: Encoded mode, specifying 9 pixels with the values 0x1, 0xE, 0x1, 0xE, 0x1, 0xE, 0x1, 0xE, and 0x1.
- 00 01: Encoded mode, specifying the end of the bitmap.

Now, suppose the bitmap has a width of 32 pixels and a height of 4 lines, and pixel values that are not specified are 0x00 by default. The resulting expended bitmap would be as follows.

```
04 00 60 60 45 56 67 78 78 00 00 00 00 00 00 00
00 00 00 00 00 00 00 00 00 00 00 00 07 87 80 00 00
1E 1E 1E 1E 10 00 00 00 00 00 00 00 00 00 00 00 00
00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00
```

### 3.1.6.2 Bitmaps with 8 Bits per Pixel

When the **Compression** field of a [BitmapInfoHeader Object \(section 2.2.2.3\)](#) is **BI\_RLE8**, an RLE compression algorithm is used to compress an 8-bit bitmap. This format specifies encoded and absolute modes, and either mode can occur anywhere in a given bitmap.

Encoded mode involves two bytes. If the first byte of a pair is greater than zero, it specifies the number of consecutive pixels to be drawn using the color index that is contained in the second byte.

If the first byte of a pair is zero and the second byte is 0x02 or less, the second byte is an escape value that can denote the end of a line, the end of the bitmap, or a relative pixel position, as follows.

| Second byte value | Meaning       |
|-------------------|---------------|
| 0x00              | End of line   |
| 0x01              | End of bitmap |
| 0x02              | Delta         |

When a delta is specified, the 2 bytes following the escape value contain unsigned values indicating the horizontal and vertical offsets of the next pixel relative to the current position.

In absolute mode, the first byte is zero, and the second byte is a value in the range 0x03 through 0xFF. The second byte represents the number of bytes that follow, each of which contains the color index of a single pixel. In absolute mode, each run must be aligned on a word boundary.

The following example shows the hexadecimal contents of an 8-bit compressed bitmap.

```
03 04 05 06 00 03 45 56 67 00 02 78 00 02 05 01
02 78 00 00 09 1E 00 01
```

This bitmap is interpreted as follows:

- 03 04: Encoded mode, specifying 3 pixels with the value 0x04.
- 05 06: Encoded mode, specifying 5 pixels with the value 0x06.
- 00 03 45 56 67 00: Absolute mode, specifying 3 pixels with the values 0x45, 0x56, and 0x67, padded to a word boundary.
- 02 78: Encoded mode, specifying 2 pixels with the value 0x78.
- 00 02 05 01: Encoded mode, specifying a new relative position 5 pixels to the right and 1 line down.
- 02 78: Encoded mode, specifying 2 pixels with the value 0x78.
- 00 00: Encoded mode, specifying the end of a line.
- 09 1E: Encoded mode, specifying 9 pixels with the value 1E.
- 00 01: Encoded mode, specifying the end of the bitmap.

Now, suppose the bitmap has a width of 32 pixels and a height of 4 lines, and pixel values that are not specified are 0x00 by default. The resulting expended bitmap would be as follows.

```
04 04 04 06 06 06 06 06 45 56 67 78 78 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00
00
00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 78 78 00 00 00 00 00 00 00 00 00 00 00
00
```


```

1E 1E 1E 1E 1E 1E 1E 1E 1E 1E 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00
00
00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00
00

```

## 3.2 WMF Metafile Example

This section provides an example of a metafile which, when processed, renders the following image.



**Figure 2: WMF metafile example**

The contents of this metafile example are shown in the following in hexadecimal bytes. The far-left column is the byte count; the far-right characters are the interpretation of the bytes in the Latin-1 **ANSI Character Set**, as specified in [\[ISO/IEC-8859-1\]](#). The sections that follow describe the packets that convey this series of bytes.

```

00000000: 01 00 09 00 00 03 36 00 00 00 02 00 0C 00 00 00 .....6.....
00000010: 00 00 08 00 00 00 FA 02 04 00 00 00 00 00 00 .....ú.....
00000020: FF 00 04 00 00 00 2D 01 00 00 07 00 00 00 FC 02 ý.....-.....ü.
00000030: 02 00 00 FF 00 FF 04 00 04 00 00 00 2C 01 01 00 ...ÿ.ÿ.....,.
00000040: 07 00 00 00 1B 04 46 00 96 00 00 00 00 00 0C 00 .....F.-.....
00000050: 00 00 21 05 0C 00 48 65 6C 6C 6F 20 50 65 6F 70 ...!...Hello Peop
00000060: 6C 65 0A 00 0A 00 03 00 00 00 00 00 00 00 00 00 le.....

```

**Note** When a WMF metafile is processed, the order in which graphics are rendered corresponds to the order of records in the metafile. This may create challenges for devices that have layers. For example, **Printer Command Language (PCL)** defines a graphics layer and a text layer. The text layer in PCL is always drawn on top of the graphics layer. Thus, when converting from metafile format to PCL, the converter, to generate the correct output, either detects text/graphic overlaps and sends the text down as graphics, or always sends the text as graphics.

The sections that follow provide definitions of the WMF header and records that correspond to this metafile. The [WMF Object Table \(section 3.1.4.1\)](#) refers to an indexed table of [WMF Object](#) that are defined in the metafile.

### 3.2.1 META\_HEADER Example

This section provides an example of a [META\\_HEADER \(section 2.3.2.2\)](#) record, which is always the first record in the metafile.

```

00000000: 01 00 09 00 00 03 36 00 00 00 02 00 0C 00 00 00
00000010: 00 00

```

|                          |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|--------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|--------------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                        | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                       | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| Type (0x0001)            |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | HeaderSize (0x0009)      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| Version (0x0300)         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | Size (0x00000036)        |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                      |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | NumberOfObjects (0x0002) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| MaxRecord (0x0000000C)   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| NumberOfMembers (0x0000) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                          |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Figure 3: META\_HEADER record example**

**Type:** 0x0001 specifies the type of metafile from the [MetafileType Enumeration \(section 2.1.1.18\)](#) to be a metafile stored in memory.

**HeaderSize:** 0x0009 specifies the number of [WORDS](#) in this record, which is equivalent to 18 (0x0012) bytes.

**Version:** 0x0300 specifies the metafile version from the [MetafileVersion Enumeration \(section 2.1.1.19\)](#) to be a WMF metafile that supports DIBs.

**Size:** 0x00000036 specifies the number of **WORDS** in the entire metafile, which is equivalent to 108 (0x0000006C) bytes.

**NumberOfObjects:** 0x0002 specifies the number of graphics objects that are defined in the metafile.

**MaxRecord:** 0x0000000C specifies the size in **WORDS** of the largest record in the metafile, which is equivalent to 24 (0x00000018) bytes.

**NumberOfMembers:** 0x0000 is not used.

**Note** Based on the value of the **NumberOfObjects** field, a [WMF Object Table \(section 3.1.4.1\)](#) can be created that is large enough for 2 objects.

### 3.2.2 META\_CREATEPENINDIRECT Example

This section provides an example of a [META\\_CREATEPENDIRECT](#) record.

```
00000010:      08 00 00 00 FA 02 04 00 00 00 00 00 00 00
00000020: FF 00
```

|                         |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |            |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
|-------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6          | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 |
| RecordSize (0x00000008) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |            |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| RecordFunction (0x02FA) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | Pen Object |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |            |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |            |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |

**Figure 4: META\_CREATEPENINDIRECT record example**

**RecordSize:** 0x00000008 specifies the number of [WORDS](#) in this record, which is equivalent to 16 (0x00000010) bytes.

**RecordFunction:** 0x02FA specifies a META\_CREATEPENINDIRECT record from the [RecordType Enumeration \(section 2.1.1.1\)](#).

**Pen Object:** A [Pen Object](#) that defines the pen to create.

|                   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                 |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
|-------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|-----------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0                 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6               | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 |
| PenStyle (0x0004) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | PointS Object   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...               |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | ColorRef Object |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...               |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | ...             |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |

**Figure 5: Pen Object example**

**PenStyle:** 0x0004 specifies the PS\_DASHDOTDOT style from the [PenStyle Enumeration \(section 2.1.1.23\)](#).

**PointS Object:** A [PointS Object](#) that specifies the width of the pen.

|            |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |            |   |   |   |                |   |   |   |   |   |   |   |   |   |                |   |
|------------|---|---|---|---|---|---|---|---|---|----------------|---|---|---|---|---|------------|---|---|---|----------------|---|---|---|---|---|---|---|---|---|----------------|---|
| 0          | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 <sup>1</sup> | 1 | 2 | 3 | 4 | 5 | 6          | 7 | 8 | 9 | 0 <sup>2</sup> | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 <sup>3</sup> | 1 |
| x (0x0000) |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   | y (0x0000) |   |   |   |                |   |   |   |   |   |   |   |   |   |                |   |

**Figure 6: PointS Object example**

**x:** 0x0000 specifies the width of the pen to be the default, which is 1 pixel.

**y:** 0x0000 is not used.

**ColorRef Object:** A [ColorRef Object](#) that specifies a green pen color.

|                 |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |                |   |   |   |   |   |   |   |   |   |                |   |  |  |  |  |  |  |  |  |
|-----------------|---|---|---|---|---|---|---|---|---|----------------|---|---|---|---|---|---|---|---|---|----------------|---|---|---|---|---|---|---|---|---|----------------|---|--|--|--|--|--|--|--|--|
| 0               | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 <sup>1</sup> | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 <sup>2</sup> | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 <sup>3</sup> | 1 |  |  |  |  |  |  |  |  |
| Reserved (0x00) |   |   |   |   |   |   |   |   |   | Blue (0x00)    |   |   |   |   |   |   |   |   |   | Green (0xFF)   |   |   |   |   |   |   |   |   |   | Red (0x00)     |   |  |  |  |  |  |  |  |  |

**Figure 7: ColorRef Object example**

**Reserved:** 0x00 is not used.

**Blue:** 0x00 specifies no blue.

**Green:** 0xFF specifies full intensity of green.

**Red:** 0x00 specifies no red.

**Note** The Pen Object created by processing this record is assigned index 0 in the [WMF Object Table \(section 3.1.4.1\)](#).

### 3.2.3 META\_SELECTOBJECT Example

This section provides an example of a [META\\_SELECTOBJECT](#) record.



```
00000020:      04 00 00 00 2D 01 00 00
```

|                         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                   | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize (0x00000004) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction (0x012D) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ObjectIndex (0x0000) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Figure 8: META\_SELECTOBJECT record example**

**RecordSize:** 0x00000004 specifies the number of [WORDS](#) in this record, which is equivalent to 8 (0x00000008) bytes.

**RecordFunction:** 0x012D specifies the type of this record from the [RecordType Enumeration \(section 2.1.1.1\)](#) to be META\_SELECTOBJECT.

**ObjectIndex:** 0x0000 specifies the index in the [WMF Object Table \(section 3.1.4.1\)](#) of the object being selected, which is the [Pen Object](#) created in the previous record.

### 3.2.4 META\_CREATEBRUSHINDIRECT Example

This section provides an example of a [META\\_CREATEBRUSHINDIRECT](#) record.

```
00000020:      07 00 00 00 FC 02
00000030: 02 00 00 FF 00 FF 04 00
```

|                         |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                          |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
|-------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|--------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6                        | 7 | 8 | 9 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 0 | 1 |
| RecordSize (0x00000007) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                          |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| RecordFunction (0x02FC) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | LogBrush Object (0x0000) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                          |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| ...                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | ...                      |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |

**Figure 9: META\_CREATEBRUSHINDIRECT record example**

**RecordSize:** 0x00000007 specifies the number of [WORDS](#) in this record, which is equivalent to 14 (0x0000000E) bytes.

**RecordFunction:** 0x02FC specifies a META\_CREATEBRUSHINDIRECT record from the [RecordType Enumeration \(section 2.1.1.1\)](#).

**LogBrush Object:** A [LogBrush Object](#) that defines the brush to create.

|                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                     |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|---------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|---------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                   | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                  | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| BrushStyle (0x0002) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ColorRef Object     |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                 |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | BrushHatch (0x0004) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Figure 10: LogBrush Object example**

**BrushStyle:** 0x0002 specifies the BS\_HATCHED style from the [BrushStyle Enumeration \(section 2.1.1.4\)](#).

**ColorRef Object:** A [ColorRef Object](#) that specifies a magenta brush color.

|                 |   |   |   |   |   |   |   |   |   |             |    |    |    |    |    |    |    |    |    |              |    |    |    |    |    |    |    |    |    |            |    |  |  |  |  |
|-----------------|---|---|---|---|---|---|---|---|---|-------------|----|----|----|----|----|----|----|----|----|--------------|----|----|----|----|----|----|----|----|----|------------|----|--|--|--|--|
| 0               | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10          | 11 | 12 | 13 | 14 | 15 | 16 | 17 | 18 | 19 | 20           | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30         | 31 |  |  |  |  |
| Reserved (0x00) |   |   |   |   |   |   |   |   |   | Blue (0xFF) |    |    |    |    |    |    |    |    |    | Green (0x00) |    |    |    |    |    |    |    |    |    | Red (0xFF) |    |  |  |  |  |

**Figure 11: ColorRef Object example**

**Reserved:** 0x00 is not used.

**Blue:** 0xFF specifies full intensity blue.

**Green:** 0x00 specifies no green.

**Red:** 0xFF specifies full intensity red.

**BrushHatch:** 0x0004 specifies the hatch style from the [HatchStyle Enumeration \(section 2.1.1.12\)](#), a horizontal and vertical cross-hatch.

**Note** The [Brush Object](#) created by processing this record is assigned index 1 in the [WMF Object Table \(section 3.1.4.1\)](#).

### 3.2.5 META\_SELECTOBJECT Example

This section provides an example of a [META\\_SELECTOBJECT](#) record.

00000030: 04 00 00 00 2D 01 01 00

|                         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                   | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize (0x00000004) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                      |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction (0x012D) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | ObjectIndex (0x0001) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Figure 12: META\_SELECTOBJECT record example**

**RecordSize:** 0x00000004 specifies the number of [WORDS](#) in this record, which is equivalent to 8 (0x00000008) bytes.

**RecordFunction:** 0x012D specifies the type of this record from the [RecordType Enumeration \(section 2.1.1.1\)](#) to be META\_SELECTOBJECT.

**ObjectIndex:** 0x0001 specifies the index in the [WMF Object Table \(section 3.1.4.1\)](#) of the object being selected, which is the [Brush Object](#) created in the previous record.

### 3.2.6 META\_RECTANGLE Example

This section provides an example of a [META\\_RECTANGLE](#) record.

00000040: 07 00 00 00 1B 04 46 00 96 00 00 00 00 00

|                         |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
|-------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 1 | 0 | 1 | 2 | 3 | 4 | 5 | 6                   | 7 | 8 | 9 | 2 | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 3 | 0 | 1 |
| RecordSize (0x00000007) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| RecordFunction (0x041B) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | BottomRect (0x0046) |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| RightRect (0x0096)      |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   | TopRect (0x0000)    |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |
| LeftRect (0x0000)       |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |                     |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |   |

**Figure 13: META\_RECTANGLE Record Example**

**RecordSize:** 0x00000007 specifies the number of **WORDS** in this record, which is equivalent to 14 (0x0000000E) bytes.

**RecordFunction:** 0x041B defines the type of this record from the [RecordType Enumeration \(section 2.1.1.1\)](#) to be META\_RECTANGLE.

**BottomRect:** 0x0046 defines the y-coordinate, in logical units, of the lower-right corner of the rectangle.

**RightRect:** 0x0096 defines the x-coordinate, in logical units, of the lower-right corner of the rectangle.

**TopRect:** 0x0000 defines the y-coordinate, in logical units, of the upper-left corner of the rectangle.

**LeftRect:** 0x0000 defines the x-coordinate, in logical units, of the upper-left corner of the rectangle.

### 3.2.7 META\_TEXTOUT Example

This section provides an example of a [META\\_TEXTOUT](#) record.

```
0000004E:                                0C 00
00000050: 00 00 21 05 0C 00 48 65 6C 6C 6F 20 50 65 6F 70
00000060: 6C 65 0A 00 0A 00
```

|                         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
|-------------------------|---|---|---|---|---|---|---|---|---|----|----|----|----|----|----|-----------------------|----|----|----|----|----|----|----|----|----|----|----|----|----|----|----|
| 0                       | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 | 15 | 16                    | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 | 27 | 28 | 29 | 30 | 31 |
| RecordSize (0x0000000C) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| RecordFunction (0x0521) |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | StringLength (0x000C) |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| String "Hello People"   |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| ...                     |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    |                       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |
| YStart (0x000A)         |   |   |   |   |   |   |   |   |   |    |    |    |    |    |    | XStart (0x000A)       |    |    |    |    |    |    |    |    |    |    |    |    |    |    |    |

**Figure 14: META\_TEXTOUT record example**

**RecordSize:** 0x0000000C specifies the number of **WORDS** in this record, which is equivalent to 24 (0x00000018) bytes.



## 4 Security Considerations

This file format enables third parties to send payloads (such as PostScript) to pass through as executable code.

## 5 Appendix A: Product Behavior

The information in this specification is applicable to the following Microsoft products or supplemental software. References to product versions include released service packs:

- Microsoft Windows NT® 3.1 operating system
- Microsoft Windows NT® 3.5 operating system
- Microsoft Windows NT® 3.51 operating system
- Microsoft Windows® 95 operating system
- Microsoft Windows NT® 4.0 operating system
- Microsoft Windows® 98 operating system
- Microsoft Windows® Millennium Edition operating system
- Microsoft Windows® 2000 operating system
- Windows® XP operating system
- Windows Server® 2003 operating system
- Windows Vista® operating system
- Windows Server® 2008 operating system
- Windows® 7 operating system
- Windows Server® 2008 R2 operating system

Exceptions, if any, are noted below. If a service pack or Quick Fix Engineering (QFE) number appears with the product version, behavior changed in that service pack or QFE. The new behavior also applies to subsequent service packs of the product unless otherwise specified. If a product edition appears with the product version, behavior is different in that product edition.

Unless otherwise specified, any statement of optional behavior in this specification that is prescribed using the terms SHOULD or SHOULD NOT implies product behavior in accordance with the SHOULD or SHOULD NOT prescription. Unless otherwise specified, the term MAY implies that the product does not follow the prescription.

[<1> Section 1.1:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: sRGB color management technology is not available.

[<2> Section 1.1:](#) In the following Windows versions, the technology used for color management is **Windows Color System (WCS)**:

- Windows Vista
- Windows Server 2008
- Windows 7
- Windows Server 2008 R2

[<3> Section 1.4:](#) Windows NT 3.1, Windows NT 3.51, Windows NT Server 4.0, and Windows 95: The WMF is used primarily with the **Win16** and **Win32s** APIs.

[<4> Section 2.1.1.1:](#) Windows NT 3.1, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This record type is not supported.

[<5> Section 2.1.1.1:](#) For most WMF record types, the high-order byte of the **RecordFunction** field signifies the minimum number of 16-bit parameters, ideally specified in the WMF record; however, the value is not reliable for that purpose.

Windows does not require that this value is correct and does not use it, with the following exceptions:

- **META\_BITBLT**
- **META\_DIBBITBLT**
- **META\_DIBSTRETCHBLT**
- **META\_POLYGON**
- **META\_POLYLINE**
- **META\_SETPALENTRIES**
- **META\_STRETCHBLT**

[<6> Section 2.1.1.3:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: Neither JPEG nor PNG format is supported.

[<7> Section 2.1.1.4:](#) In Windows implementations, **BS\_HOLLOW** was added as a duplicate symbolic name for **BS\_NULL**, because **BS\_NULL** was too easily mistaken for a NULL pointer.

**BS\_HOLLOW** is used by an application when GDI requires a non-NULL brush parameter but the application requires that no brush be used.

[<8> Section 2.1.1.5:](#) Windows NT 3.1 and Windows NT 3.51: This value is not supported.

[<9> Section 2.1.1.10:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: Anti-aliasing is not supported.

[<10> Section 2.1.1.10:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: Anti-aliasing is not supported.

[<11> Section 2.1.1.10:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, Windows Millennium Edition, and Windows 2000: ClearType is not supported.

[<12> Section 2.1.1.11:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This functionality is not supported.

[<13> Section 2.1.1.13:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<14> Section 2.1.1.14:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This functionality is not supported.

[<15> Section 2.1.1.15:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This functionality is not supported.

[<16> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<17> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<18> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<19> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<20> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<21> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<22> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, Windows Millennium Edition, Windows 2000, Windows XP, and Windows Server 2003: This functionality is not supported.

[<23> Section 2.1.1.17:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<24> Section 2.1.1.26:](#) In Windows implementations, the PostScript printer driver uses a default line join style of **PostScriptFlatCap**.

[<25> Section 2.1.1.28:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows 98, and Windows Millennium Edition: This functionality is not supported.

[<26> Section 2.1.1.28:](#) Windows NT 4.0 and Windows 2000: This functionality is not supported.

[<27> Section 2.1.1.28:](#) Windows NT 4.0 and Windows 2000: This functionality is not supported.

[<28> Section 2.1.1.29:](#) In Windows implementations, the PostScript printer driver uses a default line join style of **PostScriptMiterJoin**.

[<29> Section 2.1.1.30:](#) Windows 95 and Windows 98: The symbolic name "STRETCH\_ANDSCANS" is synonymous with this value.

[<30> Section 2.1.1.30:](#) Windows 95 and Windows 98: The symbolic name "STRETCH\_ORSCANS" is synonymous with this value.

[<31> Section 2.1.1.30:](#) Windows 95 and Windows 98: The symbolic name "STRETCH\_DELETESCANS" is synonymous with this value.

[<32> Section 2.1.1.30:](#) Windows 95 and Windows 98: The symbolic name "STRETCH\_HALFTONE" is synonymous with this value.

[<33> Section 2.1.2.1:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows NT 4.0, Windows 2000, and Windows XP: This value is always returned when enumerating fonts.

[<34> Section 2.1.2.1:](#) This value is ignored in the following Windows versions:



- Windows Vista
- Windows Server 2008
- Windows 7
- Windows Server 2008 R2

[<35> Section 2.1.2.1:](#) This value is not supported in Windows 95, Windows 98, and Windows Millennium Edition.

Font association is turned off in Windows 2000, Windows XP, and Windows Server 2003.

This value is ignored in these Windows versions:

- Windows Vista
- Windows Server 2008
- Windows 7
- Windows Server 2008 R2

[<36> Section 2.1.2.2:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This function is not supported.

[<37> Section 2.1.2.2:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This function is not supported.

[<38> Section 2.1.2.2:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This function is not supported.

[<39> Section 2.1.2.2:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This function is not supported.

[<40> Section 2.1.2.2:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, Windows NT 4.0, Windows 98, and Windows Millennium Edition: This function is not supported.

[<41> Section 2.1.2.3:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This function is not supported.

[<42> Section 2.2.1.2:](#) All Windows versions: Mapping the logical font size to the available physical fonts occurs the first time the logical font needs to be used in a drawing operation.

For the MM\_TEXT mapping mode, the following formula can be used to compute the height of a font with a specified point size.

```
Height = -MulDiv(PointSize, GetDeviceCaps(hdc, LOGPIXELSY), 72);
```

[<43> Section 2.2.1.5:](#) Windows sets this field to 0x0000.

[<44> Section 2.2.1.5:](#) Windows sets this field to an arbitrary value.

[<45> Section 2.2.2.2:](#) Although Windows processes [BitmapCoreHeader](#) objects in DIBs, it does not write them to WMF metafiles

<46> [Section 2.2.2.3](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: Neither JPEG nor PNG format is supported.

<47> [Section 2.2.2.3](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: Neither JPEG nor PNG format is supported.

<48> [Section 2.2.2.3](#): Windows implementations might write a nonzero value to this field, but it is ignored when the metafile is parsed.

<49> [Section 2.2.2.4](#): Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51: This structure is not supported.

<50> [Section 2.2.2.5](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This structure is not supported.

<51> [Section 2.2.2.10](#): In Windows implementations, **BS\_HOLLOW** was added as a duplicate symbolic name for **BS\_NULL**, because **BS\_NULL** was too easily mistaken for a NULL pointer.

**BS\_HOLLOW** is used by an application when GDI requires a non-NULL brush parameter but the application requires that no brush be used.

<52> [Section 2.2.2.10](#): In the following Windows versions, a solid-color black brush is created by default when a **BrushHatch** value of BS\_PATTERN or BS\_DIBPATTERNPT is present:

- Windows Vista
- Windows Server 2008
- Windows 7
- Windows Server 2008 R2

The behavior on other versions of Windows is undefined.

<53> [Section 2.3.1.4](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This format is not supported.

<54> [Section 2.3.1.4](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This format is not supported.

<55> [Section 2.3.1.6](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This format is not supported.

<56> [Section 2.3.1.6](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, Windows 95, and Windows NT 4.0: This format is not supported.

<57> [Section 2.3.2.2](#): Metafiles created by Windows contain the value **METAVERSION300**.

<58> [Section 2.3.2.3](#): Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, and Windows 95: This feature is not supported.

<59> [Section 2.3.4.1](#): In the following versions of Windows, a solid-color black brush is created by default, when a **BrushHatch** value of BS\_PATTERN or BS\_DIBPATTERNPT is present:

- Windows Vista
- Windows Server 2008

- Windows 7
- Windows Server 2008 R2

The behavior on other versions of Windows is undefined.

[<60> Section 2.3.5.15:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51 implementations do not write this field to WMF metafiles.

[<61> Section 2.3.5.16:](#) Windows NT 3.1, Windows NT 3.5, Windows NT 3.51, and Windows NT 4.0 implementations do not support this record type.

[<62> Section 2.3.5.20:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51 implementations do not write this field to WMF metafiles.

[<63> Section 2.3.5.22:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51 implementations do not write this field to WMF metafiles.

[<64> Section 2.3.5.23:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51 implementations do not write this field to WMF metafiles.

[<65> Section 2.3.5.24:](#) Windows NT 3.1, Windows NT 3.5, and Windows NT 3.51 implementations do not write this field to WMF metafiles.

[<66> Section 2.3.6.6:](#) Windows 95, Windows 98, and Windows Millennium Edition implementations set this field to the fill mode value (section [2.1.1.25](#)).

[<67> Section 2.3.6.11:](#) Any bytes that exceed the ByteCount field MUST be ignored by the client.

[<68> Section 2.3.6.25:](#) Windows does not check this value.

[<69> Section 3.1.5:](#) Windows applications use the Graphics Device Interface (GDI) to obtain a **device context** for performing output to a device. When the device context is created, the default values for graphics objects and properties are set up by the system and the driver for the device.

## 6 Change Tracking

This section identifies changes that were made to the [MS-WMF] protocol document between the May 2011 and June 2011 releases. Changes are classified as New, Major, Minor, Editorial, or No change.

The revision class **New** means that a new document is being released.

The revision class **Major** means that the technical content in the document was significantly revised. Major changes affect protocol interoperability or implementation. Examples of major changes are:

- A document revision that incorporates changes to interoperability requirements or functionality.
- An extensive rewrite, addition, or deletion of major portions of content.
- The removal of a document from the documentation set.
- Changes made for template compliance.

The revision class **Minor** means that the meaning of the technical content was clarified. Minor changes do not affect protocol interoperability or implementation. Examples of minor changes are updates to clarify ambiguity at the sentence, paragraph, or table level.

The revision class **Editorial** means that the language and formatting in the technical content was changed. Editorial changes apply to grammatical, formatting, and style issues.

The revision class **No change** means that no new technical or language changes were introduced. The technical content of the document is identical to the last released version, but minor editorial and formatting changes, as well as updates to the header and footer information, and to the revision summary, may have been made.

Major and minor changes can be described further using the following change types:

- New content added.
- Content updated.
- Content removed.
- New product behavior note added.
- Product behavior note updated.
- Product behavior note removed.
- New protocol syntax added.
- Protocol syntax updated.
- Protocol syntax removed.
- New content added due to protocol revision.
- Content updated due to protocol revision.
- Content removed due to protocol revision.
- New protocol syntax added due to protocol revision.

- Protocol syntax updated due to protocol revision.
- Protocol syntax removed due to protocol revision.
- New content added for template compliance.
- Content updated for template compliance.
- Content removed for template compliance.
- Obsolete document removed.

Editorial changes are always classified with the change type **Editorially updated**.

Some important terms used in the change type descriptions are defined as follows:

- **Protocol syntax** refers to data elements (such as packets, structures, enumerations, and methods) as well as interfaces.
- **Protocol revision** refers to changes made to a protocol that affect the bits that are sent over the wire.

The changes made to this document are listed in the following table. For more information, please contact [protocol@microsoft.com](mailto:protocol@microsoft.com).

| Section   | Tracking number (if applicable) and description   | Major change (Y or N) | Change type      |
|---|---|-----------------------|------------------|
| <a href="#">1.1 Glossary</a>                    | Removed "color temperature", "device space", "terminal server" and "terminal services" from document-specific glossary list. Removed "Remote Desktop Protocol" from list of [MS-GLOS] terms. Changed "gamma" to "gamma correction" in the definition of "Portable Network Graphics". Revised the definitions of "color correction", "color space", "gamma", and "mapping mode". | Y                     | Content updated. |
| <a href="#">1.2 References</a>                  | Added explanatory statement regarding the removal of the publishing year from Microsoft Open Specification document references.   | N                     | Content updated. |
| <a href="#">2.1.1.1 RecordType Enumeration</a>  | Revised the description of META_SETMAPMODE to remove the term "device space".   | N                     | Content updated. |
| <a href="#">2.1.1.7 Compression Enumeration</a> | Changed "Joint Photographic Experts Group" to "JPEG" and "Portable Network Graphics" to "PNG".  | Y                     | Content updated. |

## 7 Index

### A

[ABORTDOC packet](#) 168  
[ABORTDOC Record](#) 168  
[Applicability](#) 18

### B

[BEGIN\\_PATH packet](#) 169  
[BEGIN\\_PATH Record](#) 169  
[BinaryRasterOperation enumeration](#) 24  
[BitCount enumeration](#) 28  
[Bitmap Record Types](#) 107  
[Bitmap16 Object](#) 88  
[Bitmap16 packet](#) 88  
[BitmapCoreHeader Object](#) 89  
[BitmapCoreHeader packet](#) 89  
[BitmapInfoHeader Object](#) 90  
[BitmapInfoHeader packet](#) 90  
[BitmapV4Header Object](#) 91  
[BitmapV4Header packet](#) 91  
[BitmapV5Header Object](#) 94  
[BitmapV5Header packet](#) 94  
[Brush Object](#) 83  
[Brush packet](#) 83  
[BrushStyle enumeration](#) 29  
[Byte ordering](#) 17

### C

[Change tracking](#) 220  
[CharacterSet enumeration](#) 30  
[CHECK\\_JPEGFORMAT packet](#) 169  
[CHECK\\_JPEGFORMAT Record](#) 169  
[CHECK\\_PNGFORMAT packet](#) 170  
[CHECK\\_PNGFORMAT Record](#) 170  
[CIEXYZ Object](#) 95  
[CIEXYZ packet](#) 95  
[CIEXYZTriple Object](#) 95  
[CIEXYZTriple packet](#) 95  
[CLIP\\_CHARACTER\\_PRECIS](#) 80  
[CLIP\\_DEFAULT\\_PRECIS](#) 80  
[CLIP\\_DFA\\_DISABLE](#) 80  
[CLIP\\_EMBEDDED](#) 80  
[CLIP\\_LH\\_ANGLES](#) 80  
[CLIP\\_STROKE\\_PRECIS](#) 80  
[CLIP\\_TO\\_PATH packet](#) 171  
[CLIP\\_TO\\_PATH Record](#) 171  
[CLIP\\_TT\\_ALWAYS](#) 80  
[CLOSE\\_CHANNEL packet](#) 171  
[CLOSE\\_CHANNEL Record](#) 171  
[ColorRef Object](#) 96  
[ColorRef packet](#) 96  
[ColorUsage enumeration](#) 31  
[Compression enumeration](#) 32  
[Control Record Types](#) 121

### D

[DeviceIndependentBitmap Object](#) 96  
[DeviceIndependentBitmap packet](#) 96  
[DOWNLOAD\\_FACE packet](#) 172  
[DOWNLOAD\\_FACE Record](#) 172  
[DOWNLOAD\\_HEADER packet](#) 173  
[DOWNLOAD\\_HEADER Record](#) 173  
[DRAW\\_PATTERNRECT packet](#) 173  
[DRAW\\_PATTERNRECT Record](#) 173  
[Drawing Record Types](#) 123

### E

[ENCAPSULATED\\_POSTSCRIPT packet](#) 174  
[ENCAPSULATED\\_POSTSCRIPT Record](#) 174  
[END\\_PATH packet](#) 175  
[END\\_PATH Record](#) 175  
[ENDDOC packet](#) 176  
[ENDDOC Record](#) 176  
[Enumerations](#) 19  
[EPS\\_PRINTING packet](#) 176  
[EPS\\_PRINTING Record](#) 176  
[Escape Record Types](#) 165  
[ETO\\_CLIPPED](#) 80  
[ETO\\_GLYPH\\_INDEX](#) 80  
[ETO\\_NUMERICSLATIN](#) 80  
[ETO\\_NUMERICSLocal](#) 80  
[ETO\\_OPAQUE](#) 80  
[ETO\\_PDY](#) 80  
[ETO\\_RTLREADING](#) 80

#### Examples

[metafile design example](#) 197  
[metafile example](#) 206  
[EXTTEXTOUT packet](#) 177  
[EXTTEXTOUT Record](#) 177

### F

[FamilyFont enumeration](#) 33  
[Fields - vendor-extensible](#) 18  
[Fixed-length record objects](#) 83  
[FloodFill enumeration](#) 33  
[Font Object](#) 84  
[Font packet](#) 84  
[FontQuality enumeration](#) 34

### G

[GamutMappingIntent enumeration](#) 34  
[GET\\_COLORTABLE packet](#) 177  
[GET\\_COLORTABLE Record](#) 177  
[GET\\_DEVICEUNITS packet](#) 179  
[GET\\_DEVICEUNITS Record](#) 179  
[GET\\_EXTENDED\\_TEXTMETRICS packet](#) 179  
[GET\\_EXTENDED\\_TEXTMETRICS Record](#) 179  
[GET\\_FACENAME packet](#) 180  
[GET\\_FACENAME Record](#) 180  
[GET\\_PAIRKERNTABLE packet](#) 180  
[GET\\_PAIRKERNTABLE Record](#) 180

[GET\\_PHYSPAGESIZE packet](#) 181  
[GET\\_PHYSPAGESIZE Record](#) 181  
[GET\\_PRINTINGOFFSET packet](#) 181  
[GET\\_PRINTINGOFFSET Record](#) 181  
[GET\\_PS\\_FEATURESETTING packet](#) 182  
[GET\\_PS\\_FEATURESETTING Record](#) 182  
[GET\\_SCALINGFACTOR packet](#) 182  
[GET\\_SCALINGFACTOR Record](#) 182  
[Glossary](#) 9  
[Graphics objects](#) 17

## H

[HatchStyle enumeration](#) 35

## I

[Informative references](#) 15

[Introduction](#) 9

## L

[Layout enumeration](#) 36  
[Localization](#) 18  
[LogBrush Object](#) 97  
[LogBrush packet](#) 97  
[LogColorSpace Object](#) 98  
[LogColorSpace packet](#) 98  
[LogColorSpaceW Object](#) 100  
[LogColorSpaceW packet](#) 100  
[LogicalColorSpace enumeration](#) 36  
[LogicalColorSpaceV5 enumeration](#) 36

## M

Managing objects

[object scaling](#) 199

[object table](#) 199

[MapMode enumeration](#) 37

[META\\_ANIMATEPALETTE packet](#) 149

[META\\_ANIMATEPALETTE Record](#) 149

[META\\_ARC packet](#) 124

[META\\_ARC Record](#) 124

[META\\_BITBLT packet](#) 109

[META\\_BITBLT Record](#) 108

[META\\_BITBLT Bitmap packet](#) 109

[META\\_CHORD packet](#) 125

[META\\_CHORD Record](#) 125

[META\\_CREATEBRUSHINDIRECT packet](#) 139

[META\\_CREATEBRUSHINDIRECT Record](#) 139

[META\\_CREATEFONTINDIRECT packet](#) 140

[META\\_CREATEFONTINDIRECT Record](#) 140

[META\\_CREATEPALETTE packet](#) 141

[META\\_CREATEPALETTE Record](#) 141

[META\\_CREATEPATTERNBRUSH packet](#) 141

[META\\_CREATEPATTERNBRUSH Record](#) 141

[META\\_CREATEPENINDIRECT packet](#) 143

[META\\_CREATEPENINDIRECT Record](#) 143

[META\\_CREATEREGION packet](#) 143

[META\\_CREATEREGION Record](#) 143

[META\\_DELETEOBJECT packet](#) 144

[META\\_DELETEOBJECT Record](#) 144

[META\\_DIBBITBLT packet](#) 112

[META\\_DIBBITBLT Record](#) 110

[META\\_DIBBITBLT Bitmap packet](#) 111

[META\\_DIBCREATEPATTERNBRUSH packet](#) 144

[META\\_DIBCREATEPATTERNBRUSH Record](#) 144

[META\\_DIBSTRETCHBLT packet](#) 114

[META\\_DIBSTRETCHBLT Record](#) 112

[META\\_DIBSTRETCHBLT Bitmap packet](#) 113

[META\\_ELLIPSE packet](#) 126

[META\\_ELLIPSE Record](#) 126

[META\\_EOF Record](#) 121

[META\\_EOF Record packet](#) 121

[META\\_ESCAPE packet](#) 168

[META\\_ESCAPE Record](#) 168

[META\\_ESCAPE\\_ENHANCED METAFILE packet](#) 183

[META\\_ESCAPE\\_ENHANCED METAFILE Record](#) 183

[META\\_EXCLUDECLIPRECT packet](#) 149

[META\\_EXCLUDECLIPRECT Record](#) 149

[META\\_EXTFLOODFILL packet](#) 127

[META\\_EXTFLOODFILL Record](#) 127

[META\\_EXTTEXTOUT packet](#) 127

[META\\_EXTTEXTOUT Record](#) 127

[META\\_FILLREGION packet](#) 128

[META\\_FILLREGION Record](#) 128

[META\\_FLOODFILL packet](#) 129

[META\\_FLOODFILL Record](#) 129

[META\\_FRAMEREGION packet](#) 130

[META\\_FRAMEREGION Record](#) 130

[META\\_HEADER packet](#) 121

[META\\_HEADER Record](#) 121

[META\\_INTERSECTCLIPRECT packet](#) 150

[META\\_INTERSECTCLIPRECT Record](#) 150

[META\\_INVERTREGION packet](#) 130

[META\\_INVERTREGION Record](#) 130

[META\\_LINETO packet](#) 131

[META\\_LINETO Record](#) 131

[META\\_MOVETO packet](#) 151

[META\\_MOVETO Record](#) 151

[META\\_OFFSETCLIPRGN packet](#) 151

[META\\_OFFSETCLIPRGN Record](#) 151

[META\\_OFFSETVIEWPORTORG packet](#) 152

[META\\_OFFSETVIEWPORTORG Record](#) 152

[META\\_OFFSETWINDOWORG packet](#) 152

[META\\_OFFSETWINDOWORG Record](#) 152

[META\\_PAINTREGION packet](#) 132

[META\\_PAINTREGION Record](#) 132

[META\\_PATBLT packet](#) 132

[META\\_PATBLT Record](#) 132

[META\\_PIE packet](#) 133

[META\\_PIE Record](#) 133

[META\\_PLACEABLE packet](#) 122

[META\\_PLACEABLE Record](#) 122

[META\\_POLYGON packet](#) 134

[META\\_POLYGON Record](#) 134

[META\\_POLYLINE packet](#) 134

[META\\_POLYLINE Record](#) 134

[META\\_POLYPOLYGON packet](#) 135

[META\\_POLYPOLYGON Record](#) 135

[META\\_REALIZEPALETTE packet](#) 153

[META\\_REALIZEPALETTE Record](#) 153

[META\\_RECTANGLE packet](#) 136

- [META\\_RECTANGLE Record](#) 136
- [META\\_RESIZEPALETTE packet](#) 153
- [META\\_RESIZEPALETTE Record](#) 153
- [META\\_RESTOREDC packet](#) 153
- [META\\_RESTOREDC Record](#) 153
- [META\\_ROUNDRECT packet](#) 136
- [META\\_ROUNDRECT Record](#) 136
- [META\\_SAVEDC packet](#) 154
- [META\\_SAVEDC Record](#) 154
- [META\\_SCALEVIEWPORTEXT packet](#) 154
- [META\\_SCALEVIEWPORTEXT Record](#) 154
- [META\\_SCALEWINDOWEXT packet](#) 155
- [META\\_SCALEWINDOWEXT Record](#) 155
- [META\\_SELECTCLIPREGION packet](#) 145
- [META\\_SELECTCLIPREGION Record](#) 145
- [META\\_SELECTOBJECT packet](#) 146
- [META\\_SELECTOBJECT Record](#) 146
- [META\\_SELECTPALETTE packet](#) 146
- [META\\_SELECTPALETTE Record](#) 146
- [META\\_SETBKCOLOR packet](#) 156
- [META\\_SETBKCOLOR Record](#) 156
- [META\\_SETBKMODE packet](#) 156
- [META\\_SETBKMODE Record](#) 156
- [META\\_SETDIBTODEV packet](#) 115
- [META\\_SETDIBTODEV Record](#) 115
- [META\\_SETLAYOUT packet](#) 157
- [META\\_SETLAYOUT Record](#) 157
- [META\\_SETMAPMODE packet](#) 157
- [META\\_SETMAPMODE Record](#) 157
- [META\\_SETMAPPERFLAGS packet](#) 158
- [META\\_SETMAPPERFLAGS Record](#) 158
- [META\\_SETPALENTRIES packet](#) 158
- [META\\_SETPALENTRIES Record](#) 158
- [META\\_SETPIXEL packet](#) 137
- [META\\_SETPIXEL Record](#) 137
- [META\\_SETPOLYFILLMODE packet](#) 159
- [META\\_SETPOLYFILLMODE Record](#) 159
- [META\\_SETRELABS packet](#) 160
- [META\\_SETRELABS Record](#) 160
- [META\\_SETROP2 packet](#) 160
- [META\\_SETROP2 Record](#) 160
- [META\\_SETSTRETCHBLTMODE packet](#) 161
- [META\\_SETSTRETCHBLTMODE Record](#) 161
- [META\\_SETTEXTALIGN packet](#) 161
- [META\\_SETTEXTALIGN Record](#) 161
- [META\\_SETTEXTCHAREXTRA packet](#) 162
- [META\\_SETTEXTCHAREXTRA Record](#) 162
- [META\\_SETTEXTCOLOR packet](#) 162
- [META\\_SETTEXTCOLOR Record](#) 162
- [META\\_SETTEXTJUSTIFICATION packet](#) 163
- [META\\_SETTEXTJUSTIFICATION Record](#) 163
- [META\\_SETVIEWPORTEXT packet](#) 163
- [META\\_SETVIEWPORTEXT Record](#) 163
- [META\\_SETVIEWPORTORG packet](#) 164
- [META\\_SETVIEWPORTORG Record](#) 164
- [META\\_SETWINDOWEXT packet](#) 164
- [META\\_SETWINDOWEXT Record](#) 164
- [META\\_SETWINDOWORG packet](#) 165
- [META\\_SETWINDOWORG Record](#) 165
- [META\\_STRETCHBLT packet](#) 118
- [META\\_STRETCHBLT Record](#) 116

- [META\\_STRETCHBLT Bitmap packet](#) 117
- [META\\_STRETCHDIB packet](#) 119
- [META\\_STRETCHDIB Record](#) 119
- [META\\_TEXTOUT packet](#) 138
- [META\\_TEXTOUT Record](#) 138
- [Metafile design example](#) 197
- Metafile example
  - [header](#) 206
  - [META\\_CREATEBRUSHINDIRECT](#) 209
  - [META\\_CREATEPENINDIRECT](#) 207
  - [META\\_EOF Example](#) 212
  - [META\\_RECTANGLE](#) 210
  - [META\\_SELECTOBJECT](#) ([section 3.2.3](#) 208, [section 3.2.5](#) 210)
  - [META\\_TEXTOUT](#) 211
  - [overview](#) 206
- Metafile structure 16
- [METAFILE\\_DRIVER packet](#) 185
- [METAFILE\\_DRIVER Record](#) 185
- [MetafileEscapes enumeration](#) 38
- [MetafileType enumeration](#) 41
- [MetafileVersion enumeration](#) 42
- [MixMode enumeration](#) 42

## N

- [NEWFRAME packet](#) 185
- [NEWFRAME Record](#) 185
- [NEXTBAND packet](#) 186
- [NEXTBAND Record](#) 186
- [Normative references](#) 15

## O

- [Object Record Types](#) 138
- [Objects](#) 82
- [OPEN\\_CHANNEL packet](#) 190
- [OPEN\\_CHANNEL Record](#) 190
- [OutPrecision enumeration](#) 42
- [Overview \(synopsis\)](#) 16

## P

- [Palette Object](#) 86
- [Palette packet](#) 86
- [PaletteEntry Object](#) 102
- [PaletteEntry Object packet](#) 102
- [PaletteEntryFlag enumeration](#) 43
- [PASSTHROUGH packet](#) 186
- [PASSTHROUGH Record](#) 186
- [Pen Object](#) 87
- [Pen packet](#) 87
- [PenStyle enumeration](#) 44
- [PitchAndFamily Object](#) 102
- [PitchAndFamily packet](#) 102
- [PitchFont enumeration](#) 45
- [PointL Object](#) 103
- [PointL packet](#) 103
- [PointS Object](#) 103
- [PointS packet](#) 103
- [PolyFillMode enumeration](#) 45
- [PolyPolygon Object](#) 103



- [PolyPolygon packet](#) 103
- [POSTSCRIPT DATA packet](#) 187
- [POSTSCRIPT DATA Record](#) 187
- [POSTSCRIPT IDENTIFY packet](#) 187
- [POSTSCRIPT IDENTIFY Record](#) 187
- [POSTSCRIPT IGNORE packet](#) 188
- [POSTSCRIPT IGNORE Record](#) 188
- [POSTSCRIPT INJECTION packet](#) 189
- [POSTSCRIPT INJECTION Record](#) 189
- [POSTSCRIPT PASSTHROUGH packet](#) 189
- [POSTSCRIPT PASSTHROUGH Record](#) 189
- [PostScriptCap enumeration](#) 46
- [PostScriptClipping enumeration](#) 46
- [PostScriptFeatureSetting enumeration](#) 46
- [PostScriptJoin enumeration](#) 47
- [Product behavior](#) 214

## Q

- [QUERY DIBSUPPORT packet](#) 190
- [QUERY DIBSUPPORT Record](#) 190
- [QUERY ESCSUPPORT packet](#) 191
- [QUERY ESCSUPPORT Record](#) 191

## R

- [Record objects - fixed-length](#) 83
- [Record objects - variable-length](#) 88
- [Records](#) 106
  - [enumerations](#) 19
  - [fixed-length record objects](#) 83
  - types ([section 2.3.1.1](#) 108, [section 2.3.1.2](#) 110, [section 2.3.1.3](#) 112, [section 2.3.1.5](#) 116)
  - [variable-length record objects](#) 88
- [RecordType enumeration](#) 19
- [Rect Object](#) 104
- [Rect packet](#) 104
- [RectL Object](#) 104
- [RectL packet](#) 104
- References
  - [informative](#) 15
  - [normative](#) 15
- [Region Object](#) 87
- [Region packet](#) 87
- [Relationship to protocols and other structures](#) 18
- [RGBQuad Object](#) 105
- [RGBQuad packet](#) 105

## S

- [Scan Object](#) 105
- [Scan packet](#) 105
- [Security](#) 213
- [SET COLORTABLE packet](#) 192
- [SET COLORTABLE Record](#) 192
- [SET COPYCOUNT packet](#) 192
- [SET COPYCOUNT Record](#) 192
- [SET LINECAP packet](#) 193
- [SET LINECAP Record](#) 193
- [SET LINEJOIN packet](#) 194
- [SET LINEJOIN Record](#) 194
- [SET MITERLIMIT packet](#) 194

- [SET MITERLIMIT Record](#) 194
- [SizeL Object](#) 106
- [SizeL packet](#) 106
- [SPCLPASSTHROUGH2 packet](#) 195
- [SPCLPASSTHROUGH2 Record](#) 195
- [STARTDOC packet](#) 196
- [STARTDOC Record](#) 196
- [State record types](#) 147
- [StretchMode enumeration](#) 48

## Structures

- [examples](#) 197
- [overview](#) 19

## T

- [TA BASELINE](#) 81
- [TA BOTTOM](#) 81
- [TA CENTER](#) 81
- [TA LEFT](#) 81
- [TA NOUPDATECP](#) 81
- [TA RIGHT](#) 81
- [TA RTLREADING](#) 81
- [TA TOP](#) 81
- [TA UPDATECP](#) 81
- [TernaryRasterOperation enumeration](#) 48
- [Tracking changes](#) 220

## V

- [Variable-length record objects](#) 88
- [Vendor-extensible fields](#) 18
- [Versioning](#) 18
- [VTA BASELINE](#) 82
- [VTA BOTTOM](#) 82
- [VTA CENTER](#) 82
- [VTA LEFT](#) 82
- [VTA RIGHT](#) 82
- [VTA TOP](#) 82

## W

- [WMF Records packet](#) 106